

September 13, 2019

Morgan Will, Development Manager Stafford Land Co. 8840 SW Holly Lane Wilsonville, OR 97070-9800

RE: Approval of Grading Permit GRAD 2019-08 "Smith Creek Development: Phase 1B" (Parcel 2, Partition Plat 2018-065; Tax Lot 052W13 00105); Accela record no. 971-19-000146-PLNG.

Dear Mr. Will:

Following original submittal of the grading permit application on August 29, 2019, staff approves the permit with the following conditions:

Planning Conditions of Approval:

- Conformance with Approved Plans: All site work shall be in substantial conformance with the grading plans received August 29, 2019, which cover the Phase 1B subarea of the subject property. (The remaining area would be Phases 3A & 4A and subject to separate grading approval.)
- 2. DEQ: All development activity shall be in accordance with the approved Department of Environmental Quality (DEQ) 1200-C permit 33148 dated May 31, 2019 and any Erosion and Sediment Control Plan (ESCP) revisions under section 12c (pp 12-14) of that permit. The applicant shall provide to the City any modifications to the DEQ permit.
- 3. Other agencies: The applicant, not the City, is responsible for obtaining permits from the US Army Corps of Engineers (USACE), Oregon Department of State Lands (DSL), Oregon Department of Transportation (ODOT), and other agencies which might require approval or permit.
- 4. ROW: All work within public rights-of-way (ROWs) or easements within City jurisdiction shall require plan approval and permit issuance from the Public Works Department.

- 5. Access: The applicant shall follow Public Works Department direction regarding construction access.
- 6. Trees: Grading excludes approval to remove any trees. Regarding tree removal from private property, see WDO 1.02 "caliper" & "Significant Tree", Figure 1.02C, 3.06.07 Significant Trees on Private Property, and 5.01.11 Significant Tree Removal Permit.

Public Works Conditions of Approval:

The applicant shall:

- 7. Comply with the submitted grading plan (Sheet 7) and erosion control plan sheets relevant to Phase 1B (Sheets EC1, 2, 4, 6 7); including measures to keep the ROW clean and to protect existing catch basins around the work area. All catch basins around the work area shall be clean of debris and soils at all times.
- 8. Continuously maintain adequate protection of all the work from damage and shall protect the public and private property of others from injury or loss arising in connection with the work.
- 9. Comply with City of Woodburn Planning Department requirements through <u>Woodburn</u> Development Ordinance (WDO) 5.01.04 Grading Permit.
- 10. Prior to starting work, contact the Public Works Department for inspection of the erosion control in the public ROW. Contact the Engineering Division at (503) 982-5240.

Background

The property owner through Stafford Land Company and Ordinance No. 2565 (2018) annexed territory including the subject property and obtained approval of a planned unit development (PUD), preliminary subdivision, and ancillary applications for the Smith Creek Development via the Final Order of November 14, 2018. The project is split into nine phases; the grading plans are limited to Phase 1B.

Context

This grading permit in no way abrogates or supersedes any conditions of approval in the Smith Creek Development Final Order of November 14, 2018.

Summary of Review:

This site is subject to the development standards of the Woodburn Development Ordinance. The applicant is requesting to grade the site in preparation for the installation of public improvements including utilities, streets, and stormwater management facilities relating to Phase 1B of the

Smith Creek Development, which is the phase that includes the new Kirksey Street connecting Ben Brown Lane in Phase 1A south to Parr Road that is the site development area boundary.

Pursuant to WDO 4.01.02, The Director shall render all Type I land use decisions. The Director's decision is the final decision of the City on a Type I application and cannot be appealed by any party through the City land use appeals process. If you have any questions regarding this matter, contact Chris Kerr, Community Development Director chris.kerr@ci.woodburn.or.us or (503) 980-2445.

Final decision approved by designee:

Colin Cortes

Colin Cortes, AICP, CNU-A, Senior Planner

September 13, 2019

Enclosures (4):

- 1. Marked Tax Map
- 2. Applicant e-mail about how the DEQ Permit applies to Ph. 1B (Sept. 6, 2019)
- 3. DEQ 1200-C Permit 33148 (abridged and highlighted)
- 4. Application Form
- 5. Approved Plans (Sheets 7 and EC1, 2, 4, 6, & 7)
- 6. Smith Creek Development Exhibits C-4 & Y-1

cc: Chris Kerr, AICP Community Development Director
Dan Handel, AICP, Associate Planner
Dago Garcia, P.E., City Engineer

file(s): GRAD 2019-08

Accela record no. 971-19-000146-PLNG



Colin Cortes

From: Morgan Will <morgan@staffordlandcompany.com>

Sent: Friday, September 06, 2019 3:23 PM

To: Colin Cortes

Cc: Chris Kerr; Eric Liljequist; Dago Garcia

Subject: RE: Smith Creek - Phase 1B, Phase 2B, & Phase 2C Grading Permits & ESC

Attachments: 1200-C_Phase 1a_20190513.pdf

This email is from an external sender.

Colin,

Roy resent the attached map to Chris earlier today. It is attached here again. The City already had it as part of all the previous Phase 1A submittals. You'll see it as Sheets EC1-EC7, which are pages 57-63 of the PDF set of the civil plan submittal, right after page 56 of the 56 civil sheets.

Because there were many land divisions and lot line adjustment applications in process at the time of the application to DEQ for the 1200-C permit, the application form we provided to DEQ did not have separate and distinct mailing address nor County tax lot numbers to write on the application form for these phases, so we used the best information available which was the address of the land before all this started. That should explain that issue for you.

The area intended for permit activity is clearly shown on the approved plans, so there should be no question about what portions of the site are approved for construction. You can see that by the limits of construction. Again, those areas include all of phases 1A, 1B, 2A, 2B, and 2C.

Within the limits of the inactive stock pile areas and the active area are shown. As we expand the active area within the limits of construction with initiation of additional phases of construction, the Permittee's Inspector (see sheet EC1) may suggest additional or changes to the Best Management Practices. The DEQ permit is a living map, and that is the Permittee's Inspector's job to maintain throughout the life of the project. In this case the BMP between the resource areas and active and inactive areas are the same as shown on the plan. Our Inspector has requested no additional changes to what is shown.

The measures in place under the inspector provide BMP and will adjust as needed as work progresses.

It is totally normal to have a permit cover a larger area and expand and contract the active area as a project's phases move.

I hope this helps you get to the finish line.

Best,

Morgan Will

Development Manager, Acquisitions & Development Stafford Development Company, LLC



Office: (503) 305-7647 ext. 203

Direct: (971) 206-8615 Mobile: (503) 939-3902

Email: morgan@staffordlandcompany.com

WE MOVED:

NEW: 8840 SW Holly Lane, Wilsonville, OR 97070

www.staffordlandcompany.com











From: Colin Cortes <Colin.Cortes@ci.woodburn.or.us>

Sent: Friday, September 6, 2019 2:50 PM

To: Morgan Will <morgan@staffordlandcompany.com>

Cc: Chris Kerr < Chris.Kerr@ci.woodburn.or.us>; Eric Liljequist < Eric.Liljequist@ci.woodburn.or.us>; Dago Garcia

<Dago.Garcia@ci.woodburn.or.us>

Subject: RE: Smith Creek - Phase 1B, Phase 2B, & Phase 2C Grading Permits & ESC

Morgan:

Staff needs additional info for the Smith Creek Development grading permit apps for Phases 1B, 2B, & 2C (GRAD 2019-08, 9, & 10 respectively).

The e-mail I reply to made explicit that you are applying the approved DEQ NPDES 1200-C permit 126319 from Phase 1A GRAD 2019-05 towards the three additional grading permit apps. Attached is a copy I abridged and highlighted.

The concern is that the permit document has no drawings or maps and one short location identifier as excerpted below, "Location: Smith Creek Development - Phase 1a, West Of 105 Ben Brown Lane, Woodburn", which seems to limit it to Phase 1A.

Expiration Date: December 14, 2020

Page 1 of 30



GENERAL PERMIT NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM STORMWATER DISCHARGE PERMIT

Oregon Department of Environmental Quality 811 SW Sixth Avenue, Portland OR 97204

Telephone: (503) 229-5279 or 1-800-452-4011 (toll free in Oregon)

Issued pursuant to ORS 468B.050 and Section 402 of the Federal Clean Water Act

REGISTERED TO: File No: 126319 Date: May 31, 2019 Permit No: 33148 Marion County Stafford Development Company, LLC EPA: ORR10F719 8840 SW Holly Ln LLID: 1228535451394

Wilsonville, OR 97070-9800 River Mile: 0.670000000000000004

Location: Smith Creek Development - Phase 1a, West Of 105 Ben Brown Lane, Woodburn

SOURCES COVERED BY THIS PERMIT:

The legally authorized representative (see Definitions) for construction activities (as defined below) that may discharge to surface waters or conveyance systems leading to surface waters of the state must register for coverage under this permit with DEQ before any land disturbance occurs, unless the construction activities are automatically covered as described in the 1200-CN permit.

I called and spoke with two DEQ reps. In short, they explained that the permit can cover more or less territory as the applicant shifts coverage through p. 12, section 12. Erosion and Sediment Control Plan (ESCP), subsection c. ESCP Revisions. I learned also that the permit at present covers 78 and fraction acres of land. I know that at present Tax Lot 052W13 00108 is contiguous with Phase 1A and is 32.9 acres, which leaves me wondering how the remaining 45 and a fraction acres covers what other phases. I spoke also with the Community Development Director.

In short, please forward written and/or visual DEQ materials that make it clear to City staff that following DEQ permit issuance on May 31 the applicant had duly interacted with the agency to include Phases 1B, 2B, & 2C in the permit scope. Thanks for your understanding.

Colin Cortes, AICP, CNU-A

Senior Planner

City of Woodburn | Community Development Dept.

503-980-2485 direct

View the Woodburn Development Ordinance (WDO).

From: Morgan Will <morgan@staffordlandcompany.com>

Sent: Thursday, September 05, 2019 12:54 PM To: Colin Cortes <Colin.Cortes@ci.woodburn.or.us>

Subject: Smith Creek - Phase 1B, Phase 2B, & Phase 2C Grading Permits & ESC

This email is from an external sender.

Colin,

As requested by you in our meeting yesterday, this email is to document that the recently submitted grading permit applications for Phase 1B, Phase 2B, and Phase 2C have erosion and sediment control (ESC) managed under the existing DEQ 1200-C Permit No. 126319, provided to you on Wednesday, June 19, 2019 in support of Phase 1's Grading Permit (GRAD 2019-05), as this 1200-C permit area includes the territory of Phase 1B, Phase 2B, and Phase 2C in anticipation of continuation of grading activity outside of Phase 1A as proposed by these new grading permit applications.

We look forward to receiving City approval of these new grading permits soon.

Best,

Morgan Will

Development Manager, Acquisitions & Development Stafford Development Company, LLC



Office: (503) 305-7647 ext. 203

Direct: (971) 206-8615 Mobile: (503) 939-3902

Email: morgan@staffordlandcompany.com

WE MOVED:

NEW: 8840 SW Holly Lane, Wilsonville, OR 97070

www.staffordlandcompany.com











From: Morgan Will

Sent: Wednesday, June 19, 2019 5:07 PM

To: 'Colin Cortes' <Colin.Cortes@ci.woodburn.or.us>; Dago Garcia <Dago.Garcia@ci.woodburn.or.us>

PUBLIC RECORDS LAW DISCLOSURE This e-mail is a public record of the City of Woodburn and is subject to public disclosure unless exempt from disclosure under Oregon Public Records Law. This e-mail is subject to the State Retention Schedule.

Expiration Date: December 14, 2020

Page 1 of 30



GENERAL PERMIT NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM STORMWATER DISCHARGE PERMIT

Oregon Department of Environmental Quality 811 SW Sixth Avenue, Portland OR 97204 Telephone: (503) 229-5279 or 1-800-452-4011 (toll free in Oregon)

Issued pursuant to ORS 468B.050 and Section 402 of the Federal Clean Water Act

REGISTERED TO: File No: 126319Permit No: 33148

Stafford Development Company, LLC

8840 SW Holly Ln

Wilsonville, OR 97070-9800

Date: May 31, 2019

Marion County EPA: ORR10F719 LLID: 1228535451394

River Mile: 0.670000000000000004

Location: Smith Creek Development - Phase 1a, West Of 105 Ben Brown Lane, Woodburn

SOURCES COVERED BY THIS PERMIT:

The *legally authorized representative* (see Definitions) for construction activities (as defined below) that may discharge to surface waters or conveyance systems leading to surface waters of the state must register for coverage under this permit with DEQ before any land disturbance occurs, unless the construction activities are automatically covered as described in the 1200-CN permit.

- Construction activities including clearing, grading, excavation, materials or equipment staging and stockpiling that will disturb one or more acres and may discharge to surface waters or conveyance systems leading to surface waters of the state.
- Construction activities including clearing, grading, excavation, materials or equipment staging and stockpiling that will disturb less than one acre that are part of a common plan of development or sale if the larger common plan of development or sale will ultimately disturb one acre or more and may discharge to surface waters or conveyance systems leading to surface waters of the state.
- This permit also authorizes discharges from any other construction activity (including construction activity that disturbs less than one acre and is not part of a common plan of development or sale) designated by DEQ, where DEQ makes that designation based on the potential for contribution to an excursion of a water quality standard or for significant contribution of pollutants to waters of the state.

This permit does not authorize the following:

- In-water or riparian work, which is regulated by other programs and agencies including the Federal Clean Water Act Section 404 permit program, the Oregon Department of State Lands, the Oregon Department of Fish and Wildlife, the U.S. Fish and Wildlife Service, the U.S. Army Corp of Engineers, the National Marine Fisheries Service, and the Department of Environmental Quality Section 401 certification program.
- Post-construction stormwater discharges that originate from the site after completion of construction activities and final stabilization.
- Discharges to underground injection control (UIC) systems.

Effective: December 15, 2015

dia Emer, Operations Administrator Expiration Date: December 14, 2020

Expiration Date: December 14, 2020

Page 2 of 30

PERMITTED ACTIVITIES

Until this permit expires, is modified or revoked, the permit registrant is authorized to construct, install, modify, or operate erosion and sediment control measures and stormwater treatment and control facilities, and to discharge stormwater and certain specified non-stormwater discharges to surface waters of the state or conveyance systems leading to surface waters of the state only in conformance with all the requirements, limitations, and conditions set forth in the permit including attached schedules as follows:

Unless specifically authorized by this permit, by regulation issued by EPA, by another NPDES permit, or by Oregon Administrative Rule, any other direct or indirect discharge to waters of the state is prohibited, including discharges to an underground injection control system.

Expiration Date: December 14, 2020 Page 3 of 30

Table of Contents

SCHEI	DULE A CONTROLS AND LIMITATIONS	
1.	Registering New Construction Activities	4
2.	Renewal Application for Permit Coverage	4
3.	Transfer of Permit Registration	5
4.	Authorized Stormwater Discharges	5
5.	Authorized Non-Stormwater Discharges	5
6.	Prohibited Discharges	6
7.	Control Measures	6
8.	Implementation of Control Measures	9
9.	BMP Maintenance	11
10.	In-stream Water Quality Standards	11
11.	Water Quality Requirements for TMDL and 303(d) Listed Waterbodies	11
12.	Erosion and Sediment Control Plan (ESCP)	12
13.	Corrective Actions	
SCHEI	DULE B MINIMUM MONITORING AND RECORDKEEPING REQUIREMENTS	16
1.	Visual Monitoring	16
2.	Recordkeeping	
SCHEI	DULE D SPECIAL CONDITIONS	18
1.	Schedule Precedence	18
2.	Other Requirements	
3.	Termination of Permit Registration	18
4.	Local Public Agencies Acting as DEQ's Agent	
5.	Permit-Specific Definitions	
	DULE F_NPDES GENERAL CONDITIONS – INDUSTRIAL FACILITIES	
	CTION A. STANDARD CONDITIONS	
	CTION B. OPERATION AND MAINTENANCE OF POLLUTION CONTROLS	
	CTION C. MONITORING AND RECORDS	
	CTION D. REPORTING REQUIREMENTS	
SEC	CTION E. DEFINITIONS	30

Expiration Date: December 14, 2020

Page 12 of 30

be identified in the ESCP as addressing this condition of the permit, and the rationale for choosing the selected BMP(s) must also be provided.

- a. Compost berms, compost blankets, or compost socks;
- b. Erosion control mats;
- c. Tackifiers used in combination with perimeter sediment control BMPs;
- d. Established vegetated buffers sized at 50 feet (horizontally) plus an additional 25 feet (horizontally) per 5 degrees of slope;
- e. Water treatment by electro-coagulation, flocculation, or filtration; and/or
- f. Other substantially equivalent sediment or turbidity BMP approved by DEQ or Agent.

12. Erosion and Sediment Control Plan (ESCP)

- a. Preparation.
 - i. The permit registrant must ensure that an ESCP is prepared and revised as necessary to reflect site conditions for the construction activity regulated by this permit, and submit revisions to DEQ or Agent in accordance with requirements of this permit. The design, installation, and maintenance of erosion and sediment controls must be adequate to address factors such as the amount, frequency, intensity, and duration of precipitation, the nature of resulting stormwater runoff, and soil characteristics, including the range of soil particle sizes expected to be present on the site.
 - ii. Qualifications to Prepare ESCP.
 - (1) For construction activities disturbing 20 or more acres, the ESCP must be prepared and stamped by a Certified Professional in Erosion and Sediment Control, Certified Professional in Storm Water Quality, Oregon Registered Professional Engineer, Oregon Registered Landscape Architect, or Oregon Certified Engineering Geologist.
 - (2) If engineered facilities such as sedimentation basins or diversion structures for erosion and sediment control are required, the ESCP must be prepared and stamped by an Oregon Registered Professional Engineer.
- b. The ESCP must include the following elements:
 - i. Name of the site.
 - ii. Local Government Requirements. Include any procedures necessary to meet applicable local government erosion and sediment control or stormwater management requirements.
 - iii. Erosion and Sediment Control Inspector.
 - (1) Inspections must be conducted by a person knowledgeable in the principles and practice of erosion and sediment controls who possesses the skills to assess conditions at the construction site that could impact stormwater quality, is knowledgeable in the correct installation of the erosion and sediment controls, and is able to assess the effectiveness of any sediment and erosion control measures selected to control the quality of stormwater discharges from the construction activity.
 - (2) Beginning January 1, 2017, for projects that are five or more acres, inspections must be conducted by a person certified in an erosion and sediment control program that has been approved by DEQ. DEQ has approved the following programs:
 - (a) Certified Professional in Erosion and Sediment Control,
 - (b) Certified Professional in Storm Water Quality,
 - (c) Washington State Certified Erosion and Sediment Control Lead, or
 - (d) Rogue Valley Sewer Services Erosion and Sediment Control Certification.

Expiration Date: December 14, 2020

Page 13 of 30

- (3) Inspections must be conducted by the Erosion and Sediment Control Inspector identified in the ESCP.
- (4) Provide the following for all personnel that will conduct inspections:
 - (a) Name and title;
 - (b) Contact phone number and, if available, e-mail address; and
 - (c) Description of experience and training.

iv. Narrative Site Description.

- (1) Description of the construction activity;
- (2) Proposed timetable indicating when each erosion and sediment control BMP is to be installed and the duration that it is to remain in place;
- (3) Estimates of the total area of the permitted site and the area of the site that is expected to undergo clearing, grading or excavation;
- (4) Nature of the fill material to be used, and of the site soils prior to disturbance;
- (5) Names of the receiving water(s) for stormwater runoff;
- (6) The types of pollutants that could be found in stormwater and their likely sources;
- (7) Any authorized non-stormwater discharges; and
- (8) If a surface water of the state is within 50 feet of the permitted activities,
 - (a) Description of area within 50 feet of project site (including any natural buffer), and
 - (b) Description of approach to manage the natural buffer zone, if any (for example, maintain natural buffer, reduce natural buffer and increase BMPs, or eliminate flow through natural buffer).

v. Site Map and Drawings.

- (1) The site map and drawings must be kept on site and must represent the actual BMP controls being used onsite;
- (2) The site map must show sufficient roads and features for DEQ or Agent to locate and access the site;
- (3) The site map and drawings must include (but is not limited to) the following features (as applicable):
 - (a) Total property boundary including surface area of the development;
 - (b) Areas of soil disturbance (including, but not limited to, showing cut and fill areas and pre- and post-development elevation contours);
 - (c) Drainage patterns before and after finish grading;
 - (d) Discharge points;
 - (e) Areas used for the storage of soils or wastes;
 - (f) Areas where vegetative practices are to be implemented;
 - (g) All erosion and sediment control measures or structures;
 - (h) Impervious structures after construction is completed (including buildings, roads, parking lots and outdoor storage areas);
 - (i) Springs, wetlands and other surface waters on site or adjacent to the site;
 - (j) Temporary and permanent stormwater conveyance systems;
 - (k) Onsite water disposal locations (for example, for dewatering);
 - (l) Storm drain catch basins depicting inlet protection, and a description of the type of catch basins used (for example, field inlet, curb inlet, grated drain and combination);
 - (m) Septic drain fields:
 - (n) Existing or proposed drywells or other UICs;
 - (o) Drinking water wells on site or adjacent to the site;
 - (p) Planters;
 - (q) Sediment and erosion controls including installation techniques;

Expiration Date: December 14, 2020

Page 14 of 30

(r) Natural buffer zones and any associated BMPs for all areas within 50 feet of a water of the state; and

(s) Detention ponds, storm drain piping, inflow and outflow details.

c. ESCP Revisions

- i. The ESCP must be accurate and reflect site conditions. Update the ESCP as needed to represent actual BMPs being used onsite.
- ii. ESCP revisions must:
 - (1) Clearly identify any changes (such as type or design) to the BMPs identified in the ESCP, their location, maintenance required, and any other revisions necessary to prevent and control erosion and sediment runoff.
 - (2) Include contact information and any applicable certification, training and experience for changes in Erosion and Sediment Control Inspector.
- iii. Approval of the revisions by DEQ or Agent prior to implementation is not required.
- iv. Submission of all ESCP revisions is not required. ESCP revisions must be submitted only if they are made for any of the following reasons:
 - (1) Part of a Corrective Action (A.13).
 - (2) Change in address of the permit registrant. Registrant must keep their address current with DEQ or Agent. Failure to do so may be used as grounds for termination of coverage.
 - (3) Change (increase or decrease) in the size of the project.
 - (4) Change (increase or decrease) in the size or location of disturbed areas.
 - (5) Change to BMPs (for example, type, design or location).
 - (6) Change in erosion and sediment control inspector.
- v. If submission of ESCP revisions is required, submit one paper copy and one electronic PDF to DEQ or Agent within 10 calendar days of the revision. These revisions should be submitted as revised pages of the ESCP or drawings only; it is not necessary to submit the entire ESCP. If the permit registrant does not receive a response to the revisions from DEQ or Agent within 10 calendar days of receipt, the proposed revisions are deemed accepted.
- vi. DEQ or Agent may require the permit registrant to revise the ESCP at any time. The permit registrant must submit the revisions according to the timeframe specified by DEQ or Agent.

13. Corrective Actions

- a. The permit registrant must take corrective actions if any of the following occur:
 - i. Significant amounts of sediment or turbidity (as described in A.8.b) are visible downstream of the permitted activities in:
 - (1) A conveyance system leading to surface waters;
 - (2) Surface waters 50 feet or more downstream of the discharge point; or
 - (3) Surface waters at any location where more than one-half of the width of the receiving surface waters is affected.
 - ii. The construction activity causes or contributes to a violation of in-stream water quality standards (A.10.a).
 - iii. DEQ or the Agent requires the permit registrant to take corrective actions to prevent or control the discharge of significant amounts of sediment or turbidity to surface waters or to conveyance systems that discharge to surface waters.
- b. If corrective actions are required, the permit registrant must do all of the following:
 - i. Source(s) of sediment must be controlled within 24 hours to prevent continued or additional discharges. Immediately, but no later than 24 hours after initial detection, take corrective actions or implement additional effective BMPs until the significant amounts of sediment or turbidity are no longer visually detectable and to ensure that the requirements of Conditions A.8.b and A.10.a are met;



CITY OF WOODBURN

GRAD ,	_1
File No: 2019	-08


Department of Economic & Development Services 270 Montgomery Street • Woodburn, Oregon 97071 Phone: 503-982-5246 • Website: www.woodburn-or.us


GRADING PERMIT


(PERMISO PARA ALTERAR LA SUPERFICIE DE TERRENO)

roject location (oblastion del ribyecto).	perty "A" Parcel 2, Partition Plat 2018-075 TL 10 Map 052W1
Property owner (Propietario): Hazel M. Smith Properties, L.	
Mailing Address (Dirección Postal):	Mailing Address (Dirección Postal):
33844 SE White Oak Rd, Corvallis, OR 97333	8840 SW Holly Lane, Wilsonville, OR 97070
Telephone (Teléfono):	Telephone (<i>Teléfono</i>): (971) 206-8615
E-mail (Dirección Cibernética):	E-mail (Dirección Cibernética):
tequired attachments (Accesorios requeridos)	morgan@staffordlandcompany.com
11"x17". Una copia electrónica, preferiblemente en fo	ormato .pdf, se solicita pero no es obligatorio.)
	ty owner, I have read the foregoing application and
Solicitud anterior y sé que lo contenido es verídico. HMS Prop LX Dwner Armed Thomas Mar (Firma del Propietario)	Applicant (Firma del Solicitante)
Solicitud anterior y se que lo contenido es verídico. HMS Prop Loc Dwner Anne Mar	Applicant Mugan While
Owner Sunk Thomas Mar (Firma del Propietario) Print Name YVONNE A Thomas	Applicant (Firma del Solicitante) Print Name Morgan Will
Solicitud anterior y se que lo contenido es verídico. HMS Prop LX Dwner Sun LAThomas na r (Firma del Propietario) Print Name YVONNE A Thomas (Escriba en letra de molde)	Applicant (Firma del Solicitante) Print Name Morgan Will (Escriba en letra de molde)
Owner Sunly homes Mar (Firma del Propietario) Print Name YVONNE A Thomas (Escriba en letra de molde)	Applicant (Firma del Solicitante) Print Name Morgan Will (Escriba en letra de molde)
Solicitud anterior y sé que lo contenido es verídico. HMS Prop LX Downer Anne Mar (Firma del Propietario) Print Name YVONNE A Thomas (Escriba en letra de molde) Date (Fecha) 8 19 2019 De (Cuota)	Applicant (Firma del Solicitante) Print Name Morgan Will (Escriba en letra de molde)

AUG 29 2019







SETBACK LIMITATIONS

N. 1.5.

GENERAL NOTES:

- A. SEE 1200-C DRAWINGS (EC1-EC7) FOR EROSION CONTROL PLAN.
- SITE GRADING SHALL NOT RESULT IN THE IMPOUNDMENT OF STORM WATER ON ADJACENT PROPERTIES.

EARTHWORK SUMMARY				
	VOLUME IN CY			
CUT	1,080			
FILL	479			
NET	601			
	ENCH SPOILS ARE NOT INCLUDED IN ACTOR SHALL INDEPENDENTLY VERIFY VOLUMES.			

RECEIVED

AUG 29 2019

COMMUNITY DEVELOPMENT DEPARTMENT

SMITH CREEK - PHASE 1B
ADJUSTED PROPERTY "A"
RE-PLAT OF PARCEL 2
PARTITION PLAT 2018-65
WOODBURN, OREGON

GRADING PLAN

TE DESCRIPTION
ZOLIS 1ST SUBMITTAL

EMERIO

Design

2677 MILMERZE ROD, SUITE 14
EUGENE, OR 97401

EXPIRES 6/39/7021

SHEET 07

21

EROSION AND SEDIMENT CONTROL NOTES:

- HOLD A PRE-CONSTRUCTION MEETING OF PROJECT CONSTRUCTION PERSONNEL THAT INCLUDES THE INSPECTOR TO DISCUSS EROSION AND SEDIMENT CONTROL MEASURES AND CONSTRUCTION LIMITS. (SCHEDULE A.8.C.I.(3))
- ALL INSPECTIONS MUST BE MADE IN ACCORDANCE WITH DEQ 1200-C PERMIT REQUIREMENTS. (SCHEDULE A.12.B AND SCHEDULE B.1)
- INSPECTION LOGS MUST BE KEPT IN ACCORDANCE WITH DEQ'S 1200-C PERMIT REQUIREMENTS. (SCHEDULE B.1.C AND B.2) RETAIN A COPY OF THE ESCP AND ALL REVISIONS ON SITE AND MAKE IT AVAILABLE ON REQUEST TO DEQ. AGENT. OR THE LOCAL
- MUNICIPALITY. DURING INACTIVE PERIODS OF GREATER THAN SEVEN (7) CONSECUTIVE CALENDAR DAYS, THE ABOVE RECORDS MUST BE RETAINED BY THE PERMIT REGISTRANT BUT DO NOT NEED TO BE AT THE CONSTRUCTION SITE. (SCHEDULE B.2.C)
- 5. ALL PERMIT REGISTRANTS MUST IMPLEMENT THE ESCP. FAILURE TO IMPLEMENT ANY OF THE CONTROL MEASURES OR PRACTICES DESCRIBED IN THE ESCP IS A VIOLATION OF THE PERMIT. (SCHEDULE A.8.a)
- THE ESCP MUST BE ACCURATE AND REFLECT SITE CONDITIONS. (SCHEDULE A.12.C.I)
- SUBMISSION OF ALL ESCP REVISIONS IS NOT REQUIRED. SUBMITTAL OF THE ESCP REVISIONS IS ONLY UNDER SPECIFIC CONDITIONS. SUBMIT ALL NECESSARY REVISION TO DEQ OR AGENT WITHIN 10 DAYS. (SCHEDULE A.12.c.iv AND V)
- PHASE CLEARING AND GRADING TO THE MAXIMUM EXTENT PRACTICAL TO PREVENT EXPOSED INACTIVE AREAS FROM BECOMING A SOURCE OF
- 9. IDENTIFY, MARK, AND PROTECT (BY FENCING OFF OR OTHER MEANS) CRITICAL RIPARIAN AREAS AND VEGETATION INCLUDING IMPORTANT TREES AND ASSOCIATED ROOTING ZONES, AND VEGETATION AREAS TO BE PRESERVED. IDENTIFY VEGETATIVE BUFFER ZONES BETWEEN THE SITE AND SENSITIVE AREAS (E.G., WETLANDS), AND OTHER AREAS TO BE PRESERVED, ESPECIALLY IN PERIMETER AREAS. (SCHEDULE A.8.c.i.(1)
- 10. PRESERVE EXISTING VEGETATION WHEN PRACTICAL AND RE-VEGETATE OPEN AREAS. RE-VEGETATE OPEN AREAS WHEN PRACTICABLE BEFORE AND AFTER GRADING OR CONSTRUCTION. IDENTIFY THE TYPE OF VEGETATIVE SEED MIX USED. (SCHEDULE A.7.a.v)
- 11. MAINTAIN AND DELINEATE ANY EXISTING NATURAL BUFFER WITHIN THE 50-FEET OF WATERS OF THE STATE. (SCHEDULE A.7.B.I. AND
- 12. INSTALL PERIMETER SEDIMENT CONTROL, INCLUDING STORM DRAIN INLET PROTECTION AS WELL AS ALL SEDIMENT BASINS, TRAPS, AND BARRIERS PRIOR TO LAND DISTURBANCE. (SCHEDULE A.8.C.I.(5))
- 13. CONTROL BOTH PEAK FLOW RATES AND TOTAL STORMWATER VOLUME, TO MINIMIZE EROSION AT OUTLETS AND DOWNSTREAM CHANNELS AND STREAMBANKS. (SCHEDULE A.7.C)
- 14. CONTROL SEDIMENT AS NEEDED ALONG THE SITE PERIMETER AND AT ALL OPERATIONAL INTERNAL STORM DRAIN INLETS AT ALL TIMES DURING CONSTRUCTION, BOTH INTERNALLY AND AT THE SITE BOUNDARY. (SCHEDULE A.7.D.I)
- 15. ESTABLISH CONCRETE TRUCK AND OTHER CONCRETE EQUIPMENT WASHOUT AREAS BEFORE BEGINNING CONCRETE WORK. (SCHEDULE A.8.c.i(6)) 16. APPLY TEMPORARY AND/OR PERMANENT SOIL STABILIZATION MEASURES IMMEDIATELY ON ALL DISTURBED AREAS AS GRADING PROGRESSES. TEMPORARY OR PERMANENT STABILIZATIONS MEASURES ARE NOT REQUIRED FOR AREAS THAT ARE INTENDED TO BE LEFT UNVEGETATED. SUCH AS DIRT ACCESS ROADS OR UTILITY POLE PADS. (SCHEDULE A.8.c.ii.(3))
- 17. ESTABLISH MATERIAL AND WASTE STORAGE AREAS, AND OTHER NON-STORMWATER CONTROLS. (SCHEDULE A.8.c.i.(7))
- 18. PREVENT TRACKING OF SEDIMENT ONTO PUBLIC OR PRIVATE ROADS USING BMPS SUCH AS: CONSTRUCTION ENTRANCE, GRAVELED (OR PAVED) EXITS AND PARKING AREAS, GRAVEL ALL UNPAVED ROADS LOCATED ONSITE, OR USE AN EXIT TIRE WASH. THESE BMPS MUST BE IN PLACE PRIOR TO LAND-DISTURBING ACTIVITIES. (SCHEDULE A.7.d.ii & A.8.c.i.(4))
- 19. WHEN TRUCKING SATURATED SOILS FROM THE SITE. EITHER USE WATER-TIGHT TRUCKS OR DRAIN LOADS ON SITE. (SCHEDULE A.7.d.ii(5)) 20. CONTROL PROHIBITED DISCHARGES FROM LEAVING THE CONSTRUCTION SITE, I.E., CONCRETE WASH-OUT. WASTEWATER FROM CLEANOUT OF
- 21. USE BMPS TO PREVENT OR MINIMIZE STORMWATER EXPOSURE TO POLLUTANTS FROM SPILLS: VEHICLE AND EQUIPMENT FUELING MAINTENANCE, AND STORAGE; OTHER CLEANING AND MAINTENANCE ACTIVITIES; AND WASTE HANDLING ACTIVITIES. THESE POLLUTANTS
- 22. IMPLEMENT THE FOLLOWING BMPS WHEN APPLICABLE: WRITTEN SPILL PREVENTION AND RESPONSE PROCEDURES, EMPLOYEE TRAINING ON SPILL PREVENTION AND PROPER DISPOSAL PROCEDURES, SPILL KITS IN ALL VEHICLES, REGULAR MAINTENANCE SCHEDULE FOR VEHICLES AND
- 24. THE APPLICATION RATE OF FERTILIZERS USED TO REESTABLISH VEGETATION MUST FOLLOW MANUFACTURER'S RECOMMENDATIONS TO MINIMIZE NUTRIENT RELEASES TO SURFACE WATERS. EXERCISE CAUTION WHEN USING TIME-RELEASE FERTILIZERS WITHIN ANY WATERWAY RIPARIAN
- 25. IF AN ACTIVE TREATMENT SYSTEM (FOR EXAMPLE, ELECTRO-COAGULATION, FLOCCULATION, FILTRATION, ETC.) FOR SEDIMENT OR OTHER POLLUTANT REMOVAL IS EMPLOYED, SUBMIT AN OPERATION AND MAINTENANCE PLAN (INCLUDING SYSTEM SCHEMATIC, LOCATION OF SYSTEM LOCATION OF DISCHARGE DISCHARGE DISPERSION DEVICE DESIGN. AND A SAMPLING PLAN AND FREQUENCY) BEFORE TREATMENT SYSTEM. OBTAIN PLAN APPROVAL BEFORE OPERATING THE TREATMENT SYSTEM. OPERATE AND MAINTAIN THE TREATMENT SYSTEM ACCORDING TO MANUFACTURER'S SPECIFICATIONS. (SCHEDULE A.9.d)
- 26. TEMPORARILY STABILIZE SOILS AT THE END OF THE SHIFT BEFORE HOLIDAYS AND WEEKENDS, IF NEEDED. THE REGISTRANT IS RESPONSIBLE FOR ENSURING THAT SOILS ARE STABLE DURING RAIN EVENTS AT ALL TIMES OF THE YEAR. (SCHEDULE A.7.B)
- 27. AS NEEDED BASED ON WEATHER CONDITIONS, AT THE END OF EACH WORKDAY SOIL STOCKPILES MUST BE STABILIZED OR COVERED, OR OTHER BMPS MUST BE IMPLEMENTED TO PREVENT DISCHARGES TO SURFACE WATERS OR CONVEYANCE SYSTEMS LEADING TO SURFACE WATERS.
- 28. CONSTRUCTION ACTIVITIES MUST AVOID OR MINIMIZE EXCAVATION AND BARE GROUND DURING WET WEATHER. (SCHEDULE A.7.a.i) 29. SEDIMENT FENCE: REMOVE TRAPPED SEDIMENT BEFORE IT REACHES ONE THIRD OF THE ABOVE GROUND FENCE HEIGHT AND BEFORE FENCE REMOVAL. (SCHEDULE A.9.c.i)
- 30. OTHER SEDIMENT BARRIERS (SUCH AS BIOBAGS): REMOVE SEDIMENT BEFORE IT REACHES TWO INCHES DEPTH ABOVE GROUND HEIGHT. AND BEFORE BMP REMOVAL. (SCHEDULE A.9.c.ii)
- 31. CATCH BASINS: CLEAN BEFORE RETENTION CAPACITY HAS BEEN REDUCED BY FIFTY PERCENT. SEDIMENT BASINS AND SEDIMENT TRAPS: REMOVE TRAPPED SEDIMENTS BEFORE DESIGN CAPACITY HAS BEEN REDUCED BY FIFTY PERCENT AND AT COMPLETION OF PROJECT.
- 32. WITHIN 24 HOURS, SIGNIFICANT SEDIMENT THAT HAS LEFT THE CONSTRUCTION SITE, MUST BE REMEDIATED. INVESTIGATE THE CAUSE OF THE SEDIMENT RELEASE AND IMPLEMENT STEPS TO PREVENT A RECURRENCE OF THE DISCHARGE WITHIN THE SAME 24 HOURS. ANY IN-STREAM CLEAN UP OF SEDIMENT SHALL BE PERFORMED ACCORDING TO THE OREGON DIVISION OF STATE LANDS REQUIRED TIMEFRAME.
- 33. THE INTENTIONAL WASHING OF SEDIMENT INTO STORM SEWERS OR DRAINAGE WAYS MUST NOT OCCUR. VACUUMING OR DRY SWEEPING AND MATERIAL PICKUP MUST BE USED TO CLEANUP RELEASED SEDIMENTS. (SCHEDULE A.9.b.ii)
- 34. THE ENTIRE SITE MUST BE TEMPORARILY STABILIZED USING VEGETATION OR A HEAVY MULCH LAYER, TEMPORARY SEEDING, OR OTHER
- METHOD SHOULD ALL CONSTRUCTION ACTIVITIES CEASE FOR 30 DAYS OR MORE (SCHEDULE 1.7.f.i) 35. PROVIDE TEMPORARY STABILIZATION FOR THAT PORTION OF THE SITE WHERE CONSTRUCTION ACTIVITIES CEASE FOR 14 DAYS OR MORE WITH A COVERING OF BLOWN STRAW AND A TACKIFIER, LOOSE STRAW, OR AN ADEQUATE COVERING OF COMPOST MULCH UNTIL WORK RESUMES ON THAT PORTION OF THE SITE (SCHEDULE A.7.f.ii)
- 36. DO NOT REMOVE TEMPORARY SEDIMENT CONTROL PRACTICES UNTIL PERMANENT VEGETATION OR OTHER COVER OF EXPOSED AREAS IS ESTABLISHED. ONCE CONSTRUCTION IS COMPLETE AND THE SITE IS STABILIZED, ALL TEMPORARY EROSION CONTROLS AND RETAINED SOILS MUST BE REMOVED AND DISPOSED OF PROPERLY, UNLESS DOING SO CONFLICTS WITH LOCAL REQUIREMENTS. (SCHEDULE A.8.C.III(1) AND D.3.II AND III)


INSPECTION FREQUENCY:


	SITE CONDITION	MINIMUM FREQUENCY
1	ACTIVE PERIOD	DAILY WHEN STORMWATER RUNOFF, INCLUDING RUNOFF FROM SNOW MELT, IS OCCURRING. AT LEAST ONCE EVERY FOURTEEN (14) CALENDAR DAYS REGARDLESS OF WHETHER STORMWATER RUNOFF IS OCCURRING.
2	PRIOR TO THE SITE BECOMING INACTIVE OR IN ANTICIPATION OF SITE INACCESSIBILITY.	ONCE TO ENSURE THAT EROSION AND SEDIMENT CONTROL MEASURES ARE IN WORKING ORDER. ANY NECESSARY MAINTENANCE AND REPAIR MUST BE MADE PRIOR TO LEAVING THE SITE.
3	INACTIVE PERIODS GREATER THAN FOURTEEN (14) CONSECUTIVE CALENDAR DAYS.	ONCE EVERY MONTH.
4	PERIODS DURING WHICH THE SITE IS INACCESSIBLE DUE TO INCLEMENT WEATHER.	IF PRACTICAL, INSPECTIONS MUST OCCUR DAILY AT A RELEVANT AND ACCESSIBLE DISCHARGE POINT OR DOWNSTREAM LOCATION.
5	PERIODS DURING WHICH DISCHARGE IS UNLIKELY DUE TO FROZEN CONDITIONS.	MONTHLY. RESUME MONITORING IMMEDIATELY UPON MELT, OR WHEN WEATHER CONDITIONS MAKE DISCHARGES LIKELY.

- HOLD A PRE-CONSTRUCTION MEETING OF PROJECT CONSTRUCTION PERSONNEL THAT INCLUDES THE INSPECTOR TO
- DISCUSS EROSION AND SEDIMENT CONTROL MEASURES AND CONSTRUCTION LIMITS.
- * ALL INSPECTIONS MUST BE MADE IN ACCORDANCE WITH DEQ 1200-C PERMIT REQUIREMENTS.
- * INSPECTION LOGS MUST BE KEPT IN ACCORDANCE WITH DEQ'S 1200-C PERMIT REQUIREMENTS. * RETAIN A COPY OF THE ESCP AND ALL REVISIONS ON SITE AND MAKE IT AVAILABLE ON REQUEST TO DEQ, AGENT, OR THE LOCAL MUNICIPALITY. DURING INACTIVE PERIODS OF GREATER THAN SEVEN (7) CONSECUTIVE CALENDAR DAYS, RETAIN THE ESCP AT THE CONSTRUCTION SITE OR AT ANOTHER LOCATION. (SCHEDULE B.2.a)

SMITH CREEK PHASE 1A

RESIDENTIAL SUBDIVISION OF TAX MAP 52W13 -TL 100, TAX MAP 52W13BD -TL 100 & 200 **TAX MAP 51W18BC - TL 4000** WOODBURN, OREGON





BMP MATRIX FOR CONSTRUCTION PHASES

	CLEARING	MASS GRADING	INSTALLATION	CONSTRUCTION	STABILIZATION	(OCT. 1 - MAY 31)
EROSION PREVENTION						
PRESERVE NATURAL VEGETATION	Х	Х	X	Х	Х	Х
GROUND COVER					Х	Х
HYDRAULIC APPLICATIONS (HYDRO—SEEDING)					х	
PLASTIC SHEETING	Х	Х				Х
MATTING					Х	Х
DUST CONTROL	Х	Х	Х	Х	Х	Х
TEMPORARY/ PERMANENT SEEDING		Х			Х	Х
BUFFER ZONE	** X	Х	Х	Х	Х	Х
SEDIMENT CONTROL						
SEDIMENT FENCE (PERIMETER)	** X	Х	Х	Х	Х	Х
SEDIMENT FENCE (INTERIOR)	** X	Х	X	X	X	Х
INLET PROTECTION	** X	Х	X	X	X	X
STRAW WATTLES	** X	Х	X	X		
FILTER BERM						
DEWATERING			Х			
SEDIMENT TRAP		Х	Х	Х	Х	X
NATURAL BUFFER ENCROACMENT	Χ	Х	Х	Х	Х	Х
RUNOFF CONTROL						
CONSTRUCTION ENTRANCE	** X	Х	Х	Х		X
PIPE SLOPE DRAIN						
OUTLET PROTECTION	** X	Х	Х	Х		
SURFACE ROUGHENING		Х			Х	
CHECK DAMS					Х	
POLLUTION PREVENTION						
PROPER SIGNAGE	Х	Х	Х	Х	Х	X
HAZ WASTE MGMT	Х	Х	Х	Х	Х	X
SPILL KIT ON-SITE	Х	X	Х	Х	Х	X
CONCRETE WASHOUT AREA	Х	Х	Х	Х	Х	Х

* SIGNIFIES BMP'S REQUIRED FOR WORK WITHIN 50' OF WATER OF THE STATE **SIGNIFIES BMP THAT WILL BE INSTALLED PRIOR TO ANY GROUND DISTURBING ACTIVITY

MASS GRADING

<u> IOTICE TO EXCAVATORS:</u> ATTENTION: OREGON LAW REQUIRES YOU TO FOLLOW RULES ADOPTED BY THE OREGON JTILITY NOTIFICATION CENTER. THOSE RULES POTENTIAL UNDERGROUND FACILITY OWNER ARE SET FORTH IN OAR 952-001-0010 THROUGH OAR 952-001-0090. YOU MAY OBTAIN Dig Safely. COPIES OF THE RULES FROM THE CENTER BY CALLING 503-232-1987. IF YOU HAVE ANY Call the Oregon One-Call Center QUESTIONS ABOUT THE RULES, YOU MAY DIAL 811 or 1-800-332-2344 CONTACT THE CENTER. YOU MUST NOTIFY THE CENTER AT LEAST TOW BUSINESS DAYS BEFORE COMMENCING AN EXCAVATION. CALL 503-246-6699.

EMERGENCY TELEPHONE NUMBERS NW NATURAL GAS M-F 7am-6pm 503-226-4211 Ext.431.

AFTER HOURS 503-226-421 503-464-7777 CENTURY LINK 1-800-491-0118 503-982-5240 CITY MAINTENANCE CITY WATER 503-982-5238 FRONTIER 1-800-921-810

OWNER: ENGINEER

BETWEEN STUBB ROAD NE AND S SETTLEMIER AVE AND CAN BE IDENTIFIED

LOCATED IN THE N.W. & N.E., 1/4 OF SECTION 13, AND THE S.E. 1/4 OF

SECTION 12, T. 5 S., R. 2 W. AND THE N.W. 1/4 OF SECTION 18 AND THE

THE VERTICAL DATUM FOR THIS SURVEY IS BASED UPON POST-PROCESSED

GPS STATIC OBSERVATION OF INDEPENDENT CONTROL, PROCESSED THROUGH

OPUS, DATUM IS NAVD 88, CONVERTED TO NGVD 29 THROUGH THE VERTCON

EC2 - ON-SITE DEMOLITION & EROSION & SEDIMENT CONTROL

EC3 - ON-SITE DEMOLITION & EROSION & SEDIMENT CONTROL

INITIAL

EC4 - STREET GRADING & EROSION & SEDIMENT CONTROL EC5 - STREET GRADING & EROSION & SEDIMENT CONTROL

EC6 - EROSION AND SEDIMENT CONTROL DETAILS

EC7 - EROSION AND SEDIMENT CONTROL DETAILS

SW 1/4 OF SECTION 7, T. 5 S., R. 1 W., W.M., MARION COUNTY, OREGON

NN MARION COUNTY ASSESSOR'S MAPS AS TAX LOTS: 052W13 0100,

STAFFORD DEVELOPMENT COMPANY EMERIO DESIGN, LLC 8840 SW HOLLY LANE WILSONVILLE, OREGON 97070 CONTACT: MORGAN WILL (503) 305-7647

PROJECT LOCATION

52W13BD 0100 & 0200, 51W18BC 4000.

PROPERTY DESCRIPTION

052W13 0100, 52W13BD 0100 & 0200, 51W18BC 4000.

LAT: 45.130 LONG: -122.682

PROCESS TOOL.

EC1 - COVER SHEET

DRAWING INDEX

6445 SW FALLBROOK PL SUITE 100 BEAVERTON, OR 97008 CONTACT: ROY W. HANKINS, P.E. (503) 746-8812 (P)

SURVEYOR

BARKER SURVEYING 3657 KASHMIR WAY SE SALEM, OREGON 97317 CONTACT: GREGORY L. WILSON OREGON CITY, OR 97045 (503) 588-8800 (P)

PERMITEE'S SITE INSPECTOR

POINT ENVIRONMENTAL (541) 207-8441 PHONE: MIKEZ@POINTENV.COM E-MAIL: NAME: SEDIMENT, AND POLLUTION CONTROL FEATURES ON A WIDE VARIETY OF CIVIL INFRASTRUCTURE PROJECTS.

NARRATIVE DESCRIPTIONS

EXISTING SITE CONDITIONS A FARM ON 4 TAX LOTS

DEVELOPED SITE CONDITIONS

RESIDENTIAL SUBDIVISION

NATURE OF CONSTRUCTION ACTIVITY AND TIME TABLE FOR MAJOR ACTIVITIES

CPESC #7386.

CLEARING AND GRUBBING (MAY 2019)

MASS GRADING (EXCAVATION AND FILL) (MAY 2019)

STREET AND UTILITY CONSTRUCTION (MAY-SEPTEMBER 2019)

FINAL STABILIZATION (SEPTEMBER-DECEMBER 2019) TOTAL SITE AREA = 76.03 ACRES

TOTAL DISTURBED AREA ON-SITE = 69.04 ACRES TOTAL LEFT UNDISTURBED = 6.99 ACRES

SHALL BE GENERATED ON-SITE FROM GRADING EXCAVATION AND UTILITY TRENCH SPOILS. RECEIVING WATER BODY

ON-SITE SOILS HAVE A SLIGHT EROSION POTENTIAL. ALL FILL MATERIAL

UN-NAMED TRIBUTARY TO MILL CREEK.


THESE PLANS ARE FULL SIZE ON 34x22 (ANSI—D) PAPER, IF PLOTTED ON 11x17 (ANSI—B) SCALE ACCORDINGLY.

THE PERMITTEE IS REQUIRED TO MEET ALL THE CONDITIONS OF THE 1200-C PERMIT. THIS ESCP AND GENERAL CONDITIONS HAVE BEEN DEVELOPED TO FACILITATE COMPLIANCE WITH THE 1200-C PERMIT REQUIREMENTS. IN CASES OF DISCREPANCIES OR OMISSIONS, THE 1200-C PERMIT REQUIREMENTS SUPERCEDE REQUIREMENTS OF THIS PLAN.

RATIONALE STATEMENT

A COMPREHENSIVE LIST OF AVAILABLE BEST MANAGEMENT PRACTICES (BMP) OPTIONS BASED ON DEQ'S GUIDANCE MANUAL HAS BEEN REVIEWED TO COMPLETE THIS EROSION AND SEDIMENT CONTROL PLAN. SOME OF THE BMPS LISTED IN MATRIX AT LEFT WERE NOT CHOSEN BECAUSE THEY WERE DETERMINED TO NOT EFFECTIVELY MANAGE EROSION PREVENTION AND SEDIMENT CONTROL FOR THIS PROJECT BASED ON SPECIFIC SITE CONDITIONS, INCLUDING SOIL CONDITIONS, TOPOGRAPHIC CONSTRAINTS, ACCESSIBILITY TO THE SITE, AND OTHER RELATED CONDITIONS. AS THE PROJECT PROGRESSES AND THERE IS A NEED TO REVISE THE ESC PLAN, AN ACTION PLAN WILL BE SUBMITTED.


200











SHEET EC7




























SMITH TAX M













SHEET

EC7

SMITH CREEK -TAX MAP 52W

SEDIMENT DETAILS

EROSION & CONTROL

