



August 17, 2023

AAI Engineering  
Christopher Thornton, PE  
4875 SW Griffith Dr  
Suite 100  
Beaverton, OR 97005

**RE: Approval of Grading Permit GRAD 23-05 “Woodburn Apartments” for 119 N. Pacific Hwy (Tax Lot 051W17BC07500)**

Dear Mr. Thornton:

Staff approves the Grading Permit, subject to the conditions of approval outlined in this letter.

*Summary of Review:*

This site is subject to the development standards of the [Woodburn Development Ordinance \(WDO\)](#). The applicant is requesting to perform grading work in preparation for construction of an apartment complex. Pursuant to WDO 4.01.02, the Director shall render all Type I land use decisions. The Director’s decision is the final decision of the City on a Type I application and cannot be appealed by any party through the City land use appeals process.

*Planning Conditions of Approval:*

1. Conformance with Approved Plans: All site work shall be in substantial conformance with the approved grading plans.
2. DEQ: All development activity shall be in accordance with the approved Department of Environmental Quality (DEQ) 1200-C permit. The applicant shall provide to the City any modifications to the DEQ permit.
3. Other agencies: The applicant, not the City, is responsible for obtaining permits from Marion County, US Army Corps of Engineers (USACE), Oregon Department of State Lands (DSL), Oregon Department of Transportation (ODOT), and other agencies which might require approval or permit.

4. ROW: All work within City rights-of-way (ROWs) or easements within City jurisdiction shall require plan approval and permit issuance from the Public Works Department. All work within ODOT rights-of-way (ROWs) or easements within ODOT jurisdiction shall require plan approval and permit issuance from ODOT.

*Public Works Conditions of Approval:*

5. There is an issue with the private storm design that must be resolved prior to civil plan approval. This Grading Permit is approved prior to civil plan approval at owner's own risk.
6. The applicant shall comply with the submitted grading and erosion control plans, including measures to keep the ROW clean, to protect existing catch basins around the work area, and maintain dust control measures. All catch basins around the work area shall be clean of debris and soils at all times.
7. Construction access is limited to only one construction entrance onto State Hwy 99E.
8. The applicant shall continuously maintain adequate protection of all work from damage and protect the public and private property of others from injury or loss arising in connection with the work.
9. The applicant shall comply with City of Woodburn Planning Department requirements through Woodburn Development Ordinance (WDO) 5.01.04 Grading Permit.
10. Prior to starting work, contact ODOT for inspection of the erosion control in their rights-of-way.
11. All work in the right-of-way will need to wait for a construction permit from ODOT. Once that permit is acquired, the applicant shall leave the ROW in clean condition, free from litter and debris, at the end of each workday, or more frequently if directed by the ODOT Inspector.
12. Sidewalk and street closures are not allowed under this permit.
13. Prior to starting work, silt fencing shall be installed around the entire perimeter of the work area. Applicant shall comply with all requirements and conditions set on their 1200C permit.

Final decision approved by designee:



Heidi Hinshaw  
Associate Planner

August 17, 2023

Enclosures:

- DEQ 1200-C Permit
- Approved Plans
- Stormwater Report & Calculations

cc: Chris Kerr, Community Development Director  
Colin Cortes, AICP, CNU-A, Senior Planner  
Dan Handel, AICP, Planner  
Curtis Stultz, Public Works Director  
Dago Garcia, PE, City Engineer  
Casey Knecht, ODOT Region 2

file: GRAD 23-05



City of Woodburn  
Community Development Department  
270 Montgomery Street  
Woodburn, OR 97071  
Phone: 503-982-5246  
Email: [planning@ci.woodburn.or.us](mailto:planning@ci.woodburn.or.us)

OFFICE USE ONLY  
File Number(s):  
GRAD 23-05

971-23-000028-PLNG

## Application Packet for a Type I Grading Permit

RECEIVED

COMMUNITY DEVELOPMENT  
DEPARTMENT

Visit the City of Woodburn [Planning webpage](#) for the most current forms and applications.

MAR 09 2023

### General Information:

COMMUNITY DEVELOPMENT  
DEPARTMENT

The purpose of this review is to ensure that grading is in compliance with the Woodburn Storm Management Plan, Woodburn Flood Plain Ordinance, Public Works Department Construction Standards and Specifications, and the State Building Code. Grading permits are subject to [Woodburn Development Ordinance](#) (WDO) section 5.01.03. The requirement for a grading permit applies to any of the following activities:

- Any fill, removal, or grading of land identified within the boundaries of the regulatory floodplain;
- Any fill, removal, or grading of land identified within the Riparian Corridor & Wetlands Overlay District (RCWOD);
- Any fill, removal, or grading of land that requires a permit from the Oregon Department of State Lands;
- Any fill, removal, or grading of land area that equals or exceeds one acre; or
- Any development activity required by the WDO to submit a grading plan or permit.

**Fee:** Fees are required for an application to be accepted.

See the [planning fee schedule](#) online

### Required Submittals:

- [Uniform Application](#) – one completed copy. In the case of multiple applications, only one Uniform Application form need be submitted. **Previously submitted - DR 22-05, EXCP 22-07, VAR 22-06**
- One copy of each Oregon Department of Environmental Quality or US Army Corps of Engineers permit, if required and approved. **N/A**
- Three copies** of a construction site management plan (ledger or 24"x36" plan sizes are acceptable), which shall include the following items:
  - Site location and vicinity map to scale showing the subject and adjacent properties.
  - Site development drawings to scale, which shall include:
    - Existing site conditions including property lines, easements, driveways, and structures;
    - Existing vegetation and wetlands, including locations and species of [Significant Trees](#) (see WDO 3.06.07);
    - Riparian Corridor & Wetland Overlay District (RCWOD) boundary (see WDO 2.05.05);
    - On-site elevations (existing and proposed grade contours) and surface drainage directions;
    - Areas where ground clearing, grading, cut or fill or other ground disturbing activities will occur;
    - Construction entrances and exits, staging areas, and refuse areas;
    - Existing and proposed stormwater management facilities (catch basins, area drains, etc.)
- Documentation of proposed Best Management Practices (BMPs). See the [ODOT Erosion Control Manual](#) for further information about BMPs.

**Prior to deeming an application complete, the Director may request additional information.**

**Note to Applicant:** Upon project completion, all erosion control measures must be removed by the Applicant.



July 21, 2023

Abdulbaset Shagrun  
Woodburn Realestate, LLC  
3000 Market St NE Ste 510  
Salem, Oregon 97301-1807

Re: 1200-C National Pollutant Discharge Elimination System (NPDES) Registration  
Permit/PLC No.: NGEN12C-ORR10H830  
Project Name: 119 Pacific Highway  
Project Location: 119 N Pacific Hwy, Woodburn,  
Marion County

Dear Abdulbaset Shagrun:

The Oregon Department of Environmental Quality (DEQ) has reviewed your application and approved your registration for coverage under the NPDES Construction Stormwater Discharge Permit 1200-C (permit). As the registrant, you are legally responsible for compliance with all permit conditions. See this link <https://www.oregon.gov/deq/wq/wqpermits/Pages/Stormwater-Construction.aspx> for a copy of the permit, technical assistance, and all relevant permit forms.

### **Registrant Obligations**

- Comply with all permit conditions. DEQ strongly recommends that you read the permit.
- Fully implement your Erosion and Sediment Control Plan (ESCP). You may need to modify site control measures as site conditions change.
- Ensure that all appropriate contractors hired by you to implement the permit on your behalf have a copy of the ESCP and the permit. Keep a list of all contractors working on your site along with their contact information.
- Notify DEQ of significant projects changes, including ESCP revisions, inspectors, or project ownership changes.
- Perform & document visual monitoring according to Schedule B of the permit by a certified erosion and sediment control person.
- Terminate coverage at the end of the project. You will be charged an annual registration fee until registration is terminated.

The permit does not authorize excavation or fill in state waterways, including wetlands, and does not replace the requirement for receiving authorization to do this type of work under Section 404 of the Clean Water Act. If the authorized activity involves earthmoving in a known or suspected wetland condition you must contact the Department of State Lands at 503-986-5200 if you are west of the Cascades, or 541-388-6112 if you are east of the Cascades, and request a wetland determination prior to earth moving.

The construction stormwater general permit, technical assistance manuals and other information is also available on [DEQ Stormwater Program's website](#).

Sincerely,

[DEQ Stormwater Permitting Program](#)





**AAI** ajghian associates, inc.  
**ENGINEERING**  
 4875 SW Griffin Drive, Suite 300 | Beaverton, OR 97005  
 503.620.3630 | 503.620.5539 | Fax 1www.aaieng.com

**119 N PACIFIC HWY**  
 WOODBURN, OR

SHEET TITLE

ESCP EXISTING  
 CONDITIONS PLAN

DATE: 12/13/21

DRAWN: JS

CHECKED: CFT

REVISIONS:

© AAI ENGINEERING INC. 2023. ALL RIGHTS RESERVED.

THESE DRAWINGS ARE THE PROPERTY OF AAI ENGINEERING INC. AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER, EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF AAI ENGINEERING INC.

SHEET NUMBER

**EC2.0**

JOB NUMBER: A21194.10

**EROSION CONTROL PLAN NOTES**

1. APPROVAL OF THIS EROSION/SEDIMENTATION CONTROL (ESC) PLAN DOES NOT CONSTITUTE AN APPROVAL OF PERMANENT ROAD OR DRAINAGE DESIGN (E.G., SIZE AND LOCATION OF ROADS, RESTRICTORS, CHANNELS, RETENTION FACILITIES, UTILITIES, ETC.).
2. THE IMPLEMENTATION OF THESE ESC PLANS AND THE CONSTRUCTION, MAINTENANCE, REPLACEMENT, AND UPGRADING OF THESE ESC FACILITIES IS THE RESPONSIBILITY OF THE CONTRACTOR UNTIL ALL CONSTRUCTION IS COMPLETED AND APPROVED AND PERMANENT VEGETATION/LANDSCAPING IS ESTABLISHED.
3. THE BOUNDARIES OF THE CLEARING LIMITS SHOWN ON THIS PLAN SHALL BE CLEARLY FLAGGED IN THE FIELD PRIOR TO CONSTRUCTION. DURING THE CONSTRUCTION PERIOD, NO DISTURBANCE BEYOND THE FLAGGED CLEARING LIMITS SHALL BE PERMITTED. THE FLAGGING SHALL BE MAINTAINED BY THE CONTRACTOR FOR THE DURATION OF CONSTRUCTION.
4. THE ESC FACILITIES SHOWN ON THIS PLAN MUST BE CONSTRUCTED IN CONJUNCTION WITH ALL CLEARING AND GRADING ACTIVITIES, AND IN SUCH A MANNER AS TO ENSURE THAT SEDIMENT AND SEDIMENT LADEN WATER DO NOT ENTER THE DRAINAGE SYSTEM, ROADWAYS, OR VIOLATE APPLICABLE WATER STANDARDS.
5. THE ESC FACILITIES SHOWN ON THIS PLAN ARE THE MINIMUM REQUIREMENTS FOR ANTICIPATED SITE CONDITIONS. DURING THE CONSTRUCTION PERIOD, THESE ESC FACILITIES SHALL BE UPGRADED AS NEEDED FOR UNEXPECTED STORM EVENTS AND TO ENSURE THAT SEDIMENT AND SEDIMENT LADEN WATER DO NOT LEAVE THE SITE.
6. THE ESC FACILITIES SHALL BE INSPECTED DAILY BY THE CONTRACTOR AND MAINTAINED AS NECESSARY TO ENSURE THEIR CONTINUED FUNCTIONING.
7. THE ESC FACILITIES ON INACTIVE SITES MAY REDUCE FREQUENCY OF INSPECTIONS WHERE STABILIZATION STEPS IN SECTION 2.2.20 HAVE BEEN COMPLETED. AFTER BECOMING INACTIVE, THE ESC FACILITIES SHALL BE INSPECTED AND MAINTAINED TWICE THE FIRST MONTH, NO LESS THAN 14 CALENDAR DAYS APART, THEN A MINIMUM OF ONCE A MONTH OR WITHIN THE 24 HOURS FOLLOWING A STORM EVENT.
8. AT NO TIME SHALL MORE THAN ONE FOOT OF SEDIMENT BE ALLOWED TO ACCUMULATE WITHIN A TRAPPED CATCH BASIN. ALL CATCH BASINS AND CONVEYANCE LINES SHALL BE CLEANED PRIOR TO PAVING. THE CLEANING OPERATION SHALL NOT FLUSH SEDIMENT LADEN WATER INTO THE DOWNSTREAM SYSTEM.
9. STABILIZED CONSTRUCTION ENTRANCES SHALL BE INSTALLED AT THE BEGINNING OF CONSTRUCTION AND MAINTAINED FOR THE DURATION OF THE PROJECT. ADDITIONAL MEASURES MAY BE REQUIRED TO ENSURE THAT ALL PAVED AREAS ARE KEPT CLEAN FOR THE DURATION OF THE PROJECT.


**PRE-CONSTRUCTION, CLEARING AND DEMOLITION NOTES**

1. ALL BASE ESC MEASURES (INLET PROTECTION, PERIMETER SEDIMENT CONTROL, GRAVEL CONSTRUCTION ENTRANCES, ETC.) MUST BE IN PLACE, FUNCTIONAL, AND APPROVED IN AN INITIAL INSPECTION, PRIOR TO COMMENCEMENT OF CONSTRUCTION ACTIVITIES.
2. SEDIMENT BARRIERS APPROVED FOR USE INCLUDE SEDIMENT FENCE, BERMS CONSTRUCTED OUT OF MULCH, CHIPPINGS, OR OTHER SUITABLE MATERIAL, STRAW WATTLES, OR OTHER APPROVED MATERIALS.
3. SENSITIVE RESOURCES INCLUDING, BUT NOT LIMITED TO, TREES, WETLANDS, AND RIPARIAN PROTECTION AREAS SHALL BE CLEARLY DELINEATED WITH ORANGE CONSTRUCTION FENCING OR CHAIN LINK FENCING IN A MANNER THAT IS CLEARLY VISIBLE TO ANYONE IN THE AREA. NO ACTIVITIES ARE PERMITTED TO OCCUR BEYOND THE CONSTRUCTION BARRIER.
4. CONSTRUCTION ENTRANCES SHALL BE INSTALLED AT THE BEGINNING OF CONSTRUCTION AND MAINTAINED FOR THE DURATION OF THE PROJECT. ADDITIONAL MEASURES INCLUDING, BUT NOT LIMITED TO, STREET SWEEPING, AND VACUUMING, MAY BE REQUIRED TO INSURE THAT ALL PAVED AREAS ARE KEPT CLEAN FOR THE DURATION OF THE PROJECT.
5. RUN-ON AND RUN-OFF CONTROLS SHALL BE IN PLACE AND FUNCTIONING PRIOR TO BEGINNING SUBSTANTIAL CONSTRUCTION ACTIVITIES. RUN-ON AND RUN-OFF CONTROL MEASURES INCLUDE: SLOPE DRAINS (WITH OUTLET PROTECTION), CHECK DAMS, SURFACE ROUGHENING, AND BANK STABILIZATION.


**LEGEND**

- EXISTING CONTOUR MINOR ———— 102 ————
- EXISTING CONTOUR MAJOR ———— 100 ————
- LIMIT OF DISTURBANCE ———— ————
- FLOW ARROW →

**NORTH**



**GRAPHIC SCALE**




**CONSTRUCTION SEQUENCING & STORM FACILITY NOTES**

1. DEMOLITION WILL REMOVE IMPERVIOUS SURFACES. UNTIL NEW IMPERVIOUS SURFACES ARE INSTALLED, STORMWATER WILL BE INFILTRATED IN PLACE. CONTRACTOR TO INSTALL EROSION CONTROL MEASURES AS NEEDED TO PREVENT SEDIMENT LADEN RUNOFF FROM LEAVING THE SITE.

CONTRACTOR SHALL ENSURE THAT POSITIVE DRAINAGE IS MAINTAINED ACROSS EXPOSED AREAS AND NO LOW POINTS ARE CREATED ON-SITE AHEAD OF HOLIDAYS/WEEKENDS OR WHEN THERE IS ANY CHANCE OF RAIN.



F:\2021\A21194.10 - 119 N Pacific Hwy - Woodburn\Civil\Cad\Sheets\202000\A21194-EC2.0 - EC.dwg : Mar. 8, 23 - 1:37 PM jsparrowgrove



**AAI** ajljan associates, inc.  
**ENGINEERING**  
 4875 SW Griffin Drive, Suite 300 | Beaverton, OR 97005  
 503.620.3630 | 503.620.5539 | fax | www.aaieng.com

**119 N PACIFIC HWY**  
 WOODBURN, OR

SHEET TITLE

ESCP DEMO, GRADING,  
 EXCAVATING, AND LAND  
 DEVELOPMENT PLAN

DATE: 12/13/21

DRAWN: JS

CHECKED: CFT

REVISIONS:

© AAI ENGINEERING INC.  
 2023. ALL RIGHTS RESERVED

THESE DRAWINGS ARE THE  
 PROPERTY OF AAI ENGINEERING INC.  
 AND ARE NOT TO BE USED OR  
 REPRODUCED IN ANY MANNER,  
 EXCEPT WITH THE PRIOR WRITTEN  
 PERMISSION OF AAI ENGINEERING INC.

SHEET NUMBER

**EC3.0**

JOB NUMBER: A21194.10

**EROSION CONTROL PLAN NOTES**

1. APPROVAL OF THIS EROSION/SEDIMENTATION CONTROL (ESC) PLAN DOES NOT CONSTITUTE AN APPROVAL OF PERMANENT ROAD OR DRAINAGE DESIGN (E.G., SIZE AND LOCATION OF ROADS, RESTRICTORS, CHANNELS, RETENTION FACILITIES, UTILITIES, ETC.).
2. THE IMPLEMENTATION OF THESE ESC PLANS AND THE CONSTRUCTION, MAINTENANCE, REPLACEMENT, AND UPGRADING OF THESE ESC FACILITIES IS THE RESPONSIBILITY OF THE CONTRACTOR UNTIL ALL CONSTRUCTION IS COMPLETED AND APPROVED AND PERMANENT VEGETATION/LANDSCAPING IS ESTABLISHED.
3. THE BOUNDARIES OF THE CLEARING LIMITS SHOWN ON THIS PLAN SHALL BE CLEARLY FLAGGED IN THE FIELD PRIOR TO CONSTRUCTION. DURING THE CONSTRUCTION PERIOD, NO DISTURBANCE BEYOND THE FLAGGED CLEARING LIMITS SHALL BE PERMITTED. THE FLAGGING SHALL BE MAINTAINED BY THE CONTRACTOR FOR THE DURATION OF CONSTRUCTION.
4. THE ESC FACILITIES SHOWN ON THIS PLAN MUST BE CONSTRUCTED IN CONJUNCTION WITH ALL CLEARING AND GRADING ACTIVITIES, AND IN SUCH A MANNER AS TO ENSURE THAT SEDIMENT AND SEDIMENT LADEN WATER DO NOT ENTER THE DRAINAGE SYSTEM, ROADWAYS, OR VIOLATE APPLICABLE WATER STANDARDS.
5. THE ESC FACILITIES SHOWN ON THIS PLAN ARE THE MINIMUM REQUIREMENTS FOR ANTICIPATED SITE CONDITIONS. DURING THE CONSTRUCTION PERIOD, THESE ESC FACILITIES SHALL BE UPGRADED AS NEEDED FOR UNEXPECTED STORM EVENTS AND TO ENSURE THAT SEDIMENT AND SEDIMENT LADEN WATER DO NOT LEAVE THE SITE.
6. THE ESC FACILITIES SHALL BE INSPECTED DAILY BY THE CONTRACTOR AND MAINTAINED AS NECESSARY TO ENSURE THEIR CONTINUED FUNCTIONING.
7. THE ESC FACILITIES ON INACTIVE SITES MAY REDUCE FREQUENCY OF INSPECTIONS WHERE STABILIZATION STEPS IN SECTION 2.2.20 HAVE BEEN COMPLETED. AFTER BECOMING INACTIVE, THE ESC FACILITIES SHALL BE INSPECTED AND MAINTAINED TWICE THE FIRST MONTH, NO LESS THAN 14 CALENDAR DAYS APART, THEN A MINIMUM OF ONCE A MONTH OR WITHIN THE 24 HOURS FOLLOWING A STORM EVENT.
8. AT NO TIME SHALL MORE THAN ONE FOOT OF SEDIMENT BE ALLOWED TO ACCUMULATE WITHIN A TRAPPED CATCH BASIN. ALL CATCH BASINS AND CONVEYANCE LINES SHALL BE CLEANED PRIOR TO PAVING. THE CLEANING OPERATION SHALL NOT FLUSH SEDIMENT LADEN WATER INTO THE DOWNSTREAM SYSTEM.
9. STABILIZED CONSTRUCTION ENTRANCES SHALL BE INSTALLED AT THE BEGINNING OF CONSTRUCTION AND MAINTAINED FOR THE DURATION OF THE PROJECT. ADDITIONAL MEASURES MAY BE REQUIRED TO ENSURE THAT ALL PAVED AREAS ARE KEPT CLEAN FOR THE DURATION OF THE PROJECT.

**PRE-CONSTRUCTION, CLEARING, AND DEMOLITION NOTES**


1. ALL BASE ESC MEASURES (INLET PROTECTION, PERIMETER SEDIMENT CONTROL, GRAVEL CONSTRUCTION ENTRANCES, ETC.) MUST BE IN PLACE, FUNCTIONAL, AND APPROVED IN AN INITIAL INSPECTION, PRIOR TO COMMENCEMENT OF CONSTRUCTION ACTIVITIES.
2. ALL "SEDIMENT BARRIERS (TO BE INSTALLED AFTER GRADING)" SHALL BE INSTALLED IMMEDIATELY FOLLOWING ESTABLISHMENT OF FINISHED GRADE AS SHOWN ON THESE PLANS.
3. SENSITIVE RESOURCES INCLUDING, BUT NOT LIMITED TO, TREES, WETLANDS, AND RIPARIAN PROTECTION AREAS SHALL BE CLEARLY DELINEATED WITH ORANGE CONSTRUCTION FENCING OR CHAIN LINK FENCING IN A MANNER THAT IS CLEARLY VISIBLE TO ANYONE IN THE AREA. NO ACTIVITIES ARE PERMITTED TO OCCUR BEYOND THE CONSTRUCTION BARRIER.
4. CONSTRUCTION ENTRANCES SHALL BE INSTALLED AT THE BEGINNING OF CONSTRUCTION AND MAINTAINED FOR THE DURATION OF THE PROJECT. ADDITIONAL MEASURES INCLUDING BUT NOT LIMITED TO, STREET SWEEPING, AND VACUUMING MAY BE REQUIRED TO INSURE THAT ALL PAVED AREAS ARE KEPT CLEAN FOR THE DURATION OF THE PROJECT.
5. RUN-ON AND RUN-OFF CONTROLS SHALL BE IN PLACE AND FUNCTIONING PRIOR TO BEGINNING SUBSTANTIAL CONSTRUCTION ACTIVITIES. RUN-ON AND RUN-OFF CONTROL MEASURES INCLUDE: SLOPE DRAINS (WITH OUTLET PROTECTION), CHECK DAMNS, SURFACE ROUGHENING, AND BANK STABILIZATION.

**(X) CONSTRUCTION NOTES**

1. INSTALL CONSTRUCTION ENTRANCE, PER CWS DETAIL 855/EC8.0
2. INSTALL CONCRETE WASHOUT, PER CWS DETAIL 900/EC8.0
3. TEMPORARY STOCKPILE WITH PLASTIC SHEETING, PER CWS DETAIL 810/EC8.0
4. STAGING AND MATERIAL STORAGE

**LEGEND**

EXISTING CONTOUR MINOR	---	102	---
EXISTING CONTOUR MAJOR	---	100	---
PROPOSED CONTOUR MAJOR	---	102	---
PROPOSED CONTOUR MINOR	---	100	---
LIMIT OF DISTURBANCE	[Thick dashed line symbol]		
SEDIMENT FENCE PER CWS DETAIL 875/EC8.0	[Dashed line with circles symbol]		
CONSTRUCTION ENTRANCE PER CWS DETAIL 855/EC8.0	[Stippled area symbol]		
CONCRETE WASHOUT PER CWS DETAIL 900/EC8.0	[Square with 'x' symbol]		
FLOW ARROW (FG)	[Arrow symbol]		
AREA OF CUT	[Light gray shaded area symbol]		
AREA OF FILL	[Dark gray shaded area symbol]		
INLET PROTECTION PER CWS DETAIL 920/EC8.0	[Circle with 'x' symbol]		




**CONSTRUCTION SEQUENCING & STORM FACILITY NOTES**

1. DEMOLITION WILL REMOVE IMPERVIOUS SURFACES. UNTIL NEW IMPERVIOUS SURFACES ARE INSTALLED, STORMWATER WILL BE INFILTRATED IN PLACE. CONTRACTOR TO INSTALL EROSION CONTROL MEASURES AS NEEDED TO PREVENT SEDIMENT LADEN RUNOFF FROM LEAVING THE SITE.
2. STRAW MULCH AND/OR HYDROSEED SHALL BE USED FOR TEMPORARY STABILIZATION OF EXPOSED SOILS AFTER EXCAVATION.

CONTRACTOR SHALL ENSURE THAT POSITIVE DRAINAGE IS MAINTAINED ACROSS EXPOSED AREAS AND NO LOW POINTS ARE CREATED ON-SITE AHEAD OF HOLIDAYS/WEEKENDS OR WHEN THERE IS ANY CHANCE OF RAIN.

**GRADING PHASE INFORMATION**

1. ONSITE SOIL TYPES:  
 SOIL TYPE - AMITY SILT LOAM  
 0.5 TO 7.14 PERCENT SLOPES: PERCENTAGE OF SITE (%)
2. EXISTING VEGETATION CONSISTS OF TALL GRASS
3. CUT AND FILL DATA:  
 - CUT: 135 CU. YD  
 - FILL: 1320 CU. YD  
 - NET ADJUSTED: 1185 CU. YD (FILL)
4. ONSITE FILL MATERIALS:  
 - NATIVE SOIL  
 - CRUSHED ROCK
5. PHASE SCHEDULE:  
 - 06/23 TO 08/23







**AAI** align associates, inc.  
**ENGINEERING**  
 4875 SW Griffin Drive, Suite 300 | Beaverton, OR 97005  
 503.620.3630 | 503.620.5539 | www.aaieng.com

**119 N PACIFIC HWY**  
 WOODBURN, OR

SHEET TITLE  
 ESCP STREET AND UTILITIES  
 DATE: 12/13/21  
 DRAWN: JS  
 CHECKED: CFT  
 REVISIONS:  
 © AAI ENGINEERING INC. 2023. ALL RIGHTS RESERVED.  
 THESE DRAWINGS ARE THE PROPERTY OF AAI ENGINEERING INC. AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER, EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF AAI ENGINEERING INC.  
 SHEET NUMBER

**EC4.0**

JOB NUMBER: A21194.10

**UTILITIES PHASE NOTES**

1. STORMWATER TO BE INFILTRATED IN PLACE DURING CONSTRUCTION. PROTECT DOWNSTREAM CATCH BASINS.
2. ANY TRENCH DEWATERING SHALL BE DONE SO THE WATER INFILTRATES ON SITE.
3. STRAW MULCH AND/OR HYDROSEED SHALL BE USED FOR TEMPORARY STABILIZATION OF ANY EXPOSED TRENCH SPOILS (INCLUDING STOCKPILE IF PLASTIC SHEETING DOESN'T WORK).

**UTILITIES PHASE INFORMATION**

1. PHASE SCHEDULE:  
 - 08/23 TO 10/23

**PRE-CONSTRUCTION, CLEARING, AND DEMOLITION NOTES**

1. ALL BASE ESC MEASURES (INLET PROTECTION, PERIMETER SEDIMENT CONTROL, GRAVEL CONSTRUCTION ENTRANCES, ETC.) MUST BE IN PLACE, FUNCTIONAL, AND APPROVED IN AN INITIAL INSPECTION, PRIOR TO COMMENCEMENT OF CONSTRUCTION ACTIVITIES.
2. ALL "SEDIMENT BARRIERS (TO BE INSTALLED AFTER GRADING)" SHALL BE INSTALLED IMMEDIATELY FOLLOWING ESTABLISHMENT OF FINISHED GRADE AS SHOWN ON THESE PLANS.
3. SENSITIVE RESOURCES INCLUDING, BUT NOT LIMITED TO, TREES, WETLANDS, AND RIPARIAN PROTECTION AREAS SHALL BE CLEARLY DELINEATED WITH ORANGE CONSTRUCTION FENCING OR CHAIN LINK FENCING IN A MANNER THAT IS CLEARLY VISIBLE TO ANYONE IN THE AREA. NO ACTIVITIES ARE PERMITTED TO OCCUR BEYOND THE CONSTRUCTION BARRIER.
4. CONSTRUCTION ENTRANCES SHALL BE INSTALLED AT THE BEGINNING OF CONSTRUCTION AND MAINTAINED FOR THE DURATION OF THE PROJECT. ADDITIONAL MEASURES INCLUDING BUT NOT LIMITED TO, STREET SWEEPING, AND VACUUMING MAY BE REQUIRED TO INSURE THAT ALL PAVED AREAS ARE KEPT CLEAN FOR THE DURATION OF THE PROJECT.
5. RUN-ON AND RUN-OFF CONTROLS SHALL BE IN PLACE AND FUNCTIONING PRIOR TO BEGINNING SUBSTANTIAL CONSTRUCTION ACTIVITIES. RUN-ON AND RUN-OFF CONTROL MEASURES INCLUDE: SLOPE DRAINS (WITH OUTLET PROTECTION), CHECK DAMS, SURFACE ROUGHENING, AND BANK STABILIZATION.




**(X) CONSTRUCTION NOTES**

1. INSTALL CONSTRUCTION ENTRANCE, PER CWS DETAIL 855/EC8.0
2. INSTALL CONCRETE WASHOUT, PER CWS DETAIL 900/EC8.0
3. TEMPORARY STOCKPILE WITH PLASTIC SHEETING, PER CWS DETAIL 810/EC8.0
4. STAGING AND MATERIAL STORAGE

**LEGEND**

EXISTING CONTOUR MINOR	---	-102-
EXISTING CONTOUR MAJOR	---	100
PROPOSED CONTOUR MAJOR	---	102
PROPOSED CONTOUR MINOR	---	100
LIMIT OF DISTURBANCE	---	-----
SEDIMENT FENCE PER CWS DETAIL 875/EC8.0	---	-----
CONSTRUCTION ENTRANCE PER CWS DETAIL 855/EC8.0	---	-----
CONCRETE WASHOUT PER CWS DETAIL 900/EC8.0	---	---
INLET PROTECTION PER CWS DETAIL 920/EC8.0	---	---

CONTRACTOR SHALL ENSURE THAT POSITIVE DRAINAGE IS MAINTAINED ACROSS EXPOSED AREAS AND NO LOW POINTS ARE CREATED ON-SITE AHEAD OF HOLIDAYS/WEEKENDS OR WHEN THERE IS ANY CHANCE OF RAIN.



F:\2021\A21194.10 - 119 N Pacific Hwy - Woodburn\Civil\Cad\Sheets\2020\A21194-EC4.0 - UTILITY.dwg - Mar. 8. 23 - 1:38 PM jsparron@grove



**AAI** ajghan associates, inc.  
**ENGINEERING**  
 4875 SW Griffin Drive, Suite 300 | Beaverton, OR 97005  
 503.620.3630 | 503.620.5539 | www.aaing.com

**119 N PACIFIC HWY**  
 WOODBURN, OR


SHEET TITLE  
 ESCP OFFSITE PACIFIC HWY PLAN

DATE: 12/13/21  
 DRAWN: JS  
 CHECKED: CFT

REVISIONS:

© AAI ENGINEERING INC. 2023. ALL RIGHTS RESERVED.  
 THESE DRAWINGS ARE THE PROPERTY OF AAI ENGINEERING INC. AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER, EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF AAI ENGINEERING INC.

SHEET NUMBER



STATE HWY 99E

**OFFSITE PHASE NOTES**

1. NO DISTURBANCE SHALL TAKE PLACE OUTSIDE OF SEDIMENT FENCING.
2. CONCRETE WASHOUT FOR ALL CONCRETE WORK IS ONSITE AS SHOWN ON SHEET EC-3.0.
3. CATCH BASIN FILTER INSERTS TO REMAIN UNTIL THE COMPLETION OF THE OFFSITE PHASE.

**OFFSITE PHASE INFORMATION**

1. PHASE SCHEDULE:  
 - 8/23 TO 9/23


**PRE-CONSTRUCTION, CLEARING, AND DEMOLITION NOTES**

1. ALL BASE ESC MEASURES (INLET PROTECTION, PERIMETER SEDIMENT CONTROL, GRAVEL CONSTRUCTION ENTRANCES, ETC.) MUST BE IN PLACE, FUNCTIONAL, AND APPROVED IN AN INITIAL INSPECTION, PRIOR TO COMMENCEMENT OF CONSTRUCTION ACTIVITIES.
2. ALL "SEDIMENT BARRIERS (TO BE INSTALLED AFTER GRADING)" SHALL BE INSTALLED IMMEDIATELY FOLLOWING ESTABLISHMENT OF FINISHED GRADE AS SHOWN ON THESE PLANS.
3. SENSITIVE RESOURCES INCLUDING, BUT NOT LIMITED TO, TREES, WETLANDS, AND RIPARIAN PROTECTION AREAS SHALL BE CLEARLY DELINEATED WITH ORANGE CONSTRUCTION FENCING OR CHAIN LINK FENCING IN A MANNER THAT IS CLEARLY VISIBLE TO ANYONE IN THE AREA. NO ACTIVITIES ARE PERMITTED TO OCCUR BEYOND THE CONSTRUCTION BARRIER.
4. CONSTRUCTION ENTRANCES SHALL BE INSTALLED AT THE BEGINNING OF CONSTRUCTION AND MAINTAINED FOR THE DURATION OF THE PROJECT. ADDITIONAL MEASURES INCLUDING BUT NOT LIMITED TO, STREET SWEEPING, AND VACUUMING MAY BE REQUIRED TO INSURE THAT ALL PAVED AREAS ARE KEPT CLEAN FOR THE DURATION OF THE PROJECT.
5. RUN-ON AND RUN-OFF CONTROLS SHALL BE IN PLACE AND FUNCTIONING PRIOR TO BEGINNING SUBSTANTIAL CONSTRUCTION ACTIVITIES. RUN-ON AND RUN-OFF CONTROL MEASURES INCLUDE: SLOPE DRAINS (WITH OUTLET PROTECTION), CHECK DAMS, SURFACE ROUGHENING, AND BANK STABILIZATION.

**LEGEND**

EXISTING CONTOUR MINOR	---	102	---
EXISTING CONTOUR MAJOR	---	100	---
PROPOSED CONTOUR MAJOR	---	102	---
PROPOSED CONTOUR MINOR	---	100	---
LIMIT OF DISTURBANCE	[Thick dashed line]		
SEDIMENT FENCE PER CWS DETAIL 875/EC8.0	[Dashed line with circles]		
CONSTRUCTION ENTRANCE PER CWS DETAIL 855/EC8.0	[Stippled area]		
CONCRETE WASHOUT PER CWS DETAIL 900/EC8.0	[Dashed line with squares]		
INLET PROTECTION PER CWS DETAIL 920/EC8.0	[Circle]		

CONTRACTOR SHALL ENSURE THAT POSITIVE DRAINAGE IS MAINTAINED ACROSS EXPOSED AREAS AND NO LOW POINTS ARE CREATED ON-SITE AHEAD OF HOLIDAYS/WEEKENDS OR WHEN THERE IS ANY CHANCE OF RAIN.



**VERTICAL CONSTRUCTION PHASE NOTES**

1. PROTECT INSTALLED STORM AND SANITARY CATCHBASINS UNTIL PROJECT IS COMPLETE.
2. ALL CONSTRUCTION MATERIALS THAT COULD LEAD TO POLLUTION IF SPILLED NOT IN IMMEDIATE USE SHALL BE STORED IN A STORAGE BOX ON SITE IN A LOCATION WITH MINIMAL CONSTRUCTION ACTIVITY TO PREVENT SPILLS AND EXPOSURE TO WET WEATHER.
3. FOR SPILL PREVENTION (SPILL KITS AND OTHER SPILL CONTAINMENT DEVICES (I.E. WATTLES, ABSORBENT SOCKS/BOOMS, ORGANIC OIL ABSORBENT AGENT, ETC.) SHALL BE KEPT ONSITE WITHIN THE STORAGE CONTAINER MENTIONED ABOVE THROUGH THE COMPLETION OF THE PROJECT.

**VERTICAL CONSTRUCTION PHASE INFORMATION**

1. PHASE SCHEDULE:  
- 10/23 TO 08/24

**LEGEND**

- LIMIT OF DISTURBANCE
- SEDIMENT FENCE PER CWS DETAIL 875/EC8.0
- CONSTRUCTION ENTRANCE PER CWS DETAIL 855/EC8.0
- CONCRETE WASHOUT PER CWS DETAIL 900/EC8.0
- INLET PROTECTION PER CWS DETAIL 920/EC8.0

CONTRACTOR SHALL ENSURE THAT POSITIVE DRAINAGE IS MAINTAINED ACROSS EXPOSED AREAS AND NO LOW POINTS ARE CREATED ON-SITE AHEAD OF HOLIDAYS/WEEKENDS OR WHEN THERE IS ANY CHANCE OF RAIN.



**AAI** ajigan associates, inc.  
**ENGINEERING**  
4875 SW Griffin Drive, Suite 300 | Beaverton, OR 97005  
503.820.3630 | 503.820.5539 | www.aaieng.com

**119 N PACIFIC HWY**  
WOODBURN, OR

SHEET TITLE

ESCP VERTICAL CONSTRUCTION PLAN

DATE: 12/13/21

DRAWN: JS

CHECKED: CFT

REVISIONS:


© AAI ENGINEERING INC. 2023. ALL RIGHTS RESERVED.

THESE DRAWINGS ARE THE PROPERTY OF AAI ENGINEERING INC. AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER, EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF AAI ENGINEERING INC.


SHEET NUMBER

**EC6.0**

JOB NUMBER: A21194.10



F:\2021\A21194.10 - 119 N Pacific Hwy-Woodburn\Civil\_Cad\Sheets\2020\A21194-EC6.0 - VERT CONSTR.dwg : Mr. B. 23 - 1:38 PM jsparrowgrove




**FINAL STABILIZATION PHASE NOTES**

1. ALL PERIMETER SEDIMENT FENCING AND CATCHBASIN FILTER INSERTS TO BE REMOVED UPON COMPLETION OF THIS PHASE.

**FINAL STABILIZATION PHASE INFORMATION**

1. PHASE SCHEDULE:  
- 08/24 TO 10/24

CONTRACTOR SHALL ENSURE THAT POSITIVE DRAINAGE IS MAINTAINED ACROSS EXPOSED AREAS AND NO LOW POINTS ARE CREATED ON-SITE AHEAD OF HOLIDAYS/WEEKENDS OR WHEN THERE IS ANY CHANCE OF RAIN.



**AAI** ajghan associates, inc.  
**ENGINEERING**  
4875 SW Griffin Drive, Suite 300 | Beaverton, OR 97005  
503.620.3630 | 503.620.5539 | www.aaieng.com

**119 N PACIFIC HWY**  
WOODBURN, OR

SHEET TITLE

ESCP FINAL  
LANDSCAPING AND  
STABILIZATION PLAN

DATE: 12/13/21

DRAWN: JS

CHECKED: CFT

REVISIONS:


© AAI ENGINEERING INC.  
2023. ALL RIGHTS RESERVED


THESE DRAWINGS ARE THE  
PROPERTY OF AAI ENGINEERING INC.  
AND ARE NOT TO BE USED OR  
REPRODUCED IN ANY MANNER,  
EXCEPT WITH THE PRIOR WRITTEN  
PERMISSION OF AAI ENGINEERING INC.

SHEET NUMBER


**EC7.0**

JOB NUMBER: A21194.10







PLASTIC SHEETING  
DRAWING NO. 810  
REVISED 10-31-19  
CleanWater Services




CONSTRUCTION ENTRANCE  
DRAWING NO. 855  
REVISED 10-31-19  
CleanWater Services



SEDIMENT FENCE  
DRAWING NO. 875  
REVISED 10-31-19  
CleanWater Services



CONCRETE WASHOUT  
DRAWING NO. 900  
REVISED 10-31-19  
CleanWater Services



INLET PROTECTION TYPE 5  
DRAWING NO. 920  
REVISED 10-31-19  
CleanWater Services

GENERAL EROSION CONTROL NOTES:

- COMPLY WITH ALL APPLICABLE PROVISIONS IN CHAPTER 6 OF THE DESIGN AND CONSTRUCTION STANDARDS (CURRENT); R&O 19-5 AS AMENDED BY R&O 19-22, ADOPTED NOVEMBER 12, 2019.
- ALL PUMPING OF SEDIMENT LADEN WATER SHALL BE DISCHARGED OVER AN UNDISTURBED, PREFERABLY VEGETATED AREA, AND THROUGH A SEDIMENT CONTROL BMP LIKE A FILTER BAG.
- ALL EXPOSED SOILS MUST BE COVERED DURING WET WEATHER PERIOD, OCTOBER 1, - MAY 31.
- HOLD A PRECONSTRUCTION MEETING WITH PROJECT CONSTRUCTION PERSONNEL THAT INCLUDES THE INSPECTOR TO DISCUSS EROSION AND SEDIMENT CONTROL MEASURES AND CONSTRUCTION LIMITS.

PRE-CONSTRUCTION, CLEARING, AND DEMOLITION NOTES:

- SEDIMENT BARRIERS APPROVED FOR USE INCLUDE SEDIMENT FENCE, BERMS CONSTRUCTED OUT OF MULCH, CHIPPINGS, STRAW WATTLES OR OTHER APPROVED MATERIALS.
- ALL BASE ESC MEASURES (INLET PROTECTION, PERIMETER SEDIMENT CONTROL, GRAVEL CONSTRUCTION ENTRANCES, ETC.) MUST BE IN PLACE, FUNCTIONAL AND APPROVED IN AN INITIAL INSPECTION PRIOR TO COMMENCEMENT OF CONSTRUCTION ACTIVITIES.
- RUN-ON AND RUN-OFF SHALL BE IN PLACE AND FUNCTIONING PRIOR TO BEGINNING SUBSTANTIAL CONSTRUCTION ACTIVITIES. RUN-ON AND RUN-OFF CONTROL MEASURES INCLUDE: SLOPE DRAINS (WITH OUTLET PROTECTION), CHECK DAMS, SURFACE ROUGHENING, AND BANK STABILIZATION.

GRADING, STREET AND UTILITY EROSION AND SEDIMENT CONSTRUCTION NOTES:

- IF VEGETATED SEED MIXES ARE SPECIFIED, SEEDING MUST TAKE PLACE NO LATER THAN SEPTEMBER 1ST. VEGETATED CORRIDOR AREAS REQUIRE NATIVE SEED MIXES. SEE RESTORATION PLAN FOR APPROPRIATE SEED MIX IN THOSE AREAS. SEED USED FOR TEMPORARY OR PERMANENT SEEDING OUTSIDE VEGETATED CORRIDORS SHALL BE COMPOSED OF ONE OF THE FOLLOWING MIXTURES, UNLESS OTHERWISE AUTHORIZED:
 

A. DWARF GRASS MIX (MIN. 100 LB./AC.)	B. STANDARD HEIGHT GRASS MIX (MIN. 100LB/AC)
1. DWARF PERENNIAL RYEGRASS (80% BY WEIGHT)	1. ANNUAL RYEGRASS (40% BY WEIGHT)
2. CREEPING RED FESCUE (20% BY WEIGHT)	2. TURF-TYPE FESCUE (60% BY WEIGHT)
- SLOPE TO RECEIVE TEMPORARY OR PERMANENT SEEDING HAVE THE SURFACE ROUGHENED BY MEANS OF TRACK-WALKING OR THE USE OF OTHER APPROVED IMPLEMENTS. SURFACE ROUGHENING IMPROVES SEED BEDDING AND REDUCES RUN-OFF VELOCITY.
- LONG TERM SLOPE STABILIZATION MEASURES SHALL INCLUDE THE ESTABLISHMENT OF PERMANENT VEGETATIVE COVER VIA SEEDING WITH APPROVED MIX AND APPLICATION RATE.
- TEMPORARY SLOPE STABILIZATION MEASURES SHALL INCLUDE: COVERING EXPOSED SOIL WITH PLASTIC SHEETING, STRAW MULCHING, WOOD CHIPS, OR OTHER APPROVED MEASURES.
- STOCKPILED SOIL OR STRIPPINGS SHALL BE PLACED IN A STABLE LOCATION AND CONFIGURATION. DURING "WET WEATHER" PERIODS, STOCKPILES SHALL BE COVERED WITH PLASTIC SHEETING OR STRAW MULCH. SEDIMENT FENCE IS REQUIRED AROUND THE PERIMETER OF THE STOCKPILE.
- EXPOSED CUT OR FILL AREAS SHALL BE STABILIZED THROUGH THE USE OF TEMPORARY SEEDING AND MULCHING, EROSION CONTROL BLANKETS OR MATS, MID-SLOPE SEDIMENT FENCES OR WATTLES, OR OTHER APPROPRIATE MEASURES. SLOPES EXCEEDING 25% MAY REQUIRE ADDITIONAL EROSION CONTROL MEASURES.
- AREAS SUBJECT TO WIND EROSION SHALL USE APPROPRIATE DUST CONTROL MEASURES INCLUDING THE APPLICATION OF A FINE SPRAY OF WATER, PLASTIC SHEETING, STRAW MULCHING, OR OTHER APPROVED MEASURES.
- CONSTRUCTION ENTRANCES SHALL BE INSTALLED AT THE BEGINNING OF CONSTRUCTION AND MAINTAINED FOR THE DURATION OF THE PROJECT. ADDITIONAL MEASURES INCLUDING, BUT NOT LIMITED TO, TIRE WASHES, STREET SWEEPING, AND VACUUMING MAY BE REQUIRED TO ENSURE THAT ALL PAVED AREAS ARE KEPT CLEAN FOR THE DURATION OF THE PROJECT.
- USE BMP'S SUCH AS CHECK-DAMS, BERMS, AND INLET PROTECTION TO PREVENT RUN-OFF FROM REACHING DISCHARGE POINTS.
- COVER CATCH BASINS, MANHOLES AND OTHER DISCHARGE POINTS WHEN APPLYING SEAL COAT, TACT COAT ETC. TO PREVENT PRODUCTS FROM ENTERING THE STORM SYSTEM.


EROSION AND SEDIMENT CONTROL BMP IMPLEMENTATION:

- ALL SEDIMENT BARRIERS TO BE INSTALLED AFTER GRADING SHALL BE INSTALLED IMMEDIATELY FOLLOWING ESTABLISHMENT OF FINISHED GRADE AS SHOWN ON THESE PLANS.
- LONG TERM SLOPE STABILIZATION MEASURES "INCLUDING MATTING" SHALL BE IN PLACE OVER ALL EXPOSED SOILS BY OCTOBER 1.
- THE STORM WATER FACILITY SHALL BE CONSTRUCTED AND LANDSCAPED PRIOR TO THE STORM WATER SYSTEM FUNCTIONING AND SITE PAVING.
- INLET PROTECTION SHALL BE IN-PLACE IMMEDIATELY FOLLOWING PAVING ACTIVITIES.

STANDARD EROSION CONTROL NOTES FOR SITES 1 ACRE AND GREATER  
DRAWING NO. 946  
REVISED 6-30-21  
CleanWater Services

# Onsite Plans

# 119 N PACIFIC HWY WOODBURN, OREGON



119 N PACIFIC HWY  
WOODBURN, OR 97071  
LATITUDE = 45° 8' 11.13"  
LONGITUDE = -122° 50' 42.65"  
**LEGAL DESCRIPTION:**  
TAX LOT 7500  
MAP NW1/4 SEC. 17, T5S, R1W, W.M.

**PROPERTY DESCRIPTION:**  
LOCATED IN THE NORTHWEST ONE-QUARTER  
OF SECTION 17, TOWNSHIP 5 SOUTH, RANGE 1  
WEST, OF THE WILLAMETTE MERIDIAN, CITY OF  
WOODBURN, MARION COUNTY, OREGON



**AAI** ajghian associates, inc.  
**ENGINEERING**  
4875 SW Griffith Drive, Suite 300 | Beaverton, OR 97005  
503.620.3630 | 503.620.5539 | fax | www.aaieng.com

**AAI ENGINEERING** **CIVIL ENGINEER**

CONTACT: CHRISTOPHER THORNTON, PE  
4875 SW GRIFFITH DRIVE, SUITE 100  
BEAVERTON, OREGON 97005  
PH: 503-352-7686  
FAX: 503-620-5539  
EMAIL: CHRISTOPHERT@AAIENG.COM

**STUDIO 3** **ARCHITECT**

CONTACT: JIM TOPOREK  
275 COURT STREET NE  
SALEM, OR 97301  
PHONE: 503-390-6500  
EMAIL: JIM@STUDIO3ARCHITECTURE.COM

**LAZER SITE SURVEYING** **SURVEYOR**

2003 25TH STREET SE SALEM, OR 97302  
PHONE: 503-581-6362

**119 N PACIFIC HWY**  
WOODBURN, OR

SHEET TITLE

**COVER SHEET**

DATE: 12/13/21

DRAWN: JS

CHECKED: CFT

REVISIONS:

© AAI ENGINEERING INC.  
2023. ALL RIGHTS RESERVED


THESE DRAWINGS ARE THE  
PROPERTY OF AAI ENGINEERING INC.  
AND ARE NOT TO BE USED OR  
REPRODUCED IN ANY MANNER,  
EXCEPT WITH THE PRIOR WRITTEN  
PERMISSION OF AAI ENGINEERING INC.

SHEET NUMBER

**C0.0**


JOB NUMBER: A21194.10

**NORTH**  
**VICINITY MAP**  
SCALE: NTS



**NORTH**  
**SITE PLAN**  
SCALE: 1" = 30'

SHEET LIST TABLE	
SHEET NUMBER	SHEET TITLE
C0.0	COVER SHEET
C0.1	GENERAL NOTES
C0.2	EXISTING CONDITIONS PLAN
C0.3	DEMOLITION PLAN
C1.0	HARDSCAPE PLAN
C2.0	GRADING PLAN
C3.0	STORMWATER PLAN
C3.1	WATER AND SANITARY PLAN
C4.0	DETAILS
C4.1	DETAILS
C4.2	DETAILS
C4.3	DETAILS



**AAI** ajghian associates, inc.  
**ENGINEERING**  
 4875 SW Griffin Drive, Suite 300 | Beaverton, OR 97005  
 503.620.3630 | 503.620.5539 | www.aaieng.com

**119 N PACIFIC HWY**  
 WOODBURN, OR

SHEET TITLE

**GENERAL NOTES**

DATE: 12/13/21

DRAWN: JS

CHECKED: CFT

REVISIONS:

AAI ENGINEERING INC.  
 2023, ALL RIGHTS RESERVED

THESE DRAWINGS ARE THE PROPERTY OF AAI ENGINEERING INC. AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER, EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF AAI ENGINEERING INC.

SHEET NUMBER

**C0.1**

JOB NUMBER: A21194.10

**MATERIAL NOTES**

- GENERAL: MATERIALS SHALL BE NEW. THE USE OF MANUFACTURER'S NAMES, MODELS, AND NUMBERS IS INTENDED TO ESTABLISH STYLE, QUALITY, APPEARANCE, AND USEFULNESS. PROPOSED SUBSTITUTIONS WILL REQUIRE WRITTEN APPROVAL FROM ENGINEER PRIOR TO INSTALLATION.
- STORM AND SANITARY SEWER PIPING SHALL BE PVC PIPE AS INDICATED IN THE PLANS. PIPES WITH LESS THAN 2' OF COVER SHALL BE C900/C905 PVC, HDPE OR DUCTILE IRON PIPE.
- PRIVATE WATER MAINS 4-INCH DIAMETER AND LARGER SHALL BE DUCTILE IRON PIPE SCH 52 OR C900; AS INDICATED IN THE PLANS.
- PRIVATE WATER LINES 3-INCH DIAMETER AND SMALLER SHALL BE TYPE K COPPER OR PVC; AS INDICATED IN THE PLANS.
- CONCRETE FOR CURBS, SIDEWALK AND DRIVEWAYS SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 3,500 PSI AT 28 DAYS.

**SEPARATION STATEMENT**

ALL WATER MAIN CROSSINGS SHALL CONFORM TO THE OREGON STATE HEALTH DEPARTMENT, CHAPTER 333. WATER MAINS SHALL CROSS OVER SANITARY SEWERS WITH A 18" MINIMUM CLEARANCE BETWEEN OUTSIDE DIAMETERS OF PIPE WITH ALL PIPE JOINTS EQUIDISTANT FROM CROSSING. HORIZONTAL SEPARATION BETWEEN WATER MAINS AND SANITARY SEWERS IN PARALLEL INSTALLATIONS SHALL BE 10'. MAINTAIN 12" MINIMUM VERTICAL DISTANCE FOR ALL OTHER UTILITY CROSSINGS AND 12" HORIZONTAL PARALLEL DISTANCE. IN CASES WHERE IT IS NOT POSSIBLE TO MAINTAIN THE MINIMUM 10' HORIZONTAL SEPARATION, THE WATER MAIN SHALL BE LAID ON A SEPARATE SHELF IN THE TRENCH 18" INCHES ABOVE THE SEWER.

**CONSTRUCTION NOTES**

**DEMOLITION**

- THE CONTRACTOR SHALL BE RESPONSIBLE FOR DEMOLITION AND DISPOSAL OF EXISTING AC, CURBS, SIDEWALKS AND OTHER SITE ELEMENTS WITHIN THE SITE AREA IDENTIFIED IN THE PLANS.
- EXCEPT FOR MATERIALS INDICATED TO BE STOCKPILED OR TO REMAIN ON OWNER'S PROPERTY, CLEARED MATERIALS SHALL BECOME CONTRACTOR'S PROPERTY, REMOVED FROM THE SITE, AND DISPOSED OF PROPERLY.
- ITEMS INDICATED TO BE SALVAGED SHALL BE CAREFULLY REMOVED AND DELIVERED STORED AT THE PROJECT SITE AS DIRECTED BY THE OWNER.
- ALL LANDSCAPING, PAVEMENT, CURBS AND SIDEWALKS, BEYOND THE IDENTIFIED SITE AREA, DAMAGED DURING THE CONSTRUCTION SHALL BE REPLACED TO THEIR ORIGINAL CONDITION OR BETTER.
- CONCRETE SIDEWALKS SHOWN FOR DEMOLITION SHALL BE REMOVED TO THE NEAREST EXISTING CONSTRUCTION JOINT.
- SAWCUT STRAIGHT MATCHLINES TO CREATE A BUTT JOINT BETWEEN THE EXISTING AND NEW PAVEMENT.

**UTILITIES**

- ADJUST ALL INCIDENTAL STRUCTURES, MANHOLES, VALVE BOXES, CATCH BASINS, FRAMES AND COVERS, ETC. TO FINISHED GRADE.
- CONTRACTOR SHALL ADJUST ALL EXISTING AND/OR NEW FLEXIBLE UTILITIES (WATER, TV, TELEPHONE, ELEC., ETC.) TO CLEAR ANY EXISTING OR NEW GRAVITY DRAIN UTILITIES (STORM DRAIN, SANITARY SEWER, ETC.) IF CONFLICT OCCURS.
- CONTRACTOR SHALL COORDINATE WITH PRIVATE UTILITY COMPANIES FOR THE INSTALLATION OF OR ADJUSTMENT TO GAS, ELECTRICAL, POWER AND TELEPHONE SERVICE.
- BEFORE BACKFILLING ANY SUBGRADE UTILITY IMPROVEMENTS CONTRACTOR SHALL SURVEY AND RECORD MEASUREMENTS OF EXACT LOCATION AND DEPTH AND SUBMIT TO ENGINEER AND OWNER.

**STORM AND SANITARY**

- CONNECTIONS TO EXISTING STORM AND SANITARY SEWERS SHALL CONFORM TO THE 2021 OREGON STANDARD SPECIFICATIONS FOR CONSTRUCTION, SECTION 00490, "WORK ON EXISTING SEWERS AND STRUCTURES".
- BEGIN LAYING STORM DRAIN AND SANITARY SEWER PIPE AT THE LOW POINT OF THE SYSTEM, TRUE TO GRADE AND ALIGNMENT INDICATED WITH UNBROKEN CONTINUITY OF INVERT. THE CONTRACTOR SHALL ESTABLISH LINE AND GRADE FOR THE STORM AND SANITARY SEWER PIPE USING A LASER.
- ALL ROOF DRAIN AND CATCH BASIN LEADERS SHALL HAVE A MINIMUM SLOPE OF 1 PERCENT UNLESS NOTED OTHERWISE IN THE PLANS.
- ALL STORM AND SANITARY FITTINGS TO BE ECCENTRIC FITTINGS UNLESS OTHERWISE NOTED.

**WATER**

- ALL WATER AND FIRE PROTECTION PIPE SHALL HAVE A MINIMUM 36-INCH COVER TO THE FINISH GRADE.
- ALL WATER AND FIRE PRESSURE FITTINGS SHALL BE PROPERLY RESTRAINED WITH THRUST BLOCKS PER DETAIL.
- ALL WATER MAIN / SANITARY SEWER CROSSINGS SHALL CONFORM TO THE OREGON STATE HEALTH DEPARTMENT REGULATIONS, CHAPTER 333.

**EARTHWORKS**

- CONTRACTOR SHALL PREVENT SEDIMENTS AND SEDIMENT LADEN WATER FROM ENTERING THE STORM DRAINAGE SYSTEM.
- TRENCH BEDDING AND BACKFILL SHALL BE AS SHOWN ON THE PIPE BEDDING AND BACKFILL DETAIL, THE PROJECT SPECIFICATIONS AND AS REQUIRED IN THE SOILS REPORT. FLOODING OR JETTING THE BACKFILLED TRENCHES WITH WATER WILL NOT BE PERMITTED.
- SUBGRADE AND TRENCH BACKFILL SHALL BE COMPACTED TO AT LEAST 95% OF THE MAXIMUM DRY DENSITY AS DETERMINED BY ASTM D-698. FLOODING OR JETTING THE BACKFILLED TRENCHES WITH WATER IS NOT PERMITTED.

**PAVING**

- SEE ARCHITECTURAL PLANS FOR SIDEWALK FINISHING AND SCORING PATTERNS.

**GENERAL NOTES**

- CONSTRUCTION LAYOUT (ALL ACTUAL LINES AND GRADES) SHALL BE STAKED BY A PROFESSIONAL SURVEYOR, REGISTERED IN THE STATE OF OREGON, BASED ON COORDINATES, DIMENSIONS, BEARINGS, AND ELEVATIONS, AS SHOWN, ON THE PLANS.
- PROJECT CONTROL SHALL BE FIELD VERIFIED AND CHECKED FOR RELATIVE HORIZONTAL POSITION PRIOR TO BEGINNING CONSTRUCTION LAYOUT.
- PROJECT CONTROL SHALL BE FIELD VERIFIED AND CHECKED FOR RELATIVE VERTICAL POSITION BASED ON THE BENCHMARK STATED HEREON, PRIOR TO BEGINNING CONSTRUCTION LAYOUT.
- WHEN DIMENSIONS AND COORDINATE LOCATIONS ARE REPRESENTED – DIMENSIONS SHALL HOLD OVER COORDINATE LOCATION. NOTIFY THE CIVIL ENGINEER OF RECORD IMMEDIATELY UPON DISCOVERY.
- BUILDING SETBACK DIMENSIONS FROM PROPERTY LINES SHALL HOLD OVER ALL OTHER CALLOUTS. PROPERTY LINES AND ASSOCIATED BUILDING SETBACKS SHALL BE VERIFIED PRIOR TO CONSTRUCTION LAYOUT.
- CONTRACTOR SHALL PRESERVE AND PROTECT FROM DAMAGE ALL EXISTING MONUMENTATION DURING CONSTRUCTION. THE CONTRACTOR IS RESPONSIBLE FOR COORDINATING AND PAYING FOR THE REPLACEMENT OF ANY MONUMENTS DAMAGED OR REMOVED DURING CONSTRUCTION. NEW MONUMENTS SHALL BE REESTABLISHED BY A LICENSED SURVEYOR.
- ALL CONSTRUCTION AND MATERIALS SHALL CONFORM TO THESE PLANS, THE PROJECT SPECIFICATIONS AND THE APPLICABLE REQUIREMENTS OF THE 2018 OREGON STANDARD SPECIFICATIONS FOR CONSTRUCTION, THE 2017 OREGON PLUMBING SPECIALTY CODE AND LOCAL JURISDICTION REQUIREMENTS.
- THE COMPLETED INSTALLATION SHALL CONFORM TO ALL APPLICABLE FEDERAL, STATE, AND LOCAL CODES, ORDINANCES AND REGULATIONS. ALL PERMITS, LICENSES AND INSPECTIONS REQUIRED BY THE GOVERNING AUTHORITIES FOR THE EXECUTION AND COMPLETION OF WORK SHALL BE SECURED BY THE CONTRACTOR PRIOR TO COMMENCING CONSTRUCTION.
- ATTENTION: OREGON LAW REQUIRES YOU TO FOLLOW RULES ADOPTED BY THE OREGON UTILITY NOTIFICATION CENTER. THOSE RULES ARE SET FORTH IN OAR 952-001-0010 THROUGH OAR 952-001-0090. YOU MAY OBTAIN COPIES OF THE RULES BY CALLING THE CENTER. (NOTE: THE TELEPHONE NUMBER FOR THE OREGON UTILITY NOTIFICATION CENTER IS (503) 232-1987). EXCAVATORS MUST NOTIFY ALL PERTINENT COMPANIES OR AGENCIES WITH UNDERGROUND UTILITIES IN THE PROJECT AREA AT LEAST 48 BUSINESS-DAY HOURS, BUT NOT MORE THAN 10 BUSINESS DAYS PRIOR TO COMMENCING AN EXCAVATION, SO UTILITIES MAY BE ACCURATELY LOCATED.
- THE LOCATION OF EXISTING UNDERGROUND UTILITIES SHOWN ON THE PLANS ARE FOR INFORMATION ONLY AND ARE NOT GUARANTEED TO BE COMPLETE OR ACCURATE. CONTRACTOR SHALL VERIFY ELEVATIONS, PIPE SIZE, AND MATERIAL TYPES OF ALL UNDERGROUND UTILITIES PRIOR TO COMMENCING WITH CONSTRUCTION AND SHALL BRING ANY DISCREPANCIES TO THE ATTENTION OF AAI ENGINEERING, 72 HOURS PRIOR TO START OF CONSTRUCTION TO PREVENT GRADE AND ALIGNMENT CONFLICTS.
- THE ENGINEER OR OWNER IS NOT RESPONSIBLE FOR THE SAFETY OF THE CONTRACTOR OR HIS CREW. ALL O.S.H.A. REGULATIONS SHALL BE STRICTLY ADHERED TO IN THE PERFORMANCE OF THE WORK.
- TEMPORARY AND PERMANENT EROSION CONTROL MEASURES SHALL BE IMPLEMENTED. THE ESC FACILITIES SHOWN IN THESE PLANS ARE THE MINIMUM REQUIREMENTS FOR ANTICIPATED SITE CONDITIONS. DURING THE CONSTRUCTION PERIOD, ESC FACILITIES SHALL BE UPGRADED AS NEEDED FOR UNEXPECTED STORM EVENTS AND TO ENSURE THAT SEDIMENT AND SEDIMENT LADEN WATER DO NOT LEAVE THE SITE.
- THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING ALL ROADWAYS, KEEPING THEM CLEAN AND FREE OF CONSTRUCTION MATERIALS AND DEBRIS, AND PROVIDING DUST CONTROL AS REQUIRED.
- TRAFFIC CONTROL SHALL BE PROVIDED BY THE CONTRACTOR THROUGHOUT CONSTRUCTION. CONTRACTOR SHALL PROVIDE A TRAFFIC CONTROL PLAN TO LOCAL JURISDICTION FOR REVIEW AND APPROVAL PRIOR TO COMMENCING CONSTRUCTION.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING AND SCHEDULING ALL WORK WITH THE OWNER.
- THE CONTRACTOR SHALL HAVE A FULL SET OF THE CURRENT APPROVED CONSTRUCTION DOCUMENTS INCLUDING ADDENDA ON THE PROJECT SITE AT ALL TIMES.
- THE CONTRACTOR SHALL KEEP THE ENGINEER AND JURISDICTION INFORMED OF CONSTRUCTION PROGRESS TO FACILITATE SITE OBSERVATIONS AT REQUIRED INTERVALS. 24-HOUR NOTICE IS REQUIRED.
- EXISTING SURVEY MONUMENTS ARE TO BE PROTECTED DURING CONSTRUCTION OR REPLACED IN ACCORDANCE WITH OREGON REVISED STATUTES 209.140 – 209.155.

**NOTICE TO EXCAVATORS:** ATTENTION: OREGON LAW REQUIRES YOU TO FOLLOW RULES ADOPTED BY THE OREGON UTILITY NOTIFICATION CENTER. THOSE RULES ARE SET FORTH IN OAR 952-001-0010 THROUGH OAR 952-001-0090. YOU MAY OBTAIN COPIES OF THE RULES BY CALLING THE CENTER. (NOTE: THE TELEPHONE NUMBER FOR THE OREGON UTILITY NOTIFICATION CENTER IS (503)-232-1987).

POTENTIAL UNDERGROUND FACILITY OWNERS  
**DIG SAFELY**  
 CALL THE OREGON ONE-CALL CENTER  
 1-800-332-2344  
 EMERGENCY TELEPHONE NUMBERS


NW NATURAL GAS  
 M-F 7am-5pm 503-226-4211 EXT.4313  
 AFTER HOURS 503-226-4211  
 PGE 503-464-7777  
 QWEST 1-800-573-1311  
 VERIZON 1-800-483-1000



Know what's below.  
 Call before you dig.




F:\2021\A21194.10 - 119 N Pacific Hwy - Woodburn\Civil\Cad\Sheets\A21194.C0.2.EC.dwg : Feb. 27. 23 - 11:25 AM evans



DISCLAIMER: THE BOUNDARY AS SHOWN IS PRELIMINARY. FURTHER FIELD SURVEY SEARCH FOR ADDITIONAL MONUMENTS AND REFERENCES IS ONGOING.

SURVEY FOR: SILCO COMMERCIAL CONSTRUCTION	
LOCATION: 119 N PACIFIC HWY (SH 99E) WOODBURN, OR 97071	
NW 1/4 SECTION 17 T5S, R1W, W.M. CITY OF WOODBURN MARION COUNTY, OREGON	
<b>L</b> AZER SITE / <b>R</b> IVERSIDE SURVEYING, LLC	CREW: TP/EG/CG REVIEW: R.J.G./M.A.T. SCALE: 1"=20'
2003 25TH STREET S.E. (503) 581-6362 SALEM, OREGON 97302 FAX (503) 581-0901	JOB NO.: 2021-012 SHEET DATE: 06/18/2021 1 OF 1



**SHEET NOTES**

1. SEE C0.1 FOR GENERAL SHEET NOTES.


**EASEMENT NOTE 1:**

UNABLE TO FIND EXHIBIT "A" MENTIONED IN DEED VOLUME 481 PAGE 82 FOR THIS SECTION OF SEWER LINE. USED WOODBURN UTILITY MAP SECTION 35-MC21-39 TO SHOW APPROXIMATE/GENERAL LOCATION.

BOTH SEWER EASEMENTS DEEDS FOR TAX LOT 7400 AND 7300 HAVE A GENERAL STATEMENT AS FOLLOWS; "A PERMANENT EASEMENT AND RIGHT-OF-WAY OF SUCH WIDTH AS MAY BE REASONABLY NECESSARY TO ACCOMPLISH THE PURPOSE OF THIS EASEMENT AS HEREIN AFTER SET FORTH UPON, OVER, UNDER AND ACROSS THE REAL PROPERTY". THIS WOULD THEN POINT TO THE LOCATION OF THE EXISTING LINE, AND WOULD BE THE EASEMENT AS SHOWN BY THE WOODBURN UTILITIES MAPS AS SHOWN HEREON.

**EASEMENT NOTE 2:**

R. 3657, P. 369, PERMANENT EASEMENT FOR SIDEWALK, WATER, GAS, ELECTRIC AND COMMUNICATION SERVICE LINES, FIXTURES AND FACILITIES.



119 N PACIFIC HWY  
WOODBURN, OR

SHEET TITLE

**EXISTING CONDITIONS PLAN**

DATE: 12/13/21

DRAWN: JS

CHECKED: CFT

REVISIONS:


© AAI ENGINEERING INC. 2023. ALL RIGHTS RESERVED.

THESE DRAWINGS ARE THE PROPERTY OF AAI ENGINEERING INC. AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER, EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF AAI ENGINEERING INC.

SHEET NUMBER

**C0.2**

JOB NUMBER: A21194.10



**AAI** ajiphan associates, inc.  
**ENGINEERING**  
 4875 SW Griffin Drive, Suite 300 | Beaverton, OR 97005  
 503.620.3630 | 503.620.5539 | www.aaieng.com

**119 N PACIFIC HWY**  
 WOODBURN, OR

SHEET TITLE

**DEMOLITION PLAN**

DATE: 12/13/21

DRAWN: JS

CHECKED: CFT

REVISIONS:

© AAI ENGINEERING INC. 2023. ALL RIGHTS RESERVED.

THESE DRAWINGS ARE THE PROPERTY OF AAI ENGINEERING INC. AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER, EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF AAI ENGINEERING INC.

SHEET NUMBER

**C0.3**

JOB NUMBER: A21194.10

**SHEET NOTES**


1. CONTRACTOR MAY STAGE WITHIN LIMITS OF DEMOLITION.
2. REMOVE ALL SITE COMPONENTS AND RECYCLE COMPONENTS AS REQUIRED IN THE SPECIFICATIONS.
3. ALL TRADE LICENSES AND PERMITS NECESSARY FOR THE PROCUREMENT AND COMPLETION OF THE WORK SHALL BE SECURED BY THE CONTRACTOR PRIOR TO COMMENCING DEMOLITION.
4. THE CONTRACTOR SHALL PRESERVE AND PROTECT FROM DAMAGE ALL EXISTING RIGHT-OF-WAY SURVEY MONUMENTATION DURING DEMOLITION. THE CONTRACTOR IS RESPONSIBLE FOR COORDINATING AND PAYING FOR THE REPLACEMENT BY A LICENSED SURVEYOR OF ANY DAMAGED OR REMOVED MONUMENTS.
5. PROTECT ALL ITEMS ON ADJACENT PROPERTIES AND IN THE RIGHT OF WAY INCLUDING BUT NOT LIMITED TO SIGNAL EQUIPMENT, PARKING METERS, SIDEWALKS, STREET TREES, STREET LIGHTS, CURBS, PAVEMENT AND SIGNS. CONTRACTOR SHALL BE RESPONSIBLE FOR RESTORING ANY DAMAGED ITEMS TO ORIGINAL CONDITION.
6. PROTECT STRUCTURES, UTILITIES, SIDEWALKS, AND OTHER FACILITIES IMMEDIATELY ADJACENT TO EXCAVATIONS FROM DAMAGES CAUSED BY SETTLEMENT, LATERAL MOVEMENT, UNDERMINING, WASHOUT AND OTHER HAZARDS.
7. SAWCUT STRAIGHT LINES IN SIDEWALK, AS NECESSARY.
8. CONTRACTOR IS RESPONSIBLE TO CONTROL DUST AND MUD DURING THE DEMOLITION PERIOD, AND DURING TRANSPORTATION OF DEMOLITION DEBRIS. ALL STREET SURFACES OUTSIDE THE CONSTRUCTION ZONE MUST BE KEPT CLEAN.
9. PROTECT ALL EXISTING UTILITY STRUCTURES AND UNDERGROUND MAINS TO REMAIN.
10. PROTECT ALL EXISTING VEGETATION TO REMAIN.

**X PROTECTION NOTES**


1. PROTECT EXISTING UTILITY
2. PROTECT EXISTING TRAFFIC SIGNAL
3. PROTECT EXISTING ASPHALT
4. PROTECT EXISTING CURB
5. PROTECT EXISTING SIDEWALK
6. PROTECT EXISTING SPEED LIMIT SIGN
7. PROTECT EXISTING FENCE

**X DEMOLITION NOTES**

1. REMOVE EXISTING CURB
2. REMOVE AND RELOCATE EXISTING POWER POLE AND CONNECTED OVERHEAD LINES. REMOVE AND RELOCATE EXISTING DOWN GUY AS NEEDED. CONTRACTOR TO COORDINATE WITH POWER COMPANY.
3. REMOVE EXISTING FENCE
4. REMOVE EXISTING GRAVEL
5. REMOVE EXISTING SIDEWALK
6. REMOVE EXISTING ASPHALT
7. SAWCUT LINE
8. REMOVE AND RELOCATE EXISTING CATV PEDESTAL. CONTRACTOR TO COORDINATE WITH COMM. COMPANY.



F:\2021\A21194.10 - 119 N Pacific Hwy - Woodburn\Civil\Cad\Sheets\A21194.C1.0 SITE.dwg : Feb. 27, 23 - 2:48 PM - daniel



**SHEET NOTES**

1. SEE SHEET C0.1 FOR GENERAL SHEET NOTES.
2. SEE ARCHITECTURAL PLANS FOR ADDITIONAL SITE INFORMATION.
3. THE CONTRACTOR SHALL HAVE A FULL SET OF THE CURRENT APPROVED CONSTRUCTION DOCUMENTS INCLUDING ADDENDA ON THE PROJECT SITE AT ALL TIMES.
4. THE CONTRACTOR SHALL KEEP THE ENGINEER AND JURISDICTION INFORMED OF CONSTRUCTION PROGRESS TO FACILITATE SITE OBSERVATIONS AT REQUIRED INTERVALS. 24-HOUR NOTICE IS REQUIRED.


**(X) CONSTRUCTION NOTES**

1. INSTALL CURB PER DETAIL 1/C4.0
2. INSTALL SIDEWALK PER CITY OF WOODBURN DETAIL 4150-8/C4.0
3. INSTALL ASPHALT SURFACE PER DETAIL 2/C4.0
4. INSTALL UNIT PAVER SURFACE, DESIGN BY OTHERS
5. INSTALL ADA RAMP TYPE 5 PER DETAIL 6/C4.0
6. INSTALL ADA STRIPING PER DETAIL 3/C4.0
7. INSTALL STRIPING, SEE ARCHITECTURAL PLANS FOR DETAILS
8. INSTALL DRIVEWAY PER DETAIL 4150-1/C4.0
9. INSTALL WHEELSTOP PER DETAIL 5/C4.0
10. INSTALL TRASH ENCLOSURE, DESIGN BY OTHERS
11. INSTALL RETAINING WALL, DESIGN BY OTHERS
12. INSTALL SIDEWALK PER DETAIL 7/C4.0
13. INSTALL BIKE PARKING. SEE ARCHITECTURAL PLANS FOR MORE INFORMATION.
14. INSTALL REMOVABLE BOLLARDS PER DETAIL 2/C4.2
15. INSTALL FENCE. SEE ARCHITECTURAL PLANS FOR MORE INFORMATION.


**LEGEND**

PROPERTY LINE	---
CONCRETE SIDEWALK SURFACING	[Pattern]
ASPHALT SURFACING	[Pattern]
EASEMENT BOUNDARY	---

NORTH



GRAPHIC SCALE



( IN FEET )  
1 inch = 20 feet



**AAI** ajghian associates, inc.  
**ENGINEERING**  
 4875 SW Griffin Drive, Suite 300 | Beaverton, OR 97005  
 503.620.3630 | 503.620.5539 | www.aaieng.com

**119 N PACIFIC HWY**  
 WOODBURN, OR

SHEET TITLE

**HARDSCAPE PLAN**

DATE: 12/13/21

DRAWN: JS

CHECKED: CFT

REVISIONS:


© AAI ENGINEERING INC. 2023. ALL RIGHTS RESERVED.

THESE DRAWINGS ARE THE PROPERTY OF AAI ENGINEERING INC. AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER, EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF AAI ENGINEERING INC.

SHEET NUMBER

**C1.0**

JOB NUMBER: A21194.10



**AAI** ajghjan associates, inc.  
**ENGINEERING**  
 4875 SW Griffin Drive | Suite 300 | Beaverton, OR 97005  
 503.620.3630 | fax | 503.620.5539 | www.aaieng.com

**119 N PACIFIC HWY**  
 WOODBURN, OR

SHEET TITLE

**GRADING PLAN**

DATE: 12/13/21

DRAWN: JS

CHECKED: CFT

REVISIONS:

© AAI ENGINEERING INC. 2023. ALL RIGHTS RESERVED.

THESE DRAWINGS ARE THE PROPERTY OF AAI ENGINEERING INC. AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER, EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF AAI ENGINEERING INC.

SHEET NUMBER

JOB NUMBER: A21194.10

**SHEET NOTES**




- SEE SHEET C0.1 FOR GENERAL SHEET NOTES.
- CURB HEIGHTS ARE 6" UNLESS NOTED OTHERWISE.
- LANDINGS ON ACCESSIBLE ROUTES SHALL NOT EXCEED 2% IN ANY DIRECTION.
- ALL ACCESSIBLE ROUTES SHALL COMPLY WITH CURRENT ADA ACCESSIBILITY GUIDELINES FOR BUILDING AND FACILITIES (ADAAG).
- ALL WALKWAYS FROM ACCESSIBLE UNITS ARE DESIGNED TO NOT REQUIRE HANDRAILS. THEREFORE, RAMP WITH SLOPES STEEPER THAN 5.0% AND LESS THAN 8.33% SHALL NOT EXCEED 0.5' RISE OR 6.0' LENGTH.
- FINISH GRADES ARE TO BE BROUGHT TO WITHIN 0.08 FT IN 10 FT OF THE GRADES SHOWN AT SUBGRADE AND TO WITHIN 0.03 FT IN 10 FT AT FINISH GRADE. CONTRACTOR TO ALLOW FOR PLACEMENT OF REQUIRED TOPSOIL IN ROUGH GRADING.
- GRADING ELEVATIONS AS SHOWN ON SITE AND LANDSCAPE PLANS ARE FINISHED GRADE WHICH INCLUDES SUBGRADE, SOIL, TOPSOIL, SOIL AMENDMENTS, ROCKERY AND RUNOFF PROTECTION CONTRACTOR IS RESPONSIBLE TO COORDINATE GRADING WITH BOTH EXCAVATOR AND LANDSCAPE CONTRACTOR.

**GRADING LABEL LEGEND**


CALLOUT	DESCRIPTION
	SPOT ELEVATION
XX.XX XX	DESCRIPTION LISTED BELOW.
BS	BOTTOM OF STAIRS
BW	FINISHED GRADE AT BOTTOM OF WALL
DS	DOOR SILL
EX	EXISTING GRADE
FF	FINISHED FLOOR ELEVATION
FG	FINISH GRADE
G	GROUND
SW	SIDEWALK
TC	TOP OF CURB
TP	TOP OF PAVEMENT
TS	TOP OF STAIRS
TW	FINISHED GRADE AT TOP OF WALL

**LEGEND**

EXISTING CONTOUR MINOR	--- 102 ---
EXISTING CONTOUR MAJOR	--- 100 ---
PROPOSED CONTOUR MINOR	--- 102 ---
PROPOSED CONTOUR MAJOR	--- 100 ---
GRADE BREAK	--- GB ---



F:\2021\A21194.10 - 119 N Pacific Hwy - Woodburn\Civil\Cad\Sheets\A21194\_C2.0 GRAD.dwg : Feb. 27. 23 - 2:48 PM hdmel



**AAI** ajghn associates, inc.  
**ENGINEERING**  
 4875 SW Griffin Drive, Suite 300 | Beaverton, OR 97005  
 503.620.3630 | 503.620.5539 | www.aaieng.com

**119 N PACIFIC HWY**  
 WOODBURN, OR

SHEET TITLE

**STORMWATER PLAN**

DATE: 12/13/21

DRAWN: JS

CHECKED: CFT

REVISIONS:

© AAI ENGINEERING INC. 2023. ALL RIGHTS RESERVED.

THESE DRAWINGS ARE THE PROPERTY OF AAI ENGINEERING INC. AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER, EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF AAI ENGINEERING INC.

SHEET NUMBER

**C3.0**

JOB NUMBER: A21194.10

**SHEET NOTES**

- SEE SHEET C0.1 FOR GENERAL SHEET NOTES.
- STRUCTURES HORIZONTAL LOCATIONS AND PIPE INVERTS ARE BASED ON THE CENTER OF THE STRUCTURE.
- PIPE BEDDING AND BACKFILL UTILITIES SHALL BE DONE PER DETAIL 1/C4.1.
- INSTALL THRUST BLOCKS ON FIRE AND WATER LINES PER DETAIL 2/C4.1.
- ALL SANITARY PIPING SHALL BE PVC 3034 OR APPROVED EQUAL UNLESS NOTED OTHERWISE.
- THIS PLAN IS GENERALLY DIAGRAMMATIC. IT DOES NOT SHOW EVERY JOINT, BEND, FITTING, OR ACCESSORY REQUIRED FOR CONSTRUCTION.
- CLEAN OUTS SHALL BE INSTALLED IN CONFORMANCE WITH UPC CHAPTER SEVEN, SECTION 707 AND SECTION 719. THIS PLAN MAY NOT SHOW ALL REQUIRED CLEAN OUTS.
- DOMESTIC WATER AND FIRE LINES AND ACCESSORIES BETWEEN THE WATER METER AND THE BUILDING SHALL BE INSTALLED BY A LICENSED PLUMBER EMPLOYED BY A LICENSED PLUMBING CONTRACTOR.
- UTILITIES WITHIN FIVE FEET OF A BUILDING SHALL BE CONSTRUCTED OF MATERIALS APPROVED FOR INTERIOR USE AS DESCRIBED IN THE CURRENT EDITION OF THE UPC.
- INLETS AND OUTLETS TO ON-SITE MANHOLES SHALL HAVE FLEXIBLE CONNECTION NO CLOSER THAN 12" AND NO FARTHER THAN 36" FROM THE MANHOLE.
- CONTRACTOR TO VERIFY SANITARY AND WATER SIZING AND INVERTS WITH APPROVED PLUMBING PLANS PRIOR TO ORDERING MATERIALS OR BEGINNING CONSTRUCTION OF SAID UTILITIES.
- ALL STORM AND SANITARY FITTINGS TO BE ECCENTRIC FITTINGS UNLESS OTHERWISE NOTED.

**LABEL LEGEND**

**PIPE LABELS**

- UTILITY LENGTH
- UTILITY SIZE
- XXLF - XX" XX ← UTILITY TYPE
- S=X.XXX ← SLOPE (WHERE APPLICABLE)

**STRUCTURE LABELS**

- UTILITY TYPE (FP=FIRE PROTECTION, S=SANITARY, SD=STORM DRAINAGE, W=WATER)
- STRUCTURE TYPE (SEE BELOW)
- XX XX-XX ← ID NUMBER (WHERE APPLICABLE)
- RIM=XX.XX ← STRUCTURE INFO (WHERE APPLICABLE)

**STRUCTURE TYPES**

TYPE	DESCRIPTION
CB	CATCH BASIN PER DETAIL 3/C4.1
CO	CLEANOUT PER DETAIL 3/C4.2
FCMH	FLOW CONTROL MANHOLE PER DETAIL 8/C4.1
MH	MAINTENANCE MANHOLE PER DETAIL 7/C4.1
RD	ROOF DRAIN CONNECTION - REFER TO PLUMBING PLANS


**LEGEND**

SANITARY SEWER LINE	SS SS
WATER LINE	W W W
FIRE LINE	FP FP FP FP
FDC LINE	FDC FDC FDC
STORM LINE	SD SD SD

**STORM NOTES**

- INSTALL UNDERGROUND STORM WATER DETENTION FACILITY. (108) SC-310 STORMTECH CHAMBERS WITHIN A ROCK SECTION THAT HAS A FOOTPRINT OF 2,774 SF PER DETAILS ON SHEET C4.3. WRAP ENTIRE ROCK SECTION IN GEOSYNTHETIC FABRIC.
- CONNECT TO EXISTING STORM STUB PER CITY OF WOODBURN GIS. CONTRACTOR TO LOCATE EXISTING STORM LINE PRIOR CONSTRUCTION AND NOTIFY ENGINEER OF FINDINGS. INVERT SHOWN IS APPROXIMATE.


NORTH




GRAPHIC SCALE



( IN FEET )  
1 inch = 20 feet





**AAI** ajlpa associates, inc.  
**ENGINEERING**  
 4875 SW Griffin Drive, Suite 300 | Beaverton, OR 97005  
 503.620.3630 | 503.620.5539 | www.aaieng.com

**119 N PACIFIC HWY**  
 WOODBURN, OR

**SHEET NOTES**

- SEE SHEET C0.1 FOR GENERAL SHEET NOTES.
- STRUCTURES HORIZONTAL LOCATIONS AND PIPE INVERTS ARE BASED ON THE CENTER OF THE STRUCTURE.
- PIPE BEDDING AND BACKFILL UTILITIES SHALL BE DONE PER DETAIL 1/C4.1.
- INSTALL THRUST BLOCKS ON FIRE AND WATER LINES PER DETAIL 2/C4.1.
- ALL SANITARY PIPING SHALL BE PVC 3034 OR APPROVED EQUAL UNLESS NOTED OTHERWISE.
- THIS PLAN IS GENERALLY DIAGRAMMATIC. IT DOES NOT SHOW EVERY JOINT, BEND, FITTING, OR ACCESSORY REQUIRED FOR CONSTRUCTION.
- CLEAN OUTS SHALL BE INSTALLED IN CONFORMANCE WITH UPC CHAPTER SEVEN, SECTION 707 AND SECTION 719. THIS PLAN MAY NOT SHOW ALL REQUIRED CLEAN OUTS.
- DOMESTIC WATER AND FIRE LINES AND ACCESSORIES BETWEEN THE WATER METER AND THE BUILDING SHALL BE INSTALLED BY A LICENSED PLUMBER EMPLOYED BY A LICENSED PLUMBING CONTRACTOR.
- UTILITIES WITHIN FIVE FEET OF A BUILDING SHALL BE CONSTRUCTED OF MATERIALS APPROVED FOR INTERIOR USE AS DESCRIBED IN THE CURRENT EDITION OF THE UPC.
- INLETS AND OUTLETS TO ON-SITE MANHOLES SHALL HAVE FLEXIBLE CONNECTION NO CLOSER THAN 12" AND NO FARTHER THAN 36" FROM THE MANHOLE.
- CONTRACTOR TO VERIFY SANITARY AND WATER SIZING AND INVERTS WITH APPROVED PLUMBING PLANS PRIOR TO ORDERING MATERIALS OR BEGINNING CONSTRUCTION OF SAID UTILITIES.
- ALL STORM AND SANITARY FITTINGS TO BE ECCENTRIC FITTINGS UNLESS OTHERWISE NOTED.

**LABEL LEGEND**

**PIPE LABELS**

- UTILITY LENGTH
- UTILITY SIZE
- XXLF - XX" XX ← UTILITY TYPE
- S=X.XX% ← SLOPE (WHERE APPLICABLE)

**STRUCTURE LABELS**

- UTILITY TYPE (FP=FIRE PROTECTION, S=SANITARY, SD=STORM DRAINAGE, W=WATER)
- STRUCTURE TYPE (SEE BELOW)
- XX XX-XX ← ID NUMBER (WHERE APPLICABLE)
- RIM=XX.XX ← STRUCTURE INFO (WHERE APPLICABLE)

**STRUCTURE TYPES**

TYPE	DESCRIPTION
BF	BACKFLOW PREVENTION PER DETAIL 1/C4.2
FDC	FIRE DEPARTMENT CONNECTION PER DETAIL 5/C4.1
FH	FIRE HYDRANT PER DETAIL 5070-1/C4.2
FV	FIRE SERVICE VAULT PER DETAIL 4/C4.1
WM	WATER METER PER DETAILS 5000-1 & 5000-3/C4.2

**LEGEND**

SANITARY SEWER LINE	SS SS
WATER LINE	W W W
FIRE LINE	FP FP FP FP
FDC LINE	FDC FDC FDC
STORM LINE	SD SD SD

SHEET TITLE

**WATER AND SANITARY PLAN**

DATE: 12/13/21

DRAWN: JS

CHECKED: CFT

REVISIONS:


© AAI ENGINEERING INC. 2023. ALL RIGHTS RESERVED.

THESE DRAWINGS ARE THE PROPERTY OF AAI ENGINEERING INC. AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER, EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF AAI ENGINEERING INC.

SHEET NUMBER

**C3.1**

JOB NUMBER: A21194.10





**X WATER NOTES**

- WET TAP EXISTING WATER MAIN
- CONNECT FIRE PROTECTION TO BUILDING
- CONNECT DOMESTIC WATER TO BUILDING

**X SANITARY NOTES**


- CONNECT TO EXISTING SANITARY STUB
- CONNECT TO BUILDING






- NOTES:**
- CURB EXPOSURE 'E' = 6", TYP. VARY AS SHOWN ON PLANS OR AS DIRECTED.
  - CONSTRUCT CONTRACTION JOINTS AT 15' MAX. SPACING AND AT RAMPS. CONSTRUCT EXPANSION JOINTS AT 200' MAX SPACING AT POINTS OF TANGENCY AND AT ENDS OF EACH DRIVEWAY.
  - TOPS OF ALL CURBS SHALL SLOPE TOWARD THE ROADWAY AT 2% UNLESS OTHERWISE SHOWN OR AS DIRECTED.
  - DIMENSIONS ARE NOMINAL AND MAY VARY TO CONFORM WITH CURB MACHINE AS APPROVED BY THE ENGINEER.


**1 CONCRETE CURB - STANDARD**  
SCALE: NTS



**2 ASPHALT PAVEMENT SECTION**  
SCALE: NTS



**3 TYPICAL PARKING LAYOUT**  
SCALE: NTS




- NOTES:**
- MATERIAL - 3500 PSI CONCRETE AT 28 DAYS. BROOM FINISH SURFACE & PROVIDE 3" EDGE SHINE. REFERENCE TECHNICAL SPEC. SECTION 4150.
  - EXPANSION JOINTS (EJ) SHALL BE 1/2" AC IMPREGNATED JOINT FILLER AT ALL DISSIMILAR VERTICAL SURFACES.
  - TRANSVERSE CONSTRUCTION JOINTS (CJ) 1-1/2" DEEP OR 1/3 OF THE THICKNESS (T) @ 5' INTERVALS.
  - FOR SIDEWALK AT DRIVEWAYS SEE DETAILS 4150-3 AND 4150-4.

**WOODBURN**  
Incorporated 1889  
PUBLIC WORKS DEPARTMENT  
ENGINEERING DIVISION

**SIDEWALKS**


REV: JULY 2018  
SCALE: NTS  
DET No. 4150-8



**WOODBURN**  
Incorporated 1889  
PUBLIC WORKS DEPARTMENT  
ENGINEERING DIVISION

**DRIVEWAY APPROACH**


REV: AUG. 2020  
SCALE: NTS  
DET No. 4150-1




**WOODBURN**  
Incorporated 1889  
PUBLIC WORKS DEPARTMENT  
ENGINEERING DIVISION

**DRIVEWAY APPROACH**


REV: AUG. 2020  
SCALE: NTS  
DET No. 4150-1



**4 ADA PARKING SIGN - TYPE 2**  
SCALE: NTS




**5 PRECAST CONCRETE WHEEL STOP**  
SCALE: NTS





- NOTES:**
- PROVIDE RAMP TEXTURING WITH AN EXPANDED METAL GRATE PLACED ON AND REMOVED FROM WET CONCRETE TO LEAVE A DIAMOND PATTERN. EACH DIAMOND SHALL BE 1 1/2" LONG BY 1/2" WIDE WITH THE LONG SECTION AXIS ORIENTED PERPENDICULAR TO THE CURB. THE GROOVES SHALL BE 1/8" DEEP BY 1/4" WIDE.

**6 CURB RAMP - TYPE 5**  
SCALE: NTS



- NOTES:**
- CONSTRUCT CONTRACTION JOINTS AT 15' MAX. SPACING AND AT RAMPS. CONSTRUCT EXPANSION JOINTS AT 200' MAX SPACING, AT POINTS OF TANGENCY AND AT ENDS OF EACH DRIVEWAY, UNLESS NOTED OTHERWISE.
  - CONCRETE SHALL BE 3000 P.S.I AT 28 DAYS, 6 SACK MIX, SLUMP RANGE OF 1-1/2" TO 3".
  - PANELS SHALL BE 5 FEET LONG.
  - EXPANSION JOINTS TO BE PLACED AT SIDES OF DRIVEWAY APPROACHES, UTILITY VAULTS, WHEELCHAIR RAMPS, AND AT SPACING NOT TO EXCEED 45 FEET.
  - FOR SIDEWALKS ADJACENT TO THE CURB AND POURED AT THE SAME TIME AS THE CURB, THE JOINT BETWEEN THEM SHALL BE A TROWELED JOINT WITH A MINIMUM 1/2" RADIUS.
  - SIDEWALK SHALL HAVE A MINIMUM THICKNESS OF 6 INCHES IF MOUNTABLE CURB IS USED OR IF SIDEWALK IS INTENDED AS PORTION OF DRIVEWAY. OTHERWISE SIDEWALK SHALL HAVE A MINIMUM THICKNESS OF 4 INCHES.
  - DRAIN BLOCKOUTS IN CURBS SHALL BE EXTENDED TO BACK OF SIDEWALK WITH 3" DIA. PVC PIPE AT 2% SLOPE. CONTRACTION JOINT TO BE PLACED OVER PIPE.

**7 CONCRETE SIDEWALK**  
SCALE: NTS



- NOTES:**
- REFERENCE TECHNICAL SPEC. SECTION 4150.
  - PLACE CONSTRUCTION JOINTS AT 5' INTERVALS 1/3 THICKNESS.
  - MATERIAL - 3500 PSI CONCRETE AT 28 DAYS.

**WOODBURN**  
Incorporated 1889  
PUBLIC WORKS DEPARTMENT  
ENGINEERING DIVISION

**PROPERTY LINE SIDEWALK AT DRIVEWAY**

REV: JUNE. 2018  
SCALE: NTS  
DET No. 4150-4



**AAI** ajghan associates, inc.  
**ENGINEERING**  
4875 SW Griffin Drive, Suite 300 | Beaverton, OR 97005  
503.620.3630 | aai@aaiaa.com | www.aaiaa.com

**119 N PACIFIC HWY**  
WOODBURN, OR

SHEET TITLE  
**DETAILS**

DATE: 12/13/21  
DRAWN: JS  
CHECKED: CFT

REVISIONS:

AAI ENGINEERING INC.  
2023. ALL RIGHTS RESERVED



THESE DRAWINGS ARE THE PROPERTY OF AAI ENGINEERING INC. AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER, EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF AAI ENGINEERING INC.

SHEET NUMBER


**C4.0**

**FLOW CONTROL ORIFICE SIZING**

STRUCTURE	2-YR (RESTRICTOR PLATE INVERT)	EMERGENCY OVERFLOW
FCMH-01	1.6" Ø @ 182.40	18" Ø @ 186.52




**8 FLOW CONTROL MANHOLE**  
 SCALE: NTS




- NOTES:**
- CONTRACTOR TO WIDEN EXCAVATION AS REQUIRED TO OBTAIN COMPACTION WITH CONTRACTORS COMPACTION EQUIPMENT.
  - 1/4" STEEL PLATE, BITUMINOUS COATED. AS MANUFACTURED BY GIBSON STEEL BASINS OR APPROVED EQUAL.

**3 TRAPPED CATCH BASIN**  
 SCALE: NTS




- NOTES:**
- LAY PERFORATED DRAIN PIPE ON MIN. 0.5% GRADIENT, WIDENING EXCAVATION AS REQUIRED. MAINTAIN PIPE ABOVE 2:1 SLOPE AS SHOWN.
  - CONNECT TO FOUNDATION DRAIN STUBOUT SHOWN ON PLANS.

**6 PERIMETER FOUNDATION DRAIN**  
 SCALE: NTS



- NOTES:**
- ALL PRECAST SECTIONS SHALL CONFORM TO REQUIREMENTS OF ASTM C-478.
  - MANHOLE BASE MAY BE PRECAST OR CAST IN PLACE. SEE STANDARD MANHOLE BASE DETAILS.
  - ALL CONNECTING PIPES SHALL HAVE FLEXIBLE, GASKETED AND UNRESTRAINED JOINT WITHIN 18" OF MANHOLE VAULT.

**7 STANDARD MANHOLE**  
 SCALE: NTS




- CONCRETE THRUST BLOCKING TO BE POURED AGAINST UNDISTURBED EARTH.
- KEEP CONCRETE CLEAR OF JOINT AND ACCESSORIES.
- THE REQUIRED THRUST BEARING AREAS FOR SPECIAL CONNECTIONS ARE SHOWN ENCIRCLED ON THE PLAN; e.g. 15 INDICATES 15 SQUARE FEET BEARING AREA REQUIRED.
- IF NOT SHOWN ON PLANS REQUIRED BEARING AREAS AT FITTING SHALL BE AS INDICATED BELOW, ADJUST IF NECESSARY, TO CONFORM TO THE TEST PRESSURE(S) AND ALLOWABLE SOIL BEARING STRESS (ES) STATED IN THE SPECIAL SPECIFICATIONS.
- BEARING AREAS AND SPECIAL BLOCKING DETAILS SHOWN ON PLANS TAKE PRECEDENCE OVER BEARING AREAS AND BLOCKING DETAILS SHOWN ON THIS STANDARD DETAIL.

BEARING AREA OF THRUST BLOCK IN SQUARE FOOT

FITTING SIZE	TEE PLUGGED ON RUN		90° BEND PLUGGED CROSS	45° BEND	22 1/2° BEND	11 1/2° BEND
	A1	A2				
4	1.0	1.4	1.9	1.4	1.0	
6	2.1	3.0	4.3	3.0	1.6	1.0
8	3.8	5.3	7.6	5.4	2.9	1.5
10	5.9	8.4	11.8	8.4	4.6	2.4


**NOTE:** ABOVE BEARING AREAS BASED ON TEST PRESSURE OF 150 p.s.i. AND AN ALLOWABLE SOIL BEARING STRESS OF 2000 p.s.i.. TO COMPUTE BEARING AREAS FOR DIFFERENT TEST PRESSURE AND SOIL BEARING STRESSES, USE THE FOLLOWING EQUATION: BEARING AREA = (TEST PRESSURE/150)X(2000/ SOIL BEARING STRESS)X(TABLE VALUE).

**2 THRUST BLOCK**  
 SCALE: NTS




- NOTES:**
- CONCRETE ANCHOR PAD TO BE 12"x12"x6" THICK, UNLESS NOTED OTHERWISE. ELIMINATE IF INSTALLED IN CONCRETE PAVED AREA.
  - USE FLANGE OR THREADED FITTINGS.
  - CONTRACTOR SHALL PROVIDE SINGLE CHECK VALVE AND BALL DRIP VALVE IN ACCESSIBLE LOCATION INSIDE DDCV VAULT. COORDINATE WITH PLUMBING.

**5 FIRE DEPARTMENT CONNECTION (FDC) DUAL PORT**  
 SCALE: NTS





**1 TYPICAL PIPE BEDDING AND BACKFILL**  
 SCALE: NTS



D.D.C. SIZE	UTILITY VAULT OR EQUAL WITH F.D.C.		WITHOUT F.D.C.	BILCO DOOR OR EQUAL
	676 - WA	577 - WA		
4"	676 - WA	577 - WA		J - 5AL
6"	687 - WA	676 - WA		J - 5AL
8"	5106 - LA	687 - WA		JD - 3AL
10"	5106 - LA	5106 - LA		JD - 3AL

**4 DOUBLE CHECK DETECTOR ASSEMBLY FIRE SERVICE VAULT W/ DRAIN TO GROUND**  
 SCALE: NTS






NOTE: INSTALLATION SHOWN IS ONLY A SUGGESTION. THE DISTANCE FROM BOTTOM OF DEVICE TO FINISH GRADE, FREEZE PROTECTION, AND CLEARANCE FOR TESTING & REPAIR ARE THE MAJOR CONSIDERATIONS FOR INSTALLATION. PLUGS TO BE INSTALLED IN TEST COCKS OF BELOW GROUND INSTALLATIONS (NO DISSIMILAR METALS). IF FREEZE PROTECTION IS PROVIDED, THE 24" MIN CLEARANCE MAY BE REDUCED.

**1 DOUBLE CHECK BACKFLOW ASSEMBLY**


SCALE: NTS



- NOTES:
1. CAST IRON FRAME AND COVER SHALL MEET H-20 LOAD REQUIREMENT.
  2. FOR CARRIER PIPE SIZE 6"Ø AND LESS, PROVIDE RISER PIPE SIZE TO MATCH CARRIER PIPE.
  3. FOR CARRIER PIPE SIZE 8"Ø AND LARGER, RISER PIPE SHALL BE 6"Ø.
  4. RISER PIPE MATERIAL TO MATCH CARRIER PIPE MATERIAL.

**3 STANDARD CLEANOUT (COTG)**



SCALE: NTS



**2 REMOVABLE PIPE BOLLARD**

SCALE: NTS



BROOKS PRODUCTS		
COVER	METER BOX	
DIA.	MODEL NO.	
1"	No. 37-T CAST IRON COVER*	No. 37 MB-BODY*
2"	No. 65-TF STEEL COVER (FLUSH)*	No. 65 MB-BODY*
* OR APPROVED EQUAL		



**METER BOX**

REV: FEB 2020  
SCALE: NTS  
DET No. **5050-1**


HYDRANT: MUELLER CENTURION A423 OR M & H RELIANT 929T. REFERENCE TECHNICAL SPEC. SECTION 5070.




**FIRE HYDRANT ASSEMBLY**

REV: FEB. 2020  
SCALE: NTS  
DET No. **5070-1**

FORD CO. MODEL		
CORP STOP	ANGLE METER VALVE	
DIA.	Model No.	
1"	F1000-4*	KV43-444W*
1.5"	FB500-6*	FV43-666W*
2"	FB500-7*	FV43-777W*
* OR APPROVED EQUAL		




- NOTES:
1. WATER METER AND TAILPIECE SHALL BE FURNISHED AND INSTALLED BY CITY WATER DIVISION.
  2. WATER DIVISION SHALL HAVE SOLE RESPONSIBILITY FOR TAPPING LIVE MAINS.
  3. REFERENCE TECHNICAL SPEC. SECTION 5000.
  4. 1.5" & 2" SERVICE LINES SHALL BE SADDLE TAPPED WITH BRONZE DOUBLE STRAPS.



**WATER SERVICE CONNECTION**

REV: MAY 2011  
SCALE: NTS  
DET No. **5000-4**



AAI ajghian associates, inc.  
**ENGINEERING**  
4875 SW Griffin Drive, Suite 300 | Beaverton, OR 97005  
503.620.3630 | 503.620.5639 | fax: 1.800.541.6161

**119 N PACIFIC HWY**  
WOODBURN, OR

SHEET TITLE

**DETAILS**

DATE: 12/13/21

DRAWN: JS

CHECKED: CFT

REVISIONS:

© AAI ENGINEERING INC. 2023. ALL RIGHTS RESERVED.

THESE DRAWINGS ARE THE PROPERTY OF AAI ENGINEERING INC. AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER, EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF AAI ENGINEERING INC.

SHEET NUMBER

**C4.2**

JOB NUMBER: A21194.10



### SC-310 STORMTECH CHAMBER SPECIFICATIONS

- CHAMBERS SHALL BE STORMTECH SC-310.
- CHAMBERS SHALL BE ARCH-SHAPED AND SHALL BE MANUFACTURED FROM VIRGIN, IMPACT-MODIFIED POLYPROPYLENE OR POLYETHYLENE COPOLYMERS.
- CHAMBERS SHALL MEET THE REQUIREMENTS OF ASTM F2922 (POLYETHYLENE) OR ASTM F2418 (POLYPROPYLENE), "STANDARD SPECIFICATION FOR CORRUGATED WALL STORMWATER COLLECTION CHAMBERS".
- CHAMBER ROWS SHALL PROVIDE CONTINUOUS, UNOBSTRUCTED INTERNAL SPACE WITH NO INTERNAL SUPPORTS THAT WOULD IMPEDE FLOW OR LIMIT ACCESS FOR INSPECTION.
- THE STRUCTURAL DESIGN OF THE CHAMBERS, THE STRUCTURAL BACKFILL, AND THE INSTALLATION REQUIREMENTS SHALL ENSURE THAT THE LOAD FACTORS SPECIFIED IN THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, SECTION 12.12, ARE MET FOR: 1) LONG-DURATION DEAD LOADS AND 2) SHORT-DURATION LIVE LOADS, BASED ON THE AASHTO DESIGN TRUCK WITH CONSIDERATION FOR IMPACT AND MULTIPLE VEHICLE PRESENCES.
- CHAMBERS SHALL BE DESIGNED, TESTED AND ALLOWABLE LOAD CONFIGURATIONS DETERMINED IN ACCORDANCE WITH ASTM F2787, "STANDARD PRACTICE FOR STRUCTURAL DESIGN OF THERMOPLASTIC CORRUGATED WALL STORMWATER COLLECTION CHAMBERS". LOAD CONFIGURATIONS SHALL INCLUDE: 1) INSTANTANEOUS (<1 MIN) AASHTO DESIGN TRUCK LIVE LOAD ON MINIMUM COVER 2) MAXIMUM PERMANENT (75-YR) COVER LOAD AND 3) ALLOWABLE COVER WITH PARKED (1-WEEK) AASHTO DESIGN TRUCK.
- REQUIREMENTS FOR HANDLING AND INSTALLATION:
  - TO MAINTAIN THE WIDTH OF CHAMBERS DURING SHIPPING AND HANDLING, CHAMBERS SHALL HAVE INTEGRAL, INTERLOCKING STACKING LUGS.
  - TO ENSURE A SECURE JOINT DURING INSTALLATION AND BACKFILL, THE HEIGHT OF THE CHAMBER JOINT SHALL NOT BE LESS THAN 2".
  - TO ENSURE THE INTEGRITY OF THE ARCH SHAPE DURING INSTALLATION, THE ARCH STIFFNESS CONSTANT SHALL BE GREATER THAN OR EQUAL TO 400 LB/FT<sup>2</sup>. THE ASC IS DEFINED IN SECTION 6.2.8 OF ASTM F2418. AND B) TO RESIST CHAMBER DEFORMATION DURING INSTALLATION AT ELEVATED TEMPERATURES (ABOVE 73° F / 23° C), CHAMBERS SHALL BE PRODUCED FROM REFLECTIVE GOLD OR YELLOW COLORS.
- ONLY CHAMBERS THAT ARE APPROVED BY THE SITE DESIGN ENGINEER WILL BE ALLOWED. UPON REQUEST BY THE SITE DESIGN ENGINEER OR OWNER, THE CHAMBER MANUFACTURER SHALL SUBMIT A STRUCTURAL EVALUATION FOR APPROVAL BEFORE DELIVERING CHAMBERS TO THE PROJECT SITE AS FOLLOWS:
  - THE STRUCTURAL EVALUATION SHALL BE SEALED BY A REGISTERED PROFESSIONAL ENGINEER.
  - THE STRUCTURAL EVALUATION SHALL DEMONSTRATE THAT THE SAFETY FACTORS ARE GREATER THAN OR EQUAL TO 1.95 FOR DEAD LOAD AND 1.75 FOR LIVE LOAD. THE MINIMUM REQUIRED BY ASTM F2787 AND BY SECTIONS 3 AND 12.12 OF THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS FOR THERMOPLASTIC PIPE.
  - THE TEST DERIVED CREEP MODULUS AS SPECIFIED IN ASTM F2922 SHALL BE USED FOR PERMANENT DEAD LOAD DESIGN EXCEPT THAT IT SHALL BE THE 75-YEAR MODULUS USED FOR DESIGN.
- CHAMBERS AND END CAPS SHALL BE PRODUCED AT AN ISO 9001 CERTIFIED MANUFACTURING FACILITY.


### IMPORTANT - NOTES FOR THE BIDDING AND INSTALLATION OF THE SC-310 SYSTEM

- STORMTECH SC-310 CHAMBERS SHALL NOT BE INSTALLED UNTIL THE MANUFACTURER'S REPRESENTATIVE HAS COMPLETED A PRE-CONSTRUCTION MEETING WITH THE INSTALLERS.
- STORMTECH SC-310 CHAMBERS SHALL BE INSTALLED IN ACCORDANCE WITH THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE".
- CHAMBERS ARE NOT TO BE BACKFILLED WITH A DOZER OR AN EXCAVATOR SITUATED OVER THE CHAMBERS. STORMTECH RECOMMENDS 3 BACKFILL METHODS:
  - STONESHOOTER LOCATED OFF THE CHAMBER BED.
  - BACKFILL AS ROWS ARE BUILT USING AN EXCAVATOR ON THE FOUNDATION STONE OR SUBGRADE.
  - BACKFILL FROM OUTSIDE THE EXCAVATION USING A LONG BOOM HOE OR EXCAVATOR.
- THE FOUNDATION STONE SHALL BE LEVELED AND COMPACTED PRIOR TO PLACING CHAMBERS.
- JOINTS BETWEEN CHAMBERS SHALL BE PROPERLY SEATED PRIOR TO PLACING STONE.
- MAINTAIN MINIMUM 6" (150 mm) SPACING BETWEEN THE CHAMBER ROWS.
- EMBEDMENT STONE SURROUNDING CHAMBERS MUST BE A CLEAN, CRUSHED, ANGULAR STONE 3/4"-2" (20-50 mm).
- THE CONTRACTOR MUST REPORT ANY DISCREPANCIES WITH CHAMBER FOUNDATION MATERIALS BEARING CAPACITIES TO THE SITE DESIGN ENGINEER.
- ADS RECOMMENDS THE USE OF "FLEXSTORM CATCH IT" INSERTS DURING CONSTRUCTION FOR ALL INLETS TO PROTECT THE SUBSURFACE STORMWATER MANAGEMENT SYSTEM FROM CONSTRUCTION SITE RUNOFF.


### NOTES FOR CONSTRUCTION EQUIPMENT

- STORMTECH SC-310 CHAMBERS SHALL BE INSTALLED IN ACCORDANCE WITH THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE".
  - THE USE OF CONSTRUCTION EQUIPMENT OVER SC-310 & SC-740 CHAMBERS IS LIMITED:
    - NO EQUIPMENT IS ALLOWED ON BARE CHAMBERS.
    - NO RUBBER Tired LOADERS, DUMP TRUCKS, OR EXCAVATORS ARE ALLOWED UNTIL PROPER FILL DEPTHS ARE REACHED IN ACCORDANCE WITH THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE".
    - WEIGHT LIMITS FOR CONSTRUCTION EQUIPMENT CAN BE FOUND IN THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE".
  - FULL 36" (900 mm) OF STABILIZED COVER MATERIALS OVER THE CHAMBERS IS REQUIRED FOR DUMP TRUCK TRAVEL OR DUMPING.
- USE OF A DOZER TO PUSH EMBEDMENT STONE BETWEEN THE ROWS OF CHAMBERS MAY CAUSE DAMAGE TO THE CHAMBERS AND IS NOT AN ACCEPTABLE BACKFILL METHOD. ANY CHAMBERS DAMAGED BY THE "DUMP AND PUSH" METHOD ARE NOT COVERED UNDER THE STORMTECH STANDARD WARRANTY.


CONTACT STORMTECH AT 1-888-892-2694 WITH ANY QUESTIONS ON INSTALLATION REQUIREMENTS OR WEIGHT LIMITS FOR CONSTRUCTION EQUIPMENT.



### 5 UNDERDRAIN DETAIL



### 6 INSERTA-TEE SIDE INLET DETAIL



### 2 SC-310 TECHNICAL SPECIFICATIONS

**NOMINAL CHAMBER SPECIFICATIONS**

SIZE (W X H X INSTALLED LENGTH)	34.0" X 16.0" X 85.4"	(864 mm X 406 mm X 2169 mm)
CHAMBER STORAGE	14.7 CUBIC FEET	(0.42 m <sup>3</sup> )
MINIMUM INSTALLED STORAGE*	33.0 CUBIC FEET	(0.88 m <sup>3</sup> )
WEIGHT	35.0 lbs	(15.8 kg)

\* ASSUMES 6" (152 mm) ABOVE, BELOW, AND BETWEEN CHAMBERS

PART #	STUB	A	B	C
SC310EPE00T / SC310EPE00TPC	8" (200 mm)	9.6" (244 mm)	5.8" (147 mm)	---
SC310EPE00B / SC310EPE00BPC	8" (200 mm)	11.9" (302 mm)	3.5" (89 mm)	0.5" (13 mm)
SC310EPE01T / SC310EPE01TPC	10" (250 mm)	12.7" (323 mm)	1.4" (36 mm)	---
SC310EPE01B / SC310EPE01BPC	12" (300 mm)	13.5" (343 mm)	---	0.7" (18 mm)
SC310EPE12B	12" (300 mm)	13.5" (343 mm)	---	0.9" (23 mm)
SC310EPE12BR	12" (300 mm)	13.5" (343 mm)	---	0.9" (23 mm)

ALL STUBS, EXCEPT FOR THE SC310EPE12B ARE PLACED AT BOTTOM OF END CAP SUCH THAT THE OUTSIDE DIAMETER OF THE STUB IS FLUSH WITH THE BOTTOM OF THE END CAP. FOR ADDITIONAL INFORMATION CONTACT STORMTECH AT 1-888-892-2694.

\* FOR THE SC310EPE12B THE 12" (300 mm) STUB LIES BELOW THE BOTTOM OF THE END CAP APPROXIMATELY 0.25" (6 mm). BACKFILL MATERIAL SHOULD BE REMOVED FROM BELOW THE N-12 STUB SO THAT THE FITTING SITS LEVEL.


NOTE: ALL DIMENSIONS ARE NOMINAL.

### ACCEPTABLE FILL MATERIALS: STORMTECH SC-310 CHAMBER SYSTEMS

MATERIAL LOCATION	DESCRIPTION	AASHTO MATERIAL CLASSIFICATIONS	COMPACTION / DENSITY REQUIREMENT
D	FINAL FILL: FILL MATERIAL FOR LAYER 'D' STARTS FROM THE TOP OF THE 'C' LAYER TO THE BOTTOM OF FLEXIBLE PAVEMENT OR UNPAVED FINISHED GRADE ABOVE. NOTE THAT PAVEMENT SUBBASE MAY BE PART OF THE 'D' LAYER.	N/A	PREPARE PER SITE DESIGN ENGINEER'S PLANS. PAVED INSTALLATIONS MAY HAVE STRINGENT MATERIAL AND PREPARATION REQUIREMENTS.
C	INITIAL FILL: FILL MATERIAL FOR LAYER 'C' STARTS FROM THE TOP OF THE EMBEDMENT STONE ('B' LAYER) TO 18" (450 mm) ABOVE THE TOP OF THE CHAMBER. NOTE THAT PAVEMENT SUBBASE MAY BE A PART OF THE 'C' LAYER.	AASHTO M145 <sup>1</sup> A-1, A-2-4, A-3 OR AASHTO M43 <sup>1</sup> 3, 357, 4, 467, 5, 56, 57, 6, 67, 68, 7, 78, 8, 89, 9, 10	BEGIN COMPACTIONS AFTER 12" (300 mm) OF MATERIAL OVER THE CHAMBERS IS REACHED. COMPACT ADDITIONAL LAYERS IN 6" (150 mm) MAX LIFTS TO A MIN. 95% PROCTOR DENSITY FOR WELL GRADED MATERIAL AND 95% RELATIVE DENSITY FOR PROCESSED AGGREGATE MATERIALS. ROLLER GROSS VEHICLE WEIGHT NOT TO EXCEED 12,000 lbs (53 kN). DYNAMIC FORCE NOT TO EXCEED 20,000 lbs (89 kN).
B	EMBEDMENT STONE: FILL SURROUNDING THE CHAMBERS FROM THE FOUNDATION STONE ('A' LAYER) TO THE 'C' LAYER ABOVE.	AASHTO M43 <sup>1</sup> 3, 357, 4, 467, 5, 56, 57	NO COMPACTION REQUIRED.
A	FOUNDATION STONE: FILL BELOW CHAMBERS FROM THE SUBGRADE UP TO THE FOOT (BOTTOM) OF THE CHAMBER.	AASHTO M43 <sup>1</sup> 3, 357, 4, 467, 5, 56, 57	PLATE COMPACT OR ROLL TO ACHIEVE A FLAT SURFACE. <sup>2,3</sup>

- PLEASE NOTE:
- THE LISTED AASHTO DESIGNATIONS ARE FOR GRADATIONS ONLY. THE STONE MUST ALSO BE CLEAN, CRUSHED, ANGULAR. FOR EXAMPLE, A SPECIFICATION FOR R4 STONE WOULD STATE: "CLEAN, CRUSHED, ANGULAR NO. 4 (AASHTO M43) STONE".
  - STORMTECH COMPACTION REQUIREMENTS ARE MET FOR 'A' LOCATION MATERIALS WHEN PLACED AND COMPACTED IN 6" (150 mm) MAX LIFTS USING TWO FULL COVERS WITH A VIBRATORY COMPACTOR.
  - WHERE INFILTRATION SURFACES MAY BE COMPROMISED BY COMPACTION, FOR STANDARD DESIGN LOAD CONDITIONS, A FLAT SURFACE MAY BE ACHIEVED BY RAKING OR DRAGGING WITHOUT COMPACTION EQUIPMENT. FOR SPECIAL LOAD DESIGNS, CONTACT STORMTECH FOR COMPACTION REQUIREMENTS.
  - ONCE LAYER 'C' IS PLACED, ANY SOIL/MATERIAL CAN BE PLACED IN LAYER 'D' UP TO THE FINISHED GRADE. MOST PAVEMENT SUBBASE SOILS CAN BE USED TO REPLACE THE MATERIAL. REQUIREMENTS OF LAYER 'C' OR 'D' AT THE SITE DESIGN ENGINEER'S DISCRETION.

### 3 SC-310 ISOLATOR ROW PLUS DETAIL



### INSPECTION & MAINTENANCE

- STEP 1) INSPECT ISOLATOR ROW PLUS FOR SEDIMENT
- INSPECTION PORTS (IF PRESENT)
  - REMOVE OPEN LIDS ON NYLONPLAST INLINE DRAIN
  - REMOVE AND CLEAN FLEXSTORM FILTER IF INSTALLED
  - USING A FLASHLIGHT AND STADIA ROD, MEASURE DEPTH OF SEDIMENT AND RECORD ON MAINTENANCE LOG
  - LOWER A CAMERA INTO ISOLATOR ROW PLUS FOR VISUAL INSPECTION OF SEDIMENT LEVELS (OPTIONAL)
  - IF SEDIMENT IS AT, OR ABOVE, 3" (80 mm) PROCEED TO STEP 2. IF NOT, PROCEED TO STEP 3.
- B. ALL ISOLATOR PLUS ROWS
- REMOVE COVER FROM STRUCTURE AT UPSTREAM END OF ISOLATOR ROW PLUS USING A FLASHLIGHT. INSPECT DOWN THE ISOLATOR ROW PLUS THROUGH OUTLET PIPE
  - MIRRORS ON POLES OR CAMERAS MAY BE USED TO AVOID A CONFINED SPACE ENTRY
  - FOLLOW OSHA REGULATIONS FOR CONFINED SPACE ENTRY IF ENTERING MANHOLE
  - IF SEDIMENT IS AT, OR ABOVE, 3" (80 mm) PROCEED TO STEP 2. IF NOT, PROCEED TO STEP 3.
- STEP 2) CLEAN OUT ISOLATOR ROW PLUS USING THE JETVAC PROCESS
- A FIXED CULVERT CLEANING NOZZLE WITH REAR FACING SPREAD OF 45° (1.1 m) OR MORE IS PREFERRED
  - APPLY MULTIPLE PASSES OF JETVAC UNTIL BACKFLUSH WATER IS CLEAN
  - VACUUM STRUCTURE SUMP AS REQUIRED
- STEP 3) REPLACE ALL COVERS, GRATES, FILTERS, AND LIDS. RECORD OBSERVATIONS AND ACTIONS.
- STEP 4) INSPECT AND CLEAN BASINS AND MANHOLES UPSTREAM OF THE STORMTECH SYSTEM.

- NOTES
- INSPECT EVERY 6 MONTHS DURING THE FIRST YEAR OF OPERATION. ADJUST THE INSPECTION INTERVAL BASED ON PREVIOUS OBSERVATIONS OF SEDIMENT ACCUMULATION AND HIGH WATER ELEVATIONS.
  - CONDUCT JETTING AND VACTORING ANNUALLY OR WHEN INSPECTION SHOWS THAT MAINTENANCE IS NECESSARY.

### 4 4" PVC INSPECTION PORT DETAIL (SC SERIES CHAMBER)



### 1 SC-310 CROSS SECTION DETAIL



- NOTES:
- CHAMBERS SHALL MEET THE REQUIREMENTS OF ASTM F2922 (POLYETHYLENE) OR ASTM F2418 (POLYPROPYLENE), "STANDARD SPECIFICATION FOR CORRUGATED WALL STORMWATER COLLECTION CHAMBERS".
  - SC-310 CHAMBERS SHALL BE DESIGNED IN ACCORDANCE WITH ASTM F2787 "STANDARD PRACTICE FOR STRUCTURAL DESIGN OF THERMOPLASTIC CORRUGATED WALL STORMWATER COLLECTION CHAMBERS".
  - THE SITE DESIGN ENGINEER IS RESPONSIBLE FOR ASSESSING THE BEARING RESISTANCE (ALLOWABLE BEARING CAPACITY) OF THE SUBGRADE SOILS AND THE DEPTH OF FOUNDATION STONE WITH CONSIDERATION FOR THE RANGE OF EXPECTED SOIL MOISTURE CONDITIONS.
  - PERIMETER STONE MUST BE EXTENDED HORIZONTALLY TO THE EXCAVATION WALL FOR BOTH VERTICAL AND SLOPED EXCAVATION WALLS.
  - REQUIREMENTS FOR HANDLING AND INSTALLATION:
    - TO MAINTAIN THE WIDTH OF CHAMBERS DURING SHIPPING AND HANDLING, CHAMBERS SHALL HAVE INTEGRAL, INTERLOCKING STACKING LUGS.
    - TO ENSURE A SECURE JOINT DURING INSTALLATION AND BACKFILL, THE HEIGHT OF THE CHAMBER JOINT SHALL NOT BE LESS THAN 2".
    - TO ENSURE THE INTEGRITY OF THE ARCH SHAPE DURING INSTALLATION, THE ARCH STIFFNESS CONSTANT AS DEFINED IN SECTION 6.2.8 OF ASTM F2922 SHALL BE GREATER THAN OR EQUAL TO 400 LB/FT<sup>2</sup>. AND B) TO RESIST CHAMBER DEFORMATION DURING INSTALLATION AT ELEVATED TEMPERATURES (ABOVE 73° F / 23° C), CHAMBERS SHALL BE PRODUCED FROM REFLECTIVE GOLD OR YELLOW COLORS.

DATE: PROJECT NO: NOT TO SCALE

DRAWN: REVIEWED: REV: SC-310 STANDARD DETAILS

StormTech Chamber System 888-892-2694 | WWW.STORMTECH.COM

4840 TRUENAM BLVD HILLIARD, OH 43026

ADS Advanced Drainage Systems, Inc.

SHEET



AAI ajghian associates, inc. ENGINEERING

4875 SW Griffin Drive | Suite 300 | Beaverton, OR 97005  
503.620.3630 | 503.620.5539 | www.aaing.com

119 N PACIFIC HWY WOODBURN, OR

SHEET TITLE DETAILS

DATE: 12/13/21

DRAWN: JS

CHECKED: CFT

REVISIONS:

AAI ENGINEERING INC. 2023. ALL RIGHTS RESERVED

THESE DRAWINGS ARE THE PROPERTY OF AAI ENGINEERING INC. AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER, EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF AAI ENGINEERING INC.

SHEET NUMBER

C4.3

# Storm Report



119 N Pacific Hwy

**STORMWATER REPORT & CALCULATIONS**

Woodburn, Oregon  
97071



EXPIRES: 6/30/2024

*Revised February 24, 2023*

February 08 , 2022

PROJECT NUMBER: A21152.10

Christopher Thornton, PE

**AAI Engineering**

4875 S.W. Griffith Drive

Suite 100

Beaverton, Oregon

PH 503.620.3030

FX 503.620.5539

EMAIL: christophert@aaieng.com

# 119 N Pacific Hwy

## Table of Contents

I.	Project Summary .....	1
II.	Stormwater Design.....	1
III.	Calculations .....	2
IV.	Operations and Maintenance.....	2
V.	Engineering Conclusion .....	2

## Appendices

Appendix A

Existing Conditions

Appendix B

Site Plan

Appendix C

Storm Plan and Details

Appendix D

Stormwater Calculations

Appendix E

Operations and Maintenance

# 119 N Pacific Hwy

## I. Project Summary

This report has been prepared to outline the existing and proposed on-site stormwater conditions for the 119 N Pacific Hwy project. The report is based off topographic survey and field observation.

The project is located at 119 N Pacific Hwy in Woodburn, Oregon. The total pre-developed site is approximately 1.38 acres. The site currently consists of an open field with gravel and dispersed vegetation, and is relatively flat.

See Appendix A – Existing Conditions

The primary purpose of this project is to develop the site for a new building with driveways, pedestrian connection and associated utilities. In addition to the site improvements, stormwater management will be provided, including conveyance and flow control.

See Appendix B – Site Plan and Appendix C – Storm Plan and Details.

## II. Stormwater Design

At the time of writing, additional information regarding the existing storm connection point is forthcoming. As such, the onsite storm system has been conservatively designed with respect to the available depth to invert at the site's outfall connection point.

The proposed stormwater facilities are designed to capture, convey, and detain runoff from the proposed site improvements. No runoff from adjacent properties is anticipated to be captured by the proposed facilities. In addition, site impervious runoff will be completely managed on site and will not drain onto adjacent private properties.

The stormwater runoff from the roof area will be directed into downspouts and be conveyed to the detention system by underground piping. Stormwater runoff from pavement, parking, and sidewalk areas will sheet flow into sumped and trapped catch basins and be similarly conveyed to the onsite detention system.

Per Table 7-1 of the City of Woodburn Stormwater Drainage Master Plan, a 10-acre site needs to provided a minimum of 18,883 cubic feet of storage. The proposed site area is 1.38 acres. By proportionality, a minimum of 2,605 cubic feet of storage must be provided for this site. The use of an underground chamber storage facility is proposed to provide 3,542 cubic feet of storage. The proposed detention volume meets those required by Table 7-1. A copy of this table has been provided in Appendix D - Stormwater Calculations.

Per the City's Stormwater Drainage Master Plan Runoff Detention Requirement, flow control for the onsite detention must limit the post-development 25-year outflow to no more than the 5-year

# 119 N Pacific Hwy

undeveloped site peak runoff. With the use of a flow control manhole in conjunction with the proposed detention system, the site is designed to meet this requirement.

See Appendix D – Storm Calculations, Appendix E – HydroCAD Report, and Appendix F – Geotech Report

## **III. Calculations**

HydroCAD has been used to verify detention sizing and to design the flow control orifices at the site's outfall, following the storm intensities and durations outlined in Table 7-1 of the City of Woodburn Stormwater Drainage Master Plan. Conveyance calculations have been completed using Manning's Equation for pipe flow, utilizing the appropriate ODOT IDF Curve for the lowest duration 25-year storm. A copy of the IDF curve used has been included in this report.

See Appendix D – Stormwater Calculations

## **IV. Operations and Maintenance**

See Appendix E – Operations and Maintenance for O&M requirements.


## **V. Engineering Conclusion**

Based on the requirements of the City of Woodburn Management Manual, the proposed site facilities will be adequately designed to manage the proposed development.

# 119 N Pacific Hwy


Appendix A  
Existing Conditions





DISCLAIMER: THE BOUNDARY AS SHOWN IS PRELIMINARY. FURTHER FIELD SURVEY SEARCH FOR ADDITIONAL MONUMENTS AND REFERENCES IS ONGOING.

SURVEY FOR: SILCO COMMERCIAL CONSTRUCTION	
LOCATION: 119 N PACIFIC HWY (SH 99E) WOODBURN, OR 97071	
NW 1/4 SECTION 17 T5S, R1W, W.M. CITY OF WOODBURN MARION COUNTY, OREGON	
<b>L</b> AZER <b>S</b> ITE / <b>R</b> IVERSIDE SURVEYING, LLC	CREW: TP/EG/CG REVIEW: R.J.G./M.A.T. SCALE: 1"=20'
2003 25TH STREET S.E. SALEM, OREGON 97302 FAX (503) 581-0901	JOB NO.: 2021-012 SHEET DATE: 06/18/2021 1 OF 1



**SHEET NOTES**

1. SEE C0.1 FOR GENERAL SHEET NOTES.

**EASEMENT NOTE 1:**

UNABLE TO FIND EXHIBIT "A" MENTIONED IN DEED VOLUME 481 PAGE 82 FOR THIS SECTION OF SEWER LINE. USED WOODBURN UTILITY MAP SECTION 35-MC21-39 TO SHOW APPROXIMATE/GENERAL LOCATION.

BOTH SEWER EASEMENTS DEEDS FOR TAX LOT 7400 AND 7300 HAVE A GENERAL STATEMENT AS FOLLOWS; "A PERMANENT EASEMENT AND RIGHT-OF-WAY OF SUCH WIDTH AS MAY BE REASONABLY NECESSARY TO ACCOMPLISH THE PURPOSE OF THIS EASEMENT AS HEREIN AFTER SET FORTH UPON, OVER, UNDER AND ACROSS THE REAL PROPERTY". THIS WOULD THEN POINT TO THE LOCATION OF THE EXISTING LINE, AND WOULD BE THE EASEMENT AS SHOWN BY THE WOODBURN UTILITIES MAPS AS SHOWN HEREON.

**EASEMENT NOTE 2:**

R. 3657, P. 369, PERMANENT EASEMENT FOR SIDEWALK, WATER, GAS, ELECTRIC AND COMMUNICATION SERVICE LINES, FIXTURES AND FACILITIES.



119 N PACIFIC HWY  
WOODBURN, OR

SHEET TITLE

**EXISTING  
CONDITIONS  
PLAN**

DATE: 12/13/21

DRAWN: JS

CHECKED: CFT

REVISIONS:

© AAI ENGINEERING INC. 2023. ALL RIGHTS RESERVED

THESE DRAWINGS ARE THE PROPERTY OF AAI ENGINEERING INC. AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF AAI ENGINEERING INC.

SHEET NUMBER

**C0.2**


JOB NUMBER: A21194.10

# 119 N Pacific Hwy

## Appendix B

Site Plan

F:\2021\A21194.10 - 119 N Pacific Hwy - Woodburn\Civil\Cad\Sheets\Onsite\A21194.C1.0 SITE.dwg : Feb. 27, 23 - 2:48 PM Indanel



**SHEET NOTES**


1. SEE SHEET C0.1 FOR GENERAL SHEET NOTES.
2. SEE ARCHITECTURAL PLANS FOR ADDITIONAL SITE INFORMATION.
3. THE CONTRACTOR SHALL HAVE A FULL SET OF THE CURRENT APPROVED CONSTRUCTION DOCUMENTS INCLUDING ADDENDA ON THE PROJECT SITE AT ALL TIMES.
4. THE CONTRACTOR SHALL KEEP THE ENGINEER AND JURISDICTION INFORMED OF CONSTRUCTION PROGRESS TO FACILITATE SITE OBSERVATIONS AT REQUIRED INTERVALS. 24-HOUR NOTICE IS REQUIRED.

**(X) CONSTRUCTION NOTES**

1. INSTALL CURB PER DETAIL 1/C4.0
2. INSTALL SIDEWALK PER CITY OF WOODBURN DETAIL 4150-8/C4.0
3. INSTALL ASPHALT SURFACE PER DETAIL 2/C4.0
4. INSTALL UNIT PAVER SURFACE, DESIGN BY OTHERS
5. INSTALL ADA RAMP TYPE 5 PER DETAIL 6/C4.0
6. INSTALL ADA STRIPING PER DETAIL 3/C4.0
7. INSTALL STRIPING, SEE ARCHITECTURAL PLANS FOR DETAILS
8. INSTALL DRIVEWAY PER DETAIL 4150-1/C4.0
9. INSTALL WHEELSTOP PER DETAIL 5/C4.0
10. INSTALL TRASH ENCLOSURE, DESIGN BY OTHERS
11. INSTALL RETAINING WALL, DESIGN BY OTHERS
12. INSTALL SIDEWALK PER DETAIL 7/C4.0
13. INSTALL BIKE PARKING. SEE ARCHITECTURAL PLANS FOR MORE INFORMATION.
14. INSTALL REMOVABLE BOLLARDS PER DETAIL 2/C4.2
15. INSTALL FENCE. SEE ARCHITECTURAL PLANS FOR MORE INFORMATION.

**LEGEND**

PROPERTY LINE	---
CONCRETE SIDEWALK SURFACING	[Pattern]
ASPHALT SURFACING	[Pattern]
EASEMENT BOUNDARY	---



**AAI ENGINEERING**  
 4875 SW Griffin Drive | Suite 300 | Beaverton, OR 97005  
 503.620.3600 | 503.620.5539 | www.aaieng.com

**119 N PACIFIC HWY**  
 WOODBURN, OR

SHEET TITLE

**HARDSCAPE PLAN**

DATE: 12/13/21

DRAWN: JS

CHECKED: CFT

REVISIONS:

© AAI ENGINEERING INC. 2023. ALL RIGHTS RESERVED.

THESE DRAWINGS ARE THE PROPERTY OF AAI ENGINEERING INC. AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF AAI ENGINEERING INC.

SHEET NUMBER

**C1.0**

JOB NUMBER: A21194.10

# 119 N Pacific Hwy

## Appendix C

Storm Plan and Details



**AAI ENGINEERING**  
 REGISTERED PROFESSIONAL ENGINEER  
 4875 SW Griffin Drive | Suite 300 | Beaverton, OR 97005  
 503.620.3600 | 503.620.5839 | www.aaieng.com

**119 N PACIFIC HWY**  
 WOODBURN, OR

SHEET TITLE

**BASIN MAP**

DATE: 12/13/21

DRAWN: JS

CHECKED: CFT

REVISIONS:

© AAI ENGINEERING INC. 2023. ALL RIGHTS RESERVED.

THESE DRAWINGS ARE THE PROPERTY OF AAI ENGINEERING INC. AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER, EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF AAI ENGINEERING INC.

SHEET NUMBER

**EX1.0**

JOB NUMBER: A21194.10

**LEGEND**


PROPERTY LINE	---
DRAINAGE BASIN BOUNDARY	- - - - -
DRAINAGE BASIN NUMBER	(X)
IMPERVIOUS COVER	▨
STORM LINE	— — — — —

**STRUCTURE TYPES**


TYPE	DESCRIPTION
CB	CATCH BASIN
FCMH	FLOW CONTROL MANHOLE
MH	MANHOLE
RD	ROOF DRAIN CONNECTION

**IMPERVIOUS AREA CALCULATIONS**

DRAINAGE BASIN #	TOTAL AREA (SF)	IMPERVIOUS (SF)	PERVIOUS (SF)
1	7,544	4,939	2,606
2	14,375	14,375	0
3	1,688	1,542	146
4	5,215	5,059	156
5	7,807	7,235	572
6	1,577	1,529	48
7	5,978	5,424	554
8	2,449	2,400	49
9	8,226	6,763	1,463



STATE HWY 99E



F:\2021\A21194.10 - 119 N Pacific Hwy - Woodburn\docs\Reports\Storm\_Report\A21194.Basin\_Map.dwg : Feb. 27, 23 - 2:31 PM Indriel



**AAI ENGINEERING**  
 4875 SW Griffin Drive | Suite 300 | Beaverton, OR 97005  
 503.620.3600 | 503.620.5539 | www.aaieng.com

**119 N PACIFIC HWY**  
 WOODBURN, OR

SHEET TITLE

**STORMWATER PLAN**

DATE: 12/13/21

DRAWN: JS

CHECKED: CFT

REVISIONS:

© AAI ENGINEERING INC. 2023. ALL RIGHTS RESERVED.

THESE DRAWINGS ARE THE PROPERTY OF AAI ENGINEERING INC. AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER, EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF AAI ENGINEERING INC.

SHEET NUMBER

JOB NUMBER: A21194.10

**SHEET NOTES**

- SEE SHEET C0.1 FOR GENERAL SHEET NOTES.
- STRUCTURES HORIZONTAL LOCATIONS AND PIPE INVERTS ARE BASED ON THE CENTER OF THE STRUCTURE.
- PIPE BEDDING AND BACKFILL UTILITIES SHALL BE DONE PER DETAIL 1/C4.1.
- INSTALL THRUST BLOCKS ON FIRE AND WATER LINES PER DETAIL 2/C4.1.
- ALL SANITARY PIPING SHALL BE PVC 3034 OR APPROVED EQUAL UNLESS NOTED OTHERWISE.
- THIS PLAN IS GENERALLY DIAGRAMMATIC. IT DOES NOT SHOW EVERY JOINT, BEND, FITTING, OR ACCESSORY REQUIRED FOR CONSTRUCTION.
- CLEAN OUTS SHALL BE INSTALLED IN CONFORMANCE WITH UPC CHAPTER SEVEN, SECTION 707 AND SECTION 719. THIS PLAN MAY NOT SHOW ALL REQUIRED CLEAN OUTS.
- DOMESTIC WATER AND FIRE LINES AND ACCESSORIES BETWEEN THE WATER METER AND THE BUILDING SHALL BE INSTALLED BY A LICENSED PLUMBER EMPLOYED BY A LICENSED PLUMBING CONTRACTOR.
- UTILITIES WITHIN FIVE FEET OF A BUILDING SHALL BE CONSTRUCTED OF MATERIALS APPROVED FOR INTERIOR USE AS DESCRIBED IN THE CURRENT EDITION OF THE UPC.
- INLETS AND OUTLETS TO ON-SITE MANHOLES SHALL HAVE FLEXIBLE CONNECTION NO CLOSER THAN 12" AND NO FARTHER THAN 36" FROM THE MANHOLE.
- CONTRACTOR TO VERIFY SANITARY AND WATER SIZING AND INVERTS WITH APPROVED PLUMBING PLANS PRIOR TO ORDERING MATERIALS OR BEGINNING CONSTRUCTION OF SAID UTILITIES.
- ALL STORM AND SANITARY FITTINGS TO BE ECCENTRIC FITTINGS UNLESS OTHERWISE NOTED.

**LABEL LEGEND**

**PIPE LABELS**

- UTILITY LENGTH
- UTILITY SIZE
- XXLF - XX" XX ← UTILITY TYPE
- S=X.XXX ← SLOPE (WHERE APPLICABLE)

**STRUCTURE LABELS**

- UTILITY TYPE (FP=FIRE PROTECTION, S=SANITARY, SD=STORM DRAINAGE, W=WATER)
- STRUCTURE TYPE (SEE BELOW)
- XX XX-XX ← ID NUMBER (WHERE APPLICABLE)
- RIM=XX.XX ← STRUCTURE INFO (WHERE APPLICABLE)

**STRUCTURE TYPES**

TYPE	DESCRIPTION
CB	CATCH BASIN PER DETAIL 3/C4.1
CO	CLEANOUT PER DETAIL 3/C4.2
FCMH	FLOW CONTROL MANHOLE PER DETAIL 8/C4.1
MH	MAINTENANCE MANHOLE PER DETAIL 7/C4.1
RD	ROOF DRAIN CONNECTION - REFER TO PLUMBING PLANS

**LEGEND**

SANITARY SEWER LINE	SS
WATER LINE	W
FIRE LINE	FP
FDC LINE	FDC
STORM LINE	SD

**STORM NOTES**

- INSTALL UNDERGROUND STORM WATER DETENTION FACILITY. (108) SC-310 STORMTECH CHAMBERS WITHIN A ROCK SECTION THAT HAS A FOOTPRINT OF 2,774 SF PER DETAILS ON SHEET C4.3. WRAP ENTIRE ROCK SECTION IN GEOSYNTHETIC FABRIC.
- CONNECT TO EXISTING STORM STUB PER CITY OF WOODBURN GIS. CONTRACTOR TO LOCATE EXISTING STORM LINE PRIOR CONSTRUCTION AND NOTIFY ENGINEER OF FINDINGS. INVERT SHOWN IS APPROXIMATE.


NORTH




GRAPHIC SCALE



( IN FEET )  
1 inch = 20 feet




F:\2021\A21194.10 - 119 N Pacific Hwy - Woodburn\Civil\Sheets\Onsite\A21194\_C3.0\_UTL.dwg : Feb. 27, 23 - 12:06 PM hdmel



**1 TYPICAL PIPE BEDDING AND BACKFILL**

SCALE: NTS



- CONCRETE THRUST BLOCKING TO BE POURED AGAINST UNDISTURBED EARTH.
- KEEP CONCRETE CLEAR OF JOINT AND ACCESSORIES.
- THE REQUIRED THRUST BEARING AREAS FOR SPECIAL CONNECTIONS ARE SHOWN ENCIRCLED ON THE PLAN; e.g. 19 INDICATES 15 SQUARE FEET BEARING AREA REQUIRED.
- IF NOT SHOWN ON PLANS REQUIRED BEARING AREAS AT FITTING SHALL BE AS INDICATED BELOW, ADJUST IF NECESSARY, TO CONFORM TO THE TEST PRESSURE(S) AND ALLOWABLE SOIL BEARING STRESS (ES) STATED IN THE SPECIAL SPECIFICATIONS.
- BEARING AREAS AND SPECIAL BLOCKING DETAILS SHOWN ON PLANS TAKE PRECEDENCE OVER BEARING AREAS AND BLOCKING DETAILS SHOWN ON THIS STANDARD DETAIL.


BEARING AREA OF THRUST BLOCK IN SQUARE FOOT

FITTING SIZE	TEE PLUGGED ON RUN		90° BEND PLUGGED CROSS	45° BEND	22½° BEND	11½° BEND
	A1	A2				
4	1.0	1.4	1.9	1.4	1.0	
6	2.1	3.0	4.3	3.0	1.6	1.0
8	3.8	5.3	7.6	5.4	2.9	1.5
10	5.9	8.4	11.8	8.4	4.6	2.4

NOTE: ABOVE BEARING AREAS BASED ON TEST PRESSURE OF 150 p.s.i. AND AN ALLOWABLE SOIL BEARING STRESS OF 2000 p.s.i.. TO COMPUTE BEARING AREAS FOR DIFFERENT TEST PRESSURE AND SOIL BEARING STRESSES, USE THE FOLLOWING EQUATION: BEARING AREA = (TEST PRESSURE/150)X(2000/ SOIL BEARING STRESS)X(TABLE VALUE).

**2 THRUST BLOCK**

SCALE: NTS




**3 TRAPPED CATCH BASIN**

SCALE: NTS

- NOTES:
- CONTRACTOR TO WIDEN EXCAVATION AS REQUIRED TO OBTAIN COMPACTION WITH CONTRACTORS COMPACTION EQUIPMENT.
  - 1/4" STEEL PLATE, BITUMINOUS COATED. AS MANUFACTURED BY GIBSON STEEL BASINS OR APPROVED EQUAL.

**3 TRAPPED CATCH BASIN**


SCALE: NTS



**4 DOUBLE CHECK DETECTOR ASSEMBLY FIRE SERVICE VAULT W/ DRAIN TO GROUND**

SCALE: NTS

D.D.C. SIZE	UTILITY VAULT OR EQUAL WITH F.D.C.		WITHOUT F.D.C.	BILCO DOOR OR EQUAL
	676 - WA	577 - WA		
4"	676 - WA	577 - WA		J - 5AL
6"	687 - WA	676 - WA		J - 5AL
8"	5106 - LA	687 - WA		JD - 3AL
10"	5106 - LA	5106 - LA		JD - 3AL



- NOTES:
- CONCRETE ANCHOR PAD TO BE 12"x12"x6" THICK, UNLESS NOTED OTHERWISE. ELIMINATE IF INSTALLED IN CONCRETE PAVED AREA.
  - USE FLANGE OR THREADED FITTINGS.
  - CONTRACTOR SHALL PROVIDE SINGLE CHECK VALVE AND BALL DRIP VALVE IN ACCESSIBLE LOCATION INSIDE DDC VAULT. COORDINATE WITH PLUMBING.


**5 FIRE DEPARTMENT CONNECTION (FDC) DUAL PORT**

SCALE: NTS

- NOTES:
- LAY PERFORATED DRAIN PIPE ON MIN. 0.5% GRADIENT, WIDENING EXCAVATION AS REQUIRED. MAINTAIN PIPE ABOVE 2:1 SLOPE AS SHOWN.
  - CONNECT TO FOUNDATION DRAIN STUBOUT SHOWN ON PLANS.

**6 PERIMETER FOUNDATION DRAIN**

SCALE: NTS




- NOTES:
- ALL PRECAST SECTIONS SHALL CONFORM TO REQUIREMENTS OF ASTM C-478.
  - MANHOLE BASE MAY BE PRECAST OR CAST IN PLACE. SEE STANDARD MANHOLE BASE DETAILS.
  - ALL CONNECTING PIPES SHALL HAVE FLEXIBLE, GASKETED AND UNRESTRAINED JOINT WITHIN 18" OF MANHOLE VAULT.

**7 STANDARD MANHOLE**

SCALE: NTS


**FLOW CONTROL ORIFICE SIZING**

STRUCTURE	2-YR (RESTRICTOR PLATE INVERT)	EMERGENCY OVERFLOW
FCMH-01	1.6" Ø @ 182.40	18" Ø @ 186.52



**8 FLOW CONTROL MANHOLE**

SCALE: NTS



**AAI ENGINEERING**  
 4875 SW Griffin Drive, Suite 300 | Beaverton, OR 97005  
 503.620.3600 | 503.620.5539 fax | www.aaieng.com

**119 N PACIFIC HWY**  
 WOODBURN, OR

SHEET TITLE

**DETAILS**

DATE: 12/13/21

DRAWN: JS

CHECKED: CFT

REVISIONS:



© AAI ENGINEERING INC. 2023. ALL RIGHTS RESERVED.

THESE DRAWINGS ARE THE PROPERTY OF AAI ENGINEERING INC. AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER, EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF AAI ENGINEERING INC.

SHEET NUMBER


**C4.1**

JOB NUMBER: A21194.10




NOTE: INSTALLATION SHOWN IS ONLY A SUGGESTION. THE DISTANCE FROM BOTTOM OF DEVICE TO FINISH GRADE, FREEZE PROTECTION, AND CLEARANCE FOR TESTING & REPAIR ARE THE MAJOR CONSIDERATIONS FOR INSTALLATION. PLUGS TO BE INSTALLED IN TEST COCKS OF BELOW GROUND INSTALLATIONS (NO DISSIMILAR METALS). IF FREEZE PROTECTION IS PROVIDED, THE 24" MIN CLEARANCE MAY BE REDUCED.

**1 DOUBLE CHECK BACKFLOW ASSEMBLY**  
SCALE: NTS



NOTES:  
1. CAST IRON FRAME AND COVER SHALL MEET H-20 LOAD REQUIREMENT.  
2. FOR CARRIER PIPE SIZE 6"Ø AND LESS, PROVIDE RISER PIPE SIZE TO MATCH CARRIER PIPE.  
3. FOR CARRIER PIPE SIZE 8"Ø AND LARGER, RISER PIPE SHALL BE 6"Ø.  
4. RISER PIPE MATERIAL TO MATCH CARRIER PIPE MATERIAL.

**3 STANDARD CLEANOUT (COTG)**  
SCALE: NTS



**2 REMOVABLE PIPE BOLLARD**  
SCALE: NTS

BROOKS PRODUCTS		
COVER	METER BOX	
DIA.	MODEL NO.	
1"	No. 37-T CAST IRON COVER*	No. 37 MB-BODY*
2"	No. 65-TF STEEL COVER (FLUSH)*	No. 65 MB-BODY*
* OR APPROVED EQUAL		

FOR DROP-IN COVER SEE TABLE ABOVE

FOR METER BOX SEE TABLE ABOVE

**WOODBURN**  
Incorporated 1889  
PUBLIC WORKS DEPARTMENT  
ENGINEERING DIVISION

**METER BOX**

REV: FEB 2020  
SCALE: NTS  
DET No. **5050-1**

NOTES:  
1. BED PIPE WITH 1"-MINUS SO AS TO CARRY LOAD OF PIPE EVENLY WITHOUT FIXING LOAD ON PIER BLOCKS DIG OUT BELOW BED FOR PIER BLOCKS, AS DIRECTED.  
2. BURY HEIGHT: 3-1/2 TO 4 FEET. IF GREATER DEPTH IS REQUIRED EXTENSIONS SHALL BE USED TO ADJUST FH TO PROPER HEIGHT.  
3. BACK FILL SHALL BE OF TYPE SPECIFIED.  
4. D.I. PIPE BETWEEN VALVE AND FH SHALL BE BY MEANS OF MECHANICAL JOINT WITH MEGALUG PIPE CONNECTORS OR COATED THREADED THE RODS, AS APPROVED.

HYDRANT: MUELLER CENTURION A423 OR M & H RELIANT 929T. REFERENCE TECHNICAL SPEC. SECTION 5070.

CONCRETE THRUST BLOCK SEE DETAILS 5000-1 & 2

PIPE ZONE TO BE TYPE 'D' AS SHOWN IN STANDARD DETAIL 3800-2.

**WOODBURN**  
Incorporated 1889  
PUBLIC WORKS DEPARTMENT  
ENGINEERING DIVISION

**FIRE HYDRANT ASSEMBLY**

REV: FEB 2020  
SCALE: NTS  
DET No. **5070-1**

FORD CO. MODEL		
CORP STOP	ANGLE METER VALVE	
DIA.	Model No.	
1"	F1000-4"	KV43-444W*
1.5"	FB500-6"	FV43-666W*
2"	FB500-7"	FV43-777W*
* OR APPROVED EQUAL		

PROPERTY LINE RIGHT-OF-WAY

UTILITY EASEMENT

18" MIN.

2"

METER BOX SEE DETAIL 5050-1

WATER METER SEE NOTE 1

FOR ANGLE METER VALVE SEE TABLE ABOVE.

30"

36" NORMAL COVER

45°

TYPE "K" COPPER TUBING

FOR CORPORATION STOP SEE TABLE ABOVE. SET TAP AT 45° IN DIRECTION OF METER.

D.I. WATER MAIN, TYP.

NOTES:  
1. WATER METER AND TAILPIECE SHALL BE FURNISHED AND INSTALLED BY CITY WATER DIVISION.  
2. WATER DIVISION SHALL HAVE SOLE RESPONSIBILITY FOR TAPPING LIVE MAINS.  
3. REFERENCE TECHNICAL SPEC. SECTION 5000.  
4. 1.5" & 2" SERVICE LINES SHALL BE SADDLE TAPPED WITH BRONZE DOUBLE STRAPS.

**WOODBURN**  
Incorporated 1889  
PUBLIC WORKS DEPARTMENT  
ENGINEERING DIVISION

**WATER SERVICE CONNECTION**

REV: MAY 2011  
SCALE: NTS  
DET No. **5000-4**



**AAI ENGINEERING**  
INCORPORATED  
4875 SW Griffin Drive | Suite 300 | Beaverton, OR 97005  
503.620.3600 | 503.620.5539 | www.aaieng.com

119 N PACIFIC HWY  
WOODBURN, OR

SHEET TITLE

**DETAILS**

DATE: 12/13/21

DRAWN: JS

CHECKED: CFT

REVISIONS:

© AAI ENGINEERING INC. 2023. ALL RIGHTS RESERVED.

THESE DRAWINGS ARE THE PROPERTY OF AAI ENGINEERING INC. AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF AAI ENGINEERING INC.

SHEET NUMBER

**C4.2**

JOB NUMBER: A21194.10





119 N PACIFIC HWY WOODBURN, OR

### SC-310 STORMTECH CHAMBER SPECIFICATIONS

- CHAMBERS SHALL BE STORMTECH SC-310.
- CHAMBERS SHALL BE ARCH-SHAPED AND SHALL BE MANUFACTURED FROM VIRGIN, IMPACT-MODIFIED POLYPROPYLENE OR POLYETHYLENE COPOLYMERS.
- CHAMBERS SHALL MEET THE REQUIREMENTS OF ASTM F2922 (POLYETHYLENE) OR ASTM F2418 (POLYPROPYLENE), "STANDARD SPECIFICATION FOR CORRUGATED WALL STORMWATER COLLECTION CHAMBERS".
- CHAMBER ROWS SHALL PROVIDE CONTINUOUS, UNOBSTRUCTED INTERNAL SPACE WITH NO INTERNAL SUPPORTS THAT WOULD IMPEDE FLOW OR LIMIT ACCESS FOR INSPECTION.
- THE STRUCTURAL DESIGN OF THE CHAMBERS, THE STRUCTURAL BACKFILL, AND THE INSTALLATION REQUIREMENTS SHALL ENSURE THAT THE LOAD FACTORS SPECIFIED IN THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, SECTION 12.12, ARE MET FOR: 1) LONG-DURATION DEAD LOADS AND 2) SHORT-DURATION LIVE LOADS, BASED ON THE AASHTO DESIGN TRUCK WITH CONSIDERATION FOR IMPACT AND MULTIPLE VEHICLE PRESENCES.
- CHAMBERS SHALL BE DESIGNED, TESTED AND ALLOWABLE LOAD CONFIGURATIONS DETERMINED IN ACCORDANCE WITH ASTM F2787, "STANDARD PRACTICE FOR STRUCTURAL DESIGN OF THERMOPLASTIC CORRUGATED WALL STORMWATER COLLECTION CHAMBERS". LOAD CONFIGURATIONS SHALL INCLUDE: 1) INSTANTANEOUS (<1 MIN) AASHTO DESIGN TRUCK LIVE LOAD ON MINIMUM COVER 2) MAXIMUM PERMANENT (75-YR) COVER LOAD AND 3) ALLOWABLE COVER WITH PARKED (1-WEEK) AASHTO DESIGN TRUCK.
- REQUIREMENTS FOR HANDLING AND INSTALLATION:
  - TO MAINTAIN THE WIDTH OF CHAMBERS DURING SHIPPING AND HANDLING, CHAMBERS SHALL HAVE INTEGRAL INTERLOCKING STACKING LUGS.
  - TO ENSURE A SECURE JOINT DURING INSTALLATION AND BACKFILL, THE HEIGHT OF THE CHAMBER JOINT SHALL NOT BE LESS THAN 2".
  - TO ENSURE THE INTEGRITY OF THE ARCH SHAPE DURING INSTALLATION, THE ARCH STIFFNESS CONSTANT SHALL BE GREATER THAN OR EQUAL TO 400 LB/FT<sup>2</sup>. THE ASC IS DEFINED IN SECTION 6.2.8 OF ASTM F2418. AND b) TO RESIST CHAMBER DEFORMATION DURING INSTALLATION AT ELEVATED TEMPERATURES (ABOVE 73° F / 23° C), CHAMBERS SHALL BE PRODUCED FROM REFLECTIVE GOLD OR YELLOW COLORS.
- ONLY CHAMBERS THAT ARE APPROVED BY THE SITE DESIGN ENGINEER WILL BE ALLOWED. UPON REQUEST BY THE SITE DESIGN ENGINEER OR OWNER, THE CHAMBER MANUFACTURER SHALL SUBMIT A STRUCTURAL EVALUATION FOR APPROVAL BEFORE DELIVERING CHAMBERS TO THE PROJECT SITE AS FOLLOWS:
  - THE STRUCTURAL EVALUATION SHALL BE SEALED BY A REGISTERED PROFESSIONAL ENGINEER.
  - THE STRUCTURAL EVALUATION SHALL DEMONSTRATE THAT THE SAFETY FACTORS ARE GREATER THAN OR EQUAL TO 1.95 FOR DEAD LOAD AND 1.75 FOR LIVE LOAD. THE MINIMUM REQUIRED BY ASTM F2787 AND BY SECTIONS 3 AND 12.12 OF THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS FOR THERMOPLASTIC PIPE.
  - THE TEST DERIVED CREEP MODULUS AS SPECIFIED IN ASTM F2922 SHALL BE USED FOR PERMANENT DEAD LOAD DESIGN EXCEPT THAT IT SHALL BE THE 75-YEAR MODULUS USED FOR DESIGN.
- CHAMBERS AND END CAPS SHALL BE PRODUCED AT AN ISO 9001 CERTIFIED MANUFACTURING FACILITY.

### IMPORTANT - NOTES FOR THE BIDDING AND INSTALLATION OF THE SC-310 SYSTEM




- STORMTECH SC-310 CHAMBERS SHALL NOT BE INSTALLED UNTIL THE MANUFACTURER'S REPRESENTATIVE HAS COMPLETED A PRE-CONSTRUCTION MEETING WITH THE INSTALLERS.
- STORMTECH SC-310 CHAMBERS SHALL BE INSTALLED IN ACCORDANCE WITH THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE".
- CHAMBERS ARE NOT TO BE BACKFILLED WITH A DOZER OR AN EXCAVATOR SITUATED OVER THE CHAMBERS. STORMTECH RECOMMENDS 3 BACKFILL METHODS:
  - STONESHOOTER LOCATED OFF THE CHAMBER BED.
  - BACKFILL AS ROWS ARE BUILT USING AN EXCAVATOR ON THE FOUNDATION STONE OR SUBGRADE.
  - BACKFILL FROM OUTSIDE THE EXCAVATION USING A LONG BOOM HOE OR EXCAVATOR.
- THE FOUNDATION STONE SHALL BE LEVELED AND COMPACTED PRIOR TO PLACING CHAMBERS.
- JOINTS BETWEEN CHAMBERS SHALL BE PROPERLY SEATED PRIOR TO PLACING STONE.
- MAINTAIN MINIMUM - 6" (150 mm) SPACING BETWEEN THE CHAMBER ROWS.
- EMBEDMENT STONE SURROUNDING CHAMBERS MUST BE A CLEAN, CRUSHED, ANGULAR STONE 3/4-2" (20-50 mm).
- THE CONTRACTOR MUST REPORT ANY DISCREPANCIES WITH CHAMBER FOUNDATION MATERIALS BEARING CAPACITIES TO THE SITE DESIGN ENGINEER.
- ADS RECOMMENDS THE USE OF "FLEXSTORM CATCH IT" INSERTS DURING CONSTRUCTION FOR ALL INLETS TO PROTECT THE SUBSURFACE STORMWATER MANAGEMENT SYSTEM FROM CONSTRUCTION SITE RUNOFF.

### NOTES FOR CONSTRUCTION EQUIPMENT

- STORMTECH SC-310 CHAMBERS SHALL BE INSTALLED IN ACCORDANCE WITH THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE".
- THE USE OF CONSTRUCTION EQUIPMENT OVER SC-310 & SC-740 CHAMBERS IS LIMITED:
  - NO EQUIPMENT IS ALLOWED ON BARE CHAMBERS.
  - NO RUBBER Tired LOADERS, DUMP TRUCKS, OR EXCAVATORS ARE ALLOWED UNTIL PROPER FILL DEPTHS ARE REACHED IN ACCORDANCE WITH THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE".
  - WEIGHT LIMITS FOR CONSTRUCTION EQUIPMENT CAN BE FOUND IN THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE".
- FULL 36" (900 mm) OF STABILIZED COVER MATERIALS OVER THE CHAMBERS IS REQUIRED FOR DUMP TRUCK TRAVEL OR DUMPING.

USE OF A DOZER TO PUSH EMBEDMENT STONE BETWEEN THE ROWS OF CHAMBERS MAY CAUSE DAMAGE TO THE CHAMBERS AND IS NOT AN ACCEPTABLE BACKFILL METHOD. ANY CHAMBERS DAMAGED BY THE "DUMP AND PUSH" METHOD ARE NOT COVERED UNDER THE STORMTECH STANDARD WARRANTY.

CONTACT STORMTECH AT 1-888-892-2694 WITH ANY QUESTIONS ON INSTALLATION REQUIREMENTS OR WEIGHT LIMITS FOR CONSTRUCTION EQUIPMENT.



### NOMINAL CHAMBER SPECIFICATIONS

SIZE (W X L X INSTALLED LENGTH)	34.0\"/>	
34.0\"/>	14.7 CUBIC FEET (0.42 m <sup>3</sup> )	884 mm X 406 mm X 2169 mm
MINIMUM INSTALLED STORAGE*	31.0 CUBIC FEET (0.88 m <sup>3</sup> )	
WEIGHT	35.0 lbs.	

\* ASSUMES 6\"/>

PART #	STUB	A	B	C
SC310EPE06T / SC310EPE06TPC	6\"/>	9.6\"/>	5.8\"/>	0.5\"/>
SC310EPE08T / SC310EPE08TPC	8\"/>	11.9\"/>	3.5\"/>	0.6\"/>
SC310EPE10T / SC310EPE10TPC	10\"/>	12.7\"/>	1.4\"/>	0.7\"/>
SC310EPE12B	12\"/>	13.5\"/>	0.9\"/>	0.9\"/>
SC310EPE12BR	12\"/>	13.5\"/>	0.9\"/>	0.9\"/>

ALL STUBS, EXCEPT FOR THE SC310EPE12B ARE PLACED AT BOTTOM OF END CAP SUCH THAT THE OUTSIDE DIAMETER OF THE STUB IS FLUSH WITH THE BOTTOM OF THE END CAP. FOR ADDITIONAL INFORMATION CONTACT STORMTECH AT 1-888-892-2694.

\* FOR THE SC310EPE12B THE 12\"/>

NOTE: ALL DIMENSIONS ARE NOMINAL.

### 6 INSERTA-TEE SIDE INLET DETAIL


### 2 SC-310 TECHNICAL SPECIFICATIONS

### ACCEPTABLE FILL MATERIALS: STORMTECH SC-310 CHAMBER SYSTEMS

MATERIAL LOCATION	DESCRIPTION	AASHTO MATERIAL CLASSIFICATIONS	COMPACTION / DENSITY REQUIREMENT
D	FINAL FILL: FILL MATERIAL FOR LAYER 'D' STARTS FROM THE TOP OF THE 'C' LAYER TO THE BOTTOM OF FLEXIBLE PAVEMENT OR UNPAVED FINISHED GRADE ABOVE. NOTE THAT PAVEMENT SUBBASE MAY BE PART OF THE 'D' LAYER.	N/A	PREPARE PER SITE DESIGN ENGINEER'S PLANS. PAVED INSTALLATIONS MAY HAVE STRINGENT MATERIAL AND PREPARATION REQUIREMENTS.
C	INITIAL FILL: FILL MATERIAL FOR LAYER 'C' STARTS FROM THE TOP OF THE EMBEDMENT STONE ('B' LAYER), TO 18\"/>	AASHTO M45 <sup>1</sup> A-1, A-2-4, A-3 OR AASHTO M43 <sup>1</sup> 3, 357, 4, 467, 5, 56, 57, 6, 67, 68, 7, 78, 8, 89, 9, 10	BEGIN COMPACTIONS AFTER 12\"/>
B	EMBEDMENT STONE: FILL SURROUNDING THE CHAMBERS FROM THE FOUNDATION STONE ('A' LAYER) TO THE 'C' LAYER ABOVE.	AASHTO M43 <sup>1</sup> 3, 357, 4, 467, 5, 56, 57	NO COMPACTION REQUIRED.
A	FOUNDATION STONE: FILL BELOW CHAMBERS FROM THE SUBGRADE UP TO THE FOOT (BOTTOM) OF THE CHAMBER.	AASHTO M43 <sup>1</sup> 3, 357, 4, 467, 5, 56, 57	PLATE COMPACT OR ROLL TO ACHIEVE A FLAT SURFACE. <sup>2,3</sup>

- PLEASE NOTE:
- THE LISTED AASHTO DESIGNATIONS ARE FOR GRADATIONS ONLY. THE STONE MUST ALSO BE CLEAN, CRUSHED, ANGULAR. FOR EXAMPLE, A SPECIFICATION FOR #4 STONE WOULD STATE: "CLEAN, CRUSHED, ANGULAR NO. 4 (AASHTO M43) STONE".
  - STORMTECH COMPACTION REQUIREMENTS ARE MET FOR 'A' LOCATION MATERIALS WHEN PLACED AND COMPACTED IN 6\"/>
  - WHERE INFILTRATION SURFACES MAY BE COMPROMISED BY COMPACTION, FOR STANDARD DESIGN LOAD CONDITIONS, A FLAT SURFACE MAY BE ACHIEVED BY RAKING OR DRAGGING WITHOUT COMPACTION EQUIPMENT. FOR SPECIAL LOAD DESIGNS, CONTACT STORMTECH FOR COMPACTION REQUIREMENTS.
  - ONCE LAYER 'C' IS PLACED, ANY SOIL/MATERIAL CAN BE PLACED IN LAYER 'D' UP TO THE FINISHED GRADE. MOST PAVEMENT SUBBASE SOILS CAN BE USED TO REPLACE THE MATERIAL REQUIREMENTS OF LAYER 'C' OR 'D' AT THE SITE DESIGN ENGINEER'S DISCRETION.

### 3 SC-310 ISOLATOR ROW PLUS DETAIL



### INSPECTION & MAINTENANCE


- STEP 1) INSPECT ISOLATOR ROW PLUS FOR SEDIMENT
- INSPECTION PORTS (IF PRESENT)
  - REMOVE PEN LIDS ON NYLOPLAST INLINE DRAIN
  - REMOVE AND CLEAN FLEXSTORM FILTER IF INSTALLED
  - USING A FLASHLIGHT AND STADIA ROD, MEASURE DEPTH OF SEDIMENT AND RECORD ON MAINTENANCE LOG
  - LOWER A CAMERA INTO ISOLATOR ROW PLUS FOR VISUAL INSPECTION OF SEDIMENT LEVELS (OPTIONAL).
  - IF SEDIMENT IS AT, OR ABOVE, 3\"/>
- B. ALL ISOLATOR PLUS ROWS
- REMOVE COVER FROM STRUCTURE AT UPSTREAM END OF ISOLATOR ROW PLUS
  - USING A FLASHLIGHT, INSPECT DOWN THE ISOLATOR ROW PLUS THROUGH OUTLET PIPE
  - MIRRORS ON POLES OR CAMERAS MAY BE USED TO AVOID A CONFINED SPACE ENTRY
  - FOLLOW OSHA REGULATIONS FOR CONFINED SPACE ENTRY IF ENTERING MANHOLE
  - IF SEDIMENT IS AT, OR ABOVE, 3\"/>
- STEP 2) CLEAN OUT ISOLATOR ROW PLUS USING THE JETVAC PROCESS
- A FIXED CULVERT CLEANING NOZZLE WITH REAR FACING SPREAD OF 45\"/>
  - APPLY MULTIPLE PASSES OF JETVAC UNTIL BACKFLUSH WATER IS CLEAN
  - VACUUM STRUCTURE SUMP AS REQUIRED
- STEP 3) REPLACE ALL COVERS, GRATES, FILTERS, AND LIDS; RECORD OBSERVATIONS AND ACTIONS.
- STEP 4) INSPECT AND CLEAN BASINS AND MANHOLES UPSTREAM OF THE STORMTECH SYSTEM.

### NOTES

- INSPECT EVERY 6 MONTHS DURING THE FIRST YEAR OF OPERATION. ADJUST THE INSPECTION INTERVAL BASED ON PREVIOUS OBSERVATIONS OF SEDIMENT ACCUMULATION AND HIGH WATER ELEVATIONS.
- CONDUCT JETTING AND VACTORING ANNUALLY OR WHEN INSPECTION SHOWS THAT MAINTENANCE IS NECESSARY.

### 4 4\"/>

### 1 SC-310 CROSS SECTION DETAIL



### NOTES:

- CHAMBERS SHALL MEET THE REQUIREMENTS OF ASTM F2922 (POLYETHYLENE) OR ASTM F2418 (POLYPROPYLENE), "STANDARD SPECIFICATION FOR CORRUGATED WALL STORMWATER COLLECTION CHAMBERS".
- STORMTECH CHAMBERS SHALL BE DESIGNED IN ACCORDANCE WITH ASTM F2787 "STANDARD PRACTICE FOR STRUCTURAL DESIGN OF THERMOPLASTIC CORRUGATED WALL STORMWATER COLLECTION CHAMBERS".
- THE SITE DESIGN ENGINEER IS RESPONSIBLE FOR ASSESSING THE BEARING RESISTANCE (ALLOWABLE BEARING CAPACITY) OF THE SUBGRADE SOILS AND THE DEPTH OF FOUNDATION STONE WITH CONSIDERATION FOR THE RANGE OF EXPECTED SOIL MOISTURE CONDITIONS.
- PERIMETER STONE MUST BE EXTENDED HORIZONTALLY TO THE EXCAVATION WALL FOR BOTH VERTICAL AND SLOPED EXCAVATION WALLS.
- REQUIREMENTS FOR HANDLING AND INSTALLATION:
  - TO MAINTAIN THE WIDTH OF CHAMBERS DURING SHIPPING AND HANDLING, CHAMBERS SHALL HAVE INTEGRAL, INTERLOCKING STACKING LUGS.
  - TO ENSURE A SECURE JOINT DURING INSTALLATION AND BACKFILL, THE HEIGHT OF THE CHAMBER JOINT SHALL NOT BE LESS THAN 2".
  - TO ENSURE THE INTEGRITY OF THE ARCH SHAPE DURING INSTALLATION, THE ARCH STIFFNESS CONSTANT AS DEFINED IN SECTION 6.2.8 OF ASTM F2922 SHALL BE GREATER THAN OR EQUAL TO 400 LB/FT<sup>2</sup>. AND b) TO RESIST CHAMBER DEFORMATION DURING INSTALLATION AT ELEVATED TEMPERATURES (ABOVE 73° F / 23° C), CHAMBERS SHALL BE PRODUCED FROM REFLECTIVE GOLD OR YELLOW COLORS.

SC-310 STANDARD DETAILS



4640 TRUEMAN BLVD HILLIARD, OH 43026



SHEET

ADVANCED DRAINAGE SYSTEMS, INC. ("ADS") HAS PREPARED THIS DETAIL BASED ON REFERENCED STANDARDS. ADS HAS NOT PERFORMED ANY ENGINEERING OR DESIGN SERVICES FOR THIS PROJECT. NOR HAS ADS INDEPENDENTLY VERIFIED THE INFORMATION SUPPLIED. THE INSTALLATION DETAILS PROVIDED HEREIN ARE GENERAL RECOMMENDATIONS AND ARE NOT SPECIFIC TO THIS PROJECT. UNLESS THE PLANS ARE SIGNED AND SEALED BY THE SITE DESIGN ENGINEER, THE SITE DESIGN ENGINEER SHALL REVIEW THESE DETAILS PRIOR TO CONSTRUCTION AND SEALING THE DOCUMENT. IT IS THE SITE DESIGN ENGINEER'S RESPONSIBILITY TO ENSURE THE DETAILS PROVIDED HEREIN MEET OR EXCEEDS THE APPLICABLE NATIONAL, STATE, OR LOCAL REQUIREMENTS AND TO ENSURE THAT THE DETAILS PROVIDED HEREIN ARE ACCEPTABLE FOR THIS PROJECT.

SHEET TITLE

DETAILS

DATE: 12/13/21

DRAWN: JS

CHECKED: CFT

REVISIONS:

© AAI ENGINEERING INC. 2023. ALL RIGHTS RESERVED.

THESE DRAWINGS ARE THE PROPERTY OF AAI ENGINEERING INC. AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER, EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF AAI ENGINEERING INC.

SHEET NUMBER

# C4.3

# 119 N Pacific Hwy

## Appendix D

Stormwater Calculations

**Table 7 - 1  
VOLUMES FOR DIFFERENT INTENSITY STORMS  
FOR 10-ACRE SITE**

Storms	Results (Rates)	i (INTENSITIES)	A = 435,600 =10 acres	Developed C = 0.71 (UN)developed C = 0.25	ft <sup>3</sup> Sec (cfs)	Volumes storms	ft <sup>3</sup> 3600sec hrs	ft <sup>3</sup> storage volume
100 yr.	<u>1.26"</u> 2.7 hrs	0.467 in hr	435,600 ft <sup>2</sup> or 10 acres	0.71	3.313	32,205 ft <sup>3</sup>	32,205 ft <sup>3</sup> -- <u>11,340 ft<sup>3</sup></u> 20,865 ft <sup>3</sup> storage volume	
				0.25	1.167	11,340 ft <sup>3</sup>		
50 yr.	<u>1.20"</u> 2.76 hrs	0.435 in hr	435,600 ft <sup>2</sup> or 10 acres	0.71	3.087	30,672 ft <sup>3</sup>	30,672 ft <sup>3</sup> -- <u>10,800 ft<sup>3</sup></u> 19,872 ft <sup>3</sup> storage volume	
				0.25	1.087	10,800 ft <sup>3</sup>		
25 yr.	<u>1.14"</u> 2.86 hrs	0.399 in hr	435,600 ft <sup>2</sup> or 10 acres	0.71	2.830	29,138 ft <sup>3</sup>	29,138 ft <sup>3</sup> -- <u>10,255 ft<sup>3</sup></u> 18,883 ft <sup>3</sup> storage volume	
				0.25	0.996	10,255 ft <sup>3</sup>		
10 yr.	<u>1.08"</u> 2.97 hrs	0.364 in hr	435,600 ft <sup>2</sup> or 10 acres	0.71	2.582	27,605 ft <sup>3</sup>	27,605 ft <sup>3</sup> -- <u>9,720 ft<sup>3</sup></u> 17,885 ft <sup>3</sup> storage volume	
				0.25	0.909	9,720 ft <sup>3</sup>		
5 yr.	<u>0.935"</u> 3.28 hrs	0.285 in hr	435,600 ft <sup>2</sup> or 10 acres	0.71	2.024	23,899 ft <sup>3</sup>	23,899 ft <sup>3</sup> -- <u>8,415 ft<sup>3</sup></u> 15,484 ft <sup>3</sup> storage volume	
				0.25	0.713 (320 gpm)	8,415 ft <sup>3</sup>		
2 yr.	<u>0.800"</u> 3.64 hrs	0.220 in hr	435,600 ft <sup>2</sup> or 10 acres	0.71	1.560	20,448 ft <sup>3</sup>	20,448 ft <sup>3</sup> -- <u>7,200 ft<sup>3</sup></u> 13,248 ft <sup>3</sup> storage volume	
				0.25	0.549	7,200 ft <sup>3</sup>		

**CITY OF WOODBURN  
RUN OFF DETENTION REQUIREMENT**

- 1) Construct a device that has capacity for detaining difference in run off volume received by undeveloped and developed land for a 25-year storm.
- 2) Construct a discharge orifice of a size that the quantity of run off through the orifice is equal to run off flow from a storm of 5-year or less, undeveloped land.
- 3) Construct a detention facility to have a post-development 25-year capacity with a discharge orifice (or structure) sized to limit outflow to no more than the undeveloped site peak run off for the existing (undeveloped) 5 year frequency storm. Detention volumes calculated by the following methods are acceptable:
  - A. Santa Barbara Urban Hydrograph routing model (as prescribed by the King County Surface Water Design Manual) for the post development 25-year runoff hydrograph detained back to the existing 5 year peak site discharge.
  - B. 18,883 CF/ 10 Acre drainage area as per City of Woodburn standard table, above, based on the rational method.


**SAFETY REQUIREMENTS**

- 1) Depth of storm water within 30 feet from the edge of detention ponds, if open to public, shall be limited to 3 feet, then gradual slope (3%) to higher depth shall be allowed. Maximum pond side slopes shall be 3' horizontal to 1' vertical, however, gentler slope is desirable.


REV. A STRMVOLM-10/02/95 updated 08/30/96 Item #3 added 12/9/96 Safety Item revised.  
REV. B. APPROVED BY CITY COUNCIL 12/9/96





Undeveloped



Post Developed



SC-310 Chambers



## 119 N Pacific Hwy Woodburn

Prepared by {enter your company name here}

HydroCAD® 10.00-26 s/n 01638 © 2020 HydroCAD Software Solutions LLC

Printed 2/27/2023

Page 2

---

### Project Notes

Rainfall events imported from "17043 Curtis Trailer Hydrocad.hcp"

# 119 N Pacific Hwy Woodburn

Prepared by {enter your company name here}

HydroCAD® 10.00-26 s/n 01638 © 2020 HydroCAD Software Solutions LLC

Printed 2/27/2023

Page 3

## Area Listing (all nodes)

Area (acres)	CN	Description (subcatchment-numbers)
0.128	79	50-75% Grass cover, Fair, HSG C (1S)
1.259	86	<50% Grass cover, Poor, HSG C (2S)
1.131	98	Paved parking, Concrete, Roof (1S)
<b>2.519</b>	<b>91</b>	<b>TOTAL AREA</b>

# 119 N Pacific Hwy Woodburn

Prepared by {enter your company name here}

HydroCAD® 10.00-26 s/n 01638 © 2020 HydroCAD Software Solutions LLC

Printed 2/27/2023

Page 4

## Soil Listing (all nodes)

Area (acres)	Soil Group	Subcatchment Numbers
0.000	HSG A	
0.000	HSG B	
1.388	HSG C	1S, 2S
0.000	HSG D	
1.131	Other	1S
<b>2.519</b>		<b>TOTAL AREA</b>

# 119 N Pacific Hwy Woodburn

Prepared by {enter your company name here}

Printed 2/27/2023

HydroCAD® 10.00-26 s/n 01638 © 2020 HydroCAD Software Solutions LLC

Page 5

## Ground Covers (all nodes)

HSG-A (acres)	HSG-B (acres)	HSG-C (acres)	HSG-D (acres)	Other (acres)	Total (acres)	Ground Cover	Subcatchment Numbers
0.000	0.000	0.128	0.000	0.000	0.128	50-75% Grass cover, Fair	1S
0.000	0.000	1.259	0.000	0.000	1.259	<50% Grass cover, Poor	2S
0.000	0.000	0.000	0.000	1.131	1.131	Paved parking, Concrete, Roof	1S
<b>0.000</b>	<b>0.000</b>	<b>1.388</b>	<b>0.000</b>	<b>1.131</b>	<b>2.519</b>	<b>TOTAL AREA</b>	



**119 N Pacific Hwy Woodburn**

Type IA 24-hr 3.28 hrs 5 yr Rainfall=0.94"

Prepared by {enter your company name here}

Printed 2/27/2023

HydroCAD® 10.00-26 s/n 01638 © 2020 HydroCAD Software Solutions LLC

Page 6

Time span=0.00-50.00 hrs, dt=0.05 hrs, 1001 points

Runoff by SBUH method, Split Pervious/Imperv.

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

**Subcatchment 1S: Post Developed**

Runoff Area=54,860 sf 89.80% Impervious Runoff Depth=0.66"  
Tc=5.0 min CN=79/98 Runoff=0.99 cfs 0.070 af

**Subcatchment 2S: Undeveloped**

Runoff Area=54,860 sf 0.00% Impervious Runoff Depth=0.17"  
Tc=5.0 min CN=86/0 Runoff=0.10 cfs 0.018 af

**Pond 1P: SC-310 Chambers**

Peak Elev=1.35' Storage=2,448 cf Inflow=0.99 cfs 0.070 af  
Outflow=0.08 cfs 0.070 af

**Total Runoff Area = 2.519 ac Runoff Volume = 0.087 af Average Runoff Depth = 0.42"**  
**55.10% Pervious = 1.388 ac 44.90% Impervious = 1.131 ac**

**Summary for Subcatchment 1S: Post Developed**

[49] Hint: Tc<2dt may require smaller dt

Runoff = 0.99 cfs @ 1.15 hrs, Volume= 0.070 af, Depth= 0.66"


Runoff by SBUH method, Split Pervious/Imperv., Time Span= 0.00-50.00 hrs, dt= 0.05 hrs  
 Type IA 24-hr 3.28 hrs 5 yr Rainfall=0.94"

	Area (sf)	CN	Description
*	49,266	98	Paved parking, Concrete, Roof
	5,594	79	50-75% Grass cover, Fair, HSG C
	54,860	96	Weighted Average
	5,594	79	10.20% Pervious Area
	49,266	98	89.80% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

**Subcatchment 1S: Post Developed**

Hydrograph



**119 N Pacific Hwy Woodburn**

Type IA 24-hr 3.28 hrs 5 yr Rainfall=0.94"

Prepared by {enter your company name here}

Printed 2/27/2023

HydroCAD® 10.00-26 s/n 01638 © 2020 HydroCAD Software Solutions LLC

Page 8

**Hydrograph for Subcatchment 1S: Post Developed**

Time (hours)	Precip. (inches)	Perv.Excess (inches)	Imp.Excess (inches)	Runoff (cfs)
0.00	0.00	0.00	0.00	0.00
1.00	0.28	0.00	0.13	<b>0.36</b>
2.00	0.71	0.01	0.51	<b>0.26</b>
3.00	<b>0.90</b>	<b>0.05</b>	<b>0.70</b>	0.18
4.00	<b>0.94</b>	<b>0.05</b>	<b>0.73</b>	0.00
5.00	0.94	0.05	0.73	0.00
6.00	0.94	0.05	0.73	0.00
7.00	0.94	0.05	0.73	0.00
8.00	0.94	0.05	0.73	0.00
9.00	0.94	0.05	0.73	0.00
10.00	0.94	0.05	0.73	0.00
11.00	0.94	0.05	0.73	0.00
12.00	0.94	0.05	0.73	0.00
13.00	0.94	0.05	0.73	0.00
14.00	0.94	0.05	0.73	0.00
15.00	0.94	0.05	0.73	0.00
16.00	0.94	0.05	0.73	0.00
17.00	0.94	0.05	0.73	0.00
18.00	0.94	0.05	0.73	0.00
19.00	0.94	0.05	0.73	0.00
20.00	0.94	0.05	0.73	0.00
21.00	0.94	0.05	0.73	0.00
22.00	0.94	0.05	0.73	0.00
23.00	0.94	0.05	0.73	0.00
24.00	0.94	0.05	0.73	0.00
25.00	0.94	0.05	0.73	0.00
26.00	0.94	0.05	0.73	0.00
27.00	0.94	0.05	0.73	0.00
28.00	0.94	0.05	0.73	0.00
29.00	0.94	0.05	0.73	0.00
30.00	0.94	0.05	0.73	0.00
31.00	0.94	0.05	0.73	0.00
32.00	0.94	0.05	0.73	0.00
33.00	0.94	0.05	0.73	0.00
34.00	0.94	0.05	0.73	0.00
35.00	0.94	0.05	0.73	0.00
36.00	0.94	0.05	0.73	0.00
37.00	0.94	0.05	0.73	0.00
38.00	0.94	0.05	0.73	0.00
39.00	0.94	0.05	0.73	0.00
40.00	0.94	0.05	0.73	0.00
41.00	0.94	0.05	0.73	0.00
42.00	0.94	0.05	0.73	0.00
43.00	0.94	0.05	0.73	0.00
44.00	0.94	0.05	0.73	0.00
45.00	0.94	0.05	0.73	0.00
46.00	0.94	0.05	0.73	0.00
47.00	0.94	0.05	0.73	0.00
48.00	0.94	0.05	0.73	0.00
49.00	0.94	0.05	0.73	0.00
50.00	0.94	0.05	0.73	0.00

**Summary for Subcatchment 2S: Undeveloped**

[49] Hint: Tc<2dt may require smaller dt

Runoff = 0.10 cfs @ 2.28 hrs, Volume= 0.018 af, Depth= 0.17"


Runoff by SBUH method, Split Pervious/Imperv., Time Span= 0.00-50.00 hrs, dt= 0.05 hrs  
 Type IA 24-hr 3.28 hrs 5 yr Rainfall=0.94"

Area (sf)	CN	Description
54,860	86	<50% Grass cover, Poor, HSG C
54,860	86	100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

**Subcatchment 2S: Undeveloped**

Hydrograph



# 119 N Pacific Hwy Woodburn

Type IA 24-hr 3.28 hrs 5 yr Rainfall=0.94"

Prepared by {enter your company name here}

Printed 2/27/2023

HydroCAD® 10.00-26 s/n 01638 © 2020 HydroCAD Software Solutions LLC

Page 10

## Hydrograph for Subcatchment 2S: Undeveloped

Time (hours)	Precip. (inches)	Perv.Excess (inches)	Imp.Excess (inches)	Runoff (cfs)
0.00	0.00	0.00	<b>0.00</b>	0.00
1.00	0.28	0.00	0.00	0.00
2.00	0.71	0.07	0.00	<b>0.10</b>
3.00	<b>0.90</b>	<b>0.15</b>	0.00	<b>0.09</b>
4.00	<b>0.94</b>	<b>0.17</b>	0.00	0.00
5.00	0.94	0.17	0.00	0.00
6.00	0.94	0.17	0.00	0.00
7.00	0.94	0.17	0.00	0.00
8.00	0.94	0.17	0.00	0.00
9.00	0.94	0.17	0.00	0.00
10.00	0.94	0.17	0.00	0.00
11.00	0.94	0.17	0.00	0.00
12.00	0.94	0.17	0.00	0.00
13.00	0.94	0.17	0.00	0.00
14.00	0.94	0.17	0.00	0.00
15.00	0.94	0.17	0.00	0.00
16.00	0.94	0.17	0.00	0.00
17.00	0.94	0.17	0.00	0.00
18.00	0.94	0.17	0.00	0.00
19.00	0.94	0.17	0.00	0.00
20.00	0.94	0.17	0.00	0.00
21.00	0.94	0.17	0.00	0.00
22.00	0.94	0.17	0.00	0.00
23.00	0.94	0.17	0.00	0.00
24.00	0.94	0.17	0.00	0.00
25.00	0.94	0.17	0.00	0.00
26.00	0.94	0.17	0.00	0.00
27.00	0.94	0.17	0.00	0.00
28.00	0.94	0.17	0.00	0.00
29.00	0.94	0.17	0.00	0.00
30.00	0.94	0.17	0.00	0.00
31.00	0.94	0.17	0.00	0.00
32.00	0.94	0.17	0.00	0.00
33.00	0.94	0.17	0.00	0.00
34.00	0.94	0.17	0.00	0.00
35.00	0.94	0.17	0.00	0.00
36.00	0.94	0.17	0.00	0.00
37.00	0.94	0.17	0.00	0.00
38.00	0.94	0.17	0.00	0.00
39.00	0.94	0.17	0.00	0.00
40.00	0.94	0.17	0.00	0.00
41.00	0.94	0.17	0.00	0.00
42.00	0.94	0.17	0.00	0.00
43.00	0.94	0.17	0.00	0.00
44.00	0.94	0.17	0.00	0.00
45.00	0.94	0.17	0.00	0.00
46.00	0.94	0.17	0.00	0.00
47.00	0.94	0.17	0.00	0.00
48.00	0.94	0.17	0.00	0.00
49.00	0.94	0.17	0.00	0.00
50.00	0.94	0.17	0.00	0.00

**Summary for Pond 1P: SC-310 Chambers**

Inflow Area = 1.259 ac, 89.80% Impervious, Inflow Depth = 0.66" for 5 yr event  
 Inflow = 0.99 cfs @ 1.15 hrs, Volume= 0.070 af  
 Outflow = 0.08 cfs @ 3.37 hrs, Volume= 0.070 af, Atten= 92%, Lag= 133.3 min  
 Primary = 0.08 cfs @ 3.37 hrs, Volume= 0.070 af

Routing by Stor-Ind method, Time Span= 0.00-50.00 hrs, dt= 0.05 hrs / 2  
 Peak Elev= 1.35' @ 3.37 hrs Surf.Area= 2,775 sf Storage= 2,448 cf

Plug-Flow detention time= 392.4 min calculated for 0.070 af (100% of inflow)  
 Center-of-Mass det. time= 391.9 min ( 495.9 - 104.1 )

Volume	Invert	Avail.Storage	Storage Description
#1	0.00'	1,949 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc) 6,466 cf Overall - 1,592 cf Embedded = 4,874 cf x 40.0% Voids
#2	0.00'	1,592 cf	
			<b>ADS_StormTech SC-310 +Cap</b> x 108 Inside #1 Effective Size= 28.9"W x 16.0"H => 2.07 sf x 7.12'L = 14.7 cf Overall Size= 34.0"W x 16.0"H x 7.56'L with 0.44' Overlap 108 Chambers in 10 Rows
		3,542 cf	Total Available Storage


Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
0.00	2,775	0	0
2.33	2,775	6,466	6,466

Device	Routing	Invert	Outlet Devices
#1	Primary	0.00'	<b>1.6" Horiz. Orifice/Grate</b> C= 0.600 Limited to weir flow at low heads
#2	Primary	2.12'	<b>18.0" Vert. Orifice/Grate</b> C= 0.600

**Primary OutFlow** Max=0.08 cfs @ 3.37 hrs HW=1.34' (Free Discharge)  
 1=Orifice/Grate (Orifice Controls 0.08 cfs @ 5.58 fps)  
 2=Orifice/Grate ( Controls 0.00 cfs)


### Pond 1P: SC-310 Chambers

Hydrograph




### Pond 1P: SC-310 Chambers

Stage-Discharge



### Pond 1P: SC-310 Chambers





**119 N Pacific Hwy Woodburn**

Type IA 24-hr 3.28 hrs 5 yr Rainfall=0.94"

Prepared by {enter your company name here}

Printed 2/27/2023

HydroCAD® 10.00-26 s/n 01638 © 2020 HydroCAD Software Solutions LLC

Page 14

**Hydrograph for Pond 1P: SC-310 Chambers**

Time (hours)	Inflow (cfs)	Storage (cubic-feet)	Elevation (feet)	Primary (cfs)
0.00	0.00	0	0.00	0.00
1.00	<b>0.36</b>	339	0.15	0.03
2.00	<b>0.26</b>	1,808	0.89	0.06
3.00	0.18	<b>2,344</b>	<b>1.25</b>	<b>0.08</b>
4.00	0.00	<b>2,298</b>	<b>1.22</b>	<b>0.07</b>
5.00	0.00	2,042	1.03	0.07
6.00	0.00	1,806	0.89	0.06
7.00	0.00	1,586	0.76	0.06
8.00	0.00	1,383	0.66	0.05
9.00	0.00	1,194	0.56	0.05
10.00	0.00	1,020	0.47	0.05
11.00	0.00	861	0.40	0.04
12.00	0.00	715	0.33	0.04
13.00	0.00	584	0.27	0.03
14.00	0.00	466	0.21	0.03
15.00	0.00	361	0.16	0.03
16.00	0.00	270	0.12	0.02
17.00	0.00	192	0.09	0.02
18.00	0.00	129	0.06	0.01
19.00	0.00	85	0.04	0.01
20.00	0.00	56	0.03	0.01
21.00	0.00	37	0.02	0.00
22.00	0.00	24	0.01	0.00
23.00	0.00	16	0.01	0.00
24.00	0.00	10	0.00	0.00
25.00	0.00	7	0.00	0.00
26.00	0.00	4	0.00	0.00
27.00	0.00	3	0.00	0.00
28.00	0.00	2	0.00	0.00
29.00	0.00	1	0.00	0.00
30.00	0.00	1	0.00	0.00
31.00	0.00	1	0.00	0.00
32.00	0.00	0	0.00	0.00
33.00	0.00	0	0.00	0.00
34.00	0.00	0	0.00	0.00
35.00	0.00	0	0.00	0.00
36.00	0.00	0	0.00	0.00
37.00	0.00	0	0.00	0.00
38.00	0.00	0	0.00	0.00
39.00	0.00	0	0.00	0.00
40.00	0.00	0	0.00	0.00
41.00	0.00	0	0.00	0.00
42.00	0.00	0	0.00	0.00
43.00	0.00	0	0.00	0.00
44.00	0.00	0	0.00	0.00
45.00	0.00	0	0.00	0.00
46.00	0.00	0	0.00	0.00
47.00	0.00	0	0.00	0.00
48.00	0.00	0	0.00	0.00
49.00	0.00	0	0.00	0.00
50.00	0.00	0	0.00	0.00

**Stage-Discharge for Pond 1P: SC-310 Chambers**

Elevation (feet)	Primary (cfs)	Elevation (feet)	Primary (cfs)	Elevation (feet)	Primary (cfs)	Elevation (feet)	Primary (cfs)
0.00	0.00	1.04	0.07	2.08	0.10	3.12	4.38
0.02	0.00	1.06	0.07	2.10	0.10	3.14	4.52
0.04	0.01	1.08	0.07	2.12	0.10	3.16	4.66
0.06	0.02	1.10	0.07	2.14	0.10	3.18	4.80
0.08	0.02	1.12	0.07	2.16	0.11	3.20	4.94
0.10	0.02	1.14	0.07	2.18	0.12	3.22	5.08
0.12	0.02	1.16	0.07	2.20	0.13	3.24	5.22
0.14	0.03	1.18	0.07	2.22	0.15	3.26	5.36
0.16	0.03	1.20	0.07	2.24	0.18	3.28	5.50
0.18	0.03	1.22	0.07	2.26	0.21	3.30	5.64
0.20	0.03	1.24	0.07	2.28	0.24	3.32	5.77
0.22	0.03	1.26	0.08	2.30	0.28	3.34	5.91
0.24	0.03	1.28	0.08	2.32	0.32	3.36	6.05
0.26	0.03	1.30	0.08	2.34	0.36	3.38	6.18
0.28	0.04	1.32	0.08	2.36	0.41	3.40	6.31
0.30	0.04	1.34	0.08	2.38	0.46	3.42	6.44
0.32	0.04	1.36	0.08	2.40	0.51	3.44	6.57
0.34	0.04	1.38	0.08	2.42	0.57	3.46	6.69
0.36	0.04	1.40	0.08	2.44	0.64	3.48	6.81
0.38	0.04	1.42	0.08	2.46	0.70	3.50	6.93
0.40	0.04	1.44	0.08	2.48	0.77	3.52	7.04
0.42	0.04	1.46	0.08	2.50	0.85	3.54	7.15
0.44	0.04	1.48	0.08	2.52	0.92	3.56	7.25
0.46	0.05	1.50	0.08	2.54	1.00	3.58	7.34
0.48	0.05	1.52	0.08	2.56	1.08	3.60	7.43
0.50	0.05	1.54	0.08	2.58	1.17	3.62	<b>7.50</b>
0.52	0.05	1.56	0.08	2.60	1.26		
0.54	0.05	1.58	0.08	2.62	1.35		
0.56	0.05	1.60	0.09	2.64	1.44		
0.58	0.05	1.62	0.09	2.66	1.54		
0.60	0.05	1.64	0.09	2.68	1.64		
0.62	0.05	1.66	0.09	2.70	1.75		
0.64	0.05	1.68	0.09	2.72	1.85		
0.66	0.05	1.70	0.09	2.74	1.96		
0.68	0.06	1.72	0.09	2.76	2.07		
0.70	0.06	1.74	0.09	2.78	2.18		
0.72	0.06	1.76	0.09	2.80	2.30		
0.74	0.06	1.78	0.09	2.82	2.42		
0.76	0.06	1.80	0.09	2.84	2.54		
0.78	0.06	1.82	0.09	2.86	2.66		
0.80	0.06	1.84	0.09	2.88	2.78		
0.82	0.06	1.86	0.09	2.90	2.91		
0.84	0.06	1.88	0.09	2.92	3.03		
0.86	0.06	1.90	0.09	2.94	3.16		
0.88	0.06	1.92	0.09	2.96	3.29		
0.90	0.06	1.94	0.09	2.98	3.42		
0.92	0.06	1.96	0.09	3.00	3.56		
0.94	0.07	1.98	0.09	3.02	3.69		
0.96	0.07	2.00	0.10	3.04	3.83		
0.98	0.07	2.02	0.10	3.06	3.96		
1.00	0.07	2.04	0.10	3.08	4.10		
1.02	0.07	2.06	0.10	3.10	4.24		

**Stage-Area-Storage for Pond 1P: SC-310 Chambers**

Elevation (feet)	Storage (cubic-feet)	Elevation (feet)	Storage (cubic-feet)
0.00	0	2.60	3,542
0.05	111	2.65	3,542
0.10	222	2.70	3,542
0.15	332	2.75	3,542
0.20	441	2.80	3,542
0.25	549	2.85	3,542
0.30	656	2.90	3,542
0.35	762	2.95	3,542
0.40	867	3.00	3,542
0.45	971	3.05	3,542
0.50	1,073	3.10	3,542
0.55	1,174	3.15	3,542
0.60	1,274	3.20	3,542
0.65	1,372	3.25	3,542
0.70	1,468	3.30	3,542
0.75	1,562	3.35	3,542
0.80	1,654	3.40	3,542
0.85	1,744	3.45	3,542
0.90	1,832	3.50	3,542
0.95	1,916	3.55	3,542
1.00	1,998	3.60	3,542
1.05	2,075		
1.10	2,147		
1.15	2,215		
1.20	2,278		
1.25	2,339		
1.30	2,398		
1.35	2,454		
1.40	2,509		
1.45	2,565		
1.50	2,620		
1.55	2,676		
1.60	2,731		
1.65	2,787		
1.70	2,842		
1.75	2,898		
1.80	2,953		
1.85	3,009		
1.90	3,064		
1.95	3,120		
2.00	3,175		
2.05	3,231		
2.10	3,286		
2.15	3,342		
2.20	3,397		
2.25	3,453		
2.30	<b>3,508</b>		
2.35	<b>3,542</b>		
2.40	3,542		
2.45	3,542		
2.50	3,542		
2.55	3,542		

**119 N Pacific Hwy Woodburn**

Type IA 24-hr 2.86 hrs 25 yr Rainfall=1.14"

Prepared by {enter your company name here}

Printed 2/27/2023

HydroCAD® 10.00-26 s/n 01638 © 2020 HydroCAD Software Solutions LLC

Page 17

Time span=0.00-50.00 hrs, dt=0.05 hrs, 1001 points

Runoff by SBUH method, Split Pervious/Imperv.

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

**Subcatchment 1S: Post Developed**

Runoff Area=54,860 sf 89.80% Impervious Runoff Depth=0.84"  
Tc=5.0 min CN=79/98 Runoff=1.38 cfs 0.089 af

**Subcatchment 2S: Undeveloped**

Runoff Area=54,860 sf 0.00% Impervious Runoff Depth=0.27"  
Tc=5.0 min CN=86/0 Runoff=0.22 cfs 0.029 af

**Pond 1P: SC-310 Chambers**

Peak Elev=2.05' Storage=3,229 cf Inflow=1.38 cfs 0.089 af  
Outflow=0.10 cfs 0.089 af

**Total Runoff Area = 2.519 ac Runoff Volume = 0.117 af Average Runoff Depth = 0.56"**  
**55.10% Pervious = 1.388 ac 44.90% Impervious = 1.131 ac**

**Summary for Subcatchment 1S: Post Developed**

[49] Hint: Tc<2dt may require smaller dt

Runoff = 1.38 cfs @ 1.01 hrs, Volume= 0.089 af, Depth= 0.84"


Runoff by SBUH method, Split Pervious/Imperv., Time Span= 0.00-50.00 hrs, dt= 0.05 hrs  
 Type IA 24-hr 2.86 hrs 25 yr Rainfall=1.14"

	Area (sf)	CN	Description
*	49,266	98	Paved parking, Concrete, Roof
	5,594	79	50-75% Grass cover, Fair, HSG C
	54,860	96	Weighted Average
	5,594	79	10.20% Pervious Area
	49,266	98	89.80% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

**Subcatchment 1S: Post Developed**

Hydrograph



**119 N Pacific Hwy Woodburn**

Type IA 24-hr 2.86 hrs 25 yr Rainfall=1.14"

Prepared by {enter your company name here}

Printed 2/27/2023

HydroCAD® 10.00-26 s/n 01638 © 2020 HydroCAD Software Solutions LLC

Page 19

**Hydrograph for Subcatchment 1S: Post Developed**

Time (hours)	Precip. (inches)	Perv.Excess (inches)	Imp.Excess (inches)	Runoff (cfs)
0.00	0.00	0.00	0.00	0.00
1.00	0.54	0.00	0.35	<b>1.37</b>
2.00	<b>0.94</b>	<b>0.05</b>	<b>0.73</b>	0.34
3.00	<b>1.14</b>	<b>0.11</b>	<b>0.93</b>	0.06
4.00	1.14	0.11	0.93	0.00
5.00	1.14	0.11	0.93	0.00
6.00	1.14	0.11	0.93	0.00
7.00	1.14	0.11	0.93	0.00
8.00	1.14	0.11	0.93	0.00
9.00	1.14	0.11	0.93	0.00
10.00	1.14	0.11	0.93	0.00
11.00	1.14	0.11	0.93	0.00
12.00	1.14	0.11	0.93	0.00
13.00	1.14	0.11	0.93	0.00
14.00	1.14	0.11	0.93	0.00
15.00	1.14	0.11	0.93	0.00
16.00	1.14	0.11	0.93	0.00
17.00	1.14	0.11	0.93	0.00
18.00	1.14	0.11	0.93	0.00
19.00	1.14	0.11	0.93	0.00
20.00	1.14	0.11	0.93	0.00
21.00	1.14	0.11	0.93	0.00
22.00	1.14	0.11	0.93	0.00
23.00	1.14	0.11	0.93	0.00
24.00	1.14	0.11	0.93	0.00
25.00	1.14	0.11	0.93	0.00
26.00	1.14	0.11	0.93	0.00
27.00	1.14	0.11	0.93	0.00
28.00	1.14	0.11	0.93	0.00
29.00	1.14	0.11	0.93	0.00
30.00	1.14	0.11	0.93	0.00
31.00	1.14	0.11	0.93	0.00
32.00	1.14	0.11	0.93	0.00
33.00	1.14	0.11	0.93	0.00
34.00	1.14	0.11	0.93	0.00
35.00	1.14	0.11	0.93	0.00
36.00	1.14	0.11	0.93	0.00
37.00	1.14	0.11	0.93	0.00
38.00	1.14	0.11	0.93	0.00
39.00	1.14	0.11	0.93	0.00
40.00	1.14	0.11	0.93	0.00
41.00	1.14	0.11	0.93	0.00
42.00	1.14	0.11	0.93	0.00
43.00	1.14	0.11	0.93	0.00
44.00	1.14	0.11	0.93	0.00
45.00	1.14	0.11	0.93	0.00
46.00	1.14	0.11	0.93	0.00
47.00	1.14	0.11	0.93	0.00
48.00	1.14	0.11	0.93	0.00
49.00	1.14	0.11	0.93	0.00
50.00	1.14	0.11	0.93	0.00

**Summary for Subcatchment 2S: Undeveloped**

[49] Hint: Tc<2dt may require smaller dt

Runoff = 0.22 cfs @ 1.09 hrs, Volume= 0.029 af, Depth= 0.27"


Runoff by SBUH method, Split Pervious/Imperv., Time Span= 0.00-50.00 hrs, dt= 0.05 hrs  
 Type IA 24-hr 2.86 hrs 25 yr Rainfall=1.14"

Area (sf)	CN	Description
54,860	86	<50% Grass cover, Poor, HSG C
54,860	86	100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

**Subcatchment 2S: Undeveloped**

Hydrograph



**119 N Pacific Hwy Woodburn**

Type IA 24-hr 2.86 hrs 25 yr Rainfall=1.14"

Prepared by {enter your company name here}

Printed 2/27/2023

HydroCAD® 10.00-26 s/n 01638 © 2020 HydroCAD Software Solutions LLC

Page 21

**Hydrograph for Subcatchment 2S: Undeveloped**

Time (hours)	Precip. (inches)	Perv.Excess (inches)	Imp.Excess (inches)	Runoff (cfs)
0.00	0.00	0.00	<b>0.00</b>	0.00
1.00	0.54	0.02	0.00	<b>0.18</b>
2.00	<b>0.94</b>	<b>0.17</b>	0.00	<b>0.17</b>
3.00	<b>1.14</b>	<b>0.27</b>	0.00	0.03
4.00	1.14	0.27	0.00	0.00
5.00	1.14	0.27	0.00	0.00
6.00	1.14	0.27	0.00	0.00
7.00	1.14	0.27	0.00	0.00
8.00	1.14	0.27	0.00	0.00
9.00	1.14	0.27	0.00	0.00
10.00	1.14	0.27	0.00	0.00
11.00	1.14	0.27	0.00	0.00
12.00	1.14	0.27	0.00	0.00
13.00	1.14	0.27	0.00	0.00
14.00	1.14	0.27	0.00	0.00
15.00	1.14	0.27	0.00	0.00
16.00	1.14	0.27	0.00	0.00
17.00	1.14	0.27	0.00	0.00
18.00	1.14	0.27	0.00	0.00
19.00	1.14	0.27	0.00	0.00
20.00	1.14	0.27	0.00	0.00
21.00	1.14	0.27	0.00	0.00
22.00	1.14	0.27	0.00	0.00
23.00	1.14	0.27	0.00	0.00
24.00	1.14	0.27	0.00	0.00
25.00	1.14	0.27	0.00	0.00
26.00	1.14	0.27	0.00	0.00
27.00	1.14	0.27	0.00	0.00
28.00	1.14	0.27	0.00	0.00
29.00	1.14	0.27	0.00	0.00
30.00	1.14	0.27	0.00	0.00
31.00	1.14	0.27	0.00	0.00
32.00	1.14	0.27	0.00	0.00
33.00	1.14	0.27	0.00	0.00
34.00	1.14	0.27	0.00	0.00
35.00	1.14	0.27	0.00	0.00
36.00	1.14	0.27	0.00	0.00
37.00	1.14	0.27	0.00	0.00
38.00	1.14	0.27	0.00	0.00
39.00	1.14	0.27	0.00	0.00
40.00	1.14	0.27	0.00	0.00
41.00	1.14	0.27	0.00	0.00
42.00	1.14	0.27	0.00	0.00
43.00	1.14	0.27	0.00	0.00
44.00	1.14	0.27	0.00	0.00
45.00	1.14	0.27	0.00	0.00
46.00	1.14	0.27	0.00	0.00
47.00	1.14	0.27	0.00	0.00
48.00	1.14	0.27	0.00	0.00
49.00	1.14	0.27	0.00	0.00
50.00	1.14	0.27	0.00	0.00



**Summary for Pond 1P: SC-310 Chambers**

Inflow Area = 1.259 ac, 89.80% Impervious, Inflow Depth = 0.84" for 25 yr event  
 Inflow = 1.38 cfs @ 1.01 hrs, Volume= 0.089 af  
 Outflow = 0.10 cfs @ 2.96 hrs, Volume= 0.089 af, Atten= 93%, Lag= 117.3 min  
 Primary = 0.10 cfs @ 2.96 hrs, Volume= 0.089 af

Routing by Stor-Ind method, Time Span= 0.00-50.00 hrs, dt= 0.05 hrs / 2  
 Peak Elev= 2.05' @ 2.96 hrs Surf.Area= 2,775 sf Storage= 3,229 cf

Plug-Flow detention time= 429.6 min calculated for 0.089 af (100% of inflow)  
 Center-of-Mass det. time= 429.1 min ( 519.6 - 90.5 )

Volume	Invert	Avail.Storage	Storage Description
#1	0.00'	1,949 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc) 6,466 cf Overall - 1,592 cf Embedded = 4,874 cf x 40.0% Voids
#2	0.00'	1,592 cf	
			<b>ADS_StormTech SC-310 +Cap</b> x 108 Inside #1 Effective Size= 28.9"W x 16.0"H => 2.07 sf x 7.12'L = 14.7 cf Overall Size= 34.0"W x 16.0"H x 7.56'L with 0.44' Overlap 108 Chambers in 10 Rows
		3,542 cf	Total Available Storage


Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
0.00	2,775	0	0
2.33	2,775	6,466	6,466

Device	Routing	Invert	Outlet Devices
#1	Primary	0.00'	<b>1.6" Horiz. Orifice/Grate</b> C= 0.600 Limited to weir flow at low heads
#2	Primary	2.12'	<b>18.0" Vert. Orifice/Grate</b> C= 0.600

**Primary OutFlow** Max=0.10 cfs @ 2.96 hrs HW=2.05' (Free Discharge)  
 1=Orifice/Grate (Orifice Controls 0.10 cfs @ 6.89 fps)  
 2=Orifice/Grate ( Controls 0.00 cfs)


### Pond 1P: SC-310 Chambers

Hydrograph




### Pond 1P: SC-310 Chambers

Stage-Discharge



### Pond 1P: SC-310 Chambers



**Hydrograph for Pond 1P: SC-310 Chambers**

Time (hours)	Inflow (cfs)	Storage (cubic-feet)	Elevation (feet)	Primary (cfs)
0.00	0.00	0	0.00	0.00
1.00	<b>1.37</b>	875	0.40	0.04
2.00	0.34	<b>2,616</b>	<b>1.50</b>	<b>0.08</b>
3.00	0.06	<b>3,226</b>	<b>2.05</b>	<b>0.10</b>
4.00	0.00	2,909	1.76	0.09
5.00	0.00	2,601	1.48	0.08
6.00	0.00	2,319	1.23	0.07
7.00	0.00	2,062	1.04	0.07
8.00	0.00	1,824	0.90	0.06
9.00	0.00	1,603	0.77	0.06
10.00	0.00	1,399	0.66	0.05
11.00	0.00	1,209	0.57	0.05
12.00	0.00	1,034	0.48	0.05
13.00	0.00	873	0.40	0.04
14.00	0.00	727	0.33	0.04
15.00	0.00	594	0.27	0.03
16.00	0.00	475	0.22	0.03
17.00	0.00	369	0.17	0.03
18.00	0.00	277	0.13	0.02
19.00	0.00	198	0.09	0.02
20.00	0.00	133	0.06	0.02
21.00	0.00	88	0.04	0.01
22.00	0.00	58	0.03	0.01
23.00	0.00	38	0.02	0.00
24.00	0.00	25	0.01	0.00
25.00	0.00	16	0.01	0.00
26.00	0.00	11	0.00	0.00
27.00	0.00	7	0.00	0.00
28.00	0.00	5	0.00	0.00
29.00	0.00	3	0.00	0.00
30.00	0.00	2	0.00	0.00
31.00	0.00	1	0.00	0.00
32.00	0.00	1	0.00	0.00
33.00	0.00	1	0.00	0.00
34.00	0.00	0	0.00	0.00
35.00	0.00	0	0.00	0.00
36.00	0.00	0	0.00	0.00
37.00	0.00	0	0.00	0.00
38.00	0.00	0	0.00	0.00
39.00	0.00	0	0.00	0.00
40.00	0.00	0	0.00	0.00
41.00	0.00	0	0.00	0.00
42.00	0.00	0	0.00	0.00
43.00	0.00	0	0.00	0.00
44.00	0.00	0	0.00	0.00
45.00	0.00	0	0.00	0.00
46.00	0.00	0	0.00	0.00
47.00	0.00	0	0.00	0.00
48.00	0.00	0	0.00	0.00
49.00	0.00	0	0.00	0.00
50.00	0.00	0	0.00	0.00

**Stage-Discharge for Pond 1P: SC-310 Chambers**

Elevation (feet)	Primary (cfs)	Elevation (feet)	Primary (cfs)	Elevation (feet)	Primary (cfs)	Elevation (feet)	Primary (cfs)
0.00	0.00	1.04	0.07	2.08	0.10	3.12	4.38
0.02	0.00	1.06	0.07	2.10	0.10	3.14	4.52
0.04	0.01	1.08	0.07	2.12	0.10	3.16	4.66
0.06	0.02	1.10	0.07	2.14	0.10	3.18	4.80
0.08	0.02	1.12	0.07	2.16	0.11	3.20	4.94
0.10	0.02	1.14	0.07	2.18	0.12	3.22	5.08
0.12	0.02	1.16	0.07	2.20	0.13	3.24	5.22
0.14	0.03	1.18	0.07	2.22	0.15	3.26	5.36
0.16	0.03	1.20	0.07	2.24	0.18	3.28	5.50
0.18	0.03	1.22	0.07	2.26	0.21	3.30	5.64
0.20	0.03	1.24	0.07	2.28	0.24	3.32	5.77
0.22	0.03	1.26	0.08	2.30	0.28	3.34	5.91
0.24	0.03	1.28	0.08	2.32	0.32	3.36	6.05
0.26	0.03	1.30	0.08	2.34	0.36	3.38	6.18
0.28	0.04	1.32	0.08	2.36	0.41	3.40	6.31
0.30	0.04	1.34	0.08	2.38	0.46	3.42	6.44
0.32	0.04	1.36	0.08	2.40	0.51	3.44	6.57
0.34	0.04	1.38	0.08	2.42	0.57	3.46	6.69
0.36	0.04	1.40	0.08	2.44	0.64	3.48	6.81
0.38	0.04	1.42	0.08	2.46	0.70	3.50	6.93
0.40	0.04	1.44	0.08	2.48	0.77	3.52	7.04
0.42	0.04	1.46	0.08	2.50	0.85	3.54	7.15
0.44	0.04	1.48	0.08	2.52	0.92	3.56	7.25
0.46	0.05	1.50	0.08	2.54	1.00	3.58	7.34
0.48	0.05	1.52	0.08	2.56	1.08	3.60	7.43
0.50	0.05	1.54	0.08	2.58	1.17	3.62	<b>7.50</b>
0.52	0.05	1.56	0.08	2.60	1.26		
0.54	0.05	1.58	0.08	2.62	1.35		
0.56	0.05	1.60	0.09	2.64	1.44		
0.58	0.05	1.62	0.09	2.66	1.54		
0.60	0.05	1.64	0.09	2.68	1.64		
0.62	0.05	1.66	0.09	2.70	1.75		
0.64	0.05	1.68	0.09	2.72	1.85		
0.66	0.05	1.70	0.09	2.74	1.96		
0.68	0.06	1.72	0.09	2.76	2.07		
0.70	0.06	1.74	0.09	2.78	2.18		
0.72	0.06	1.76	0.09	2.80	2.30		
0.74	0.06	1.78	0.09	2.82	2.42		
0.76	0.06	1.80	0.09	2.84	2.54		
0.78	0.06	1.82	0.09	2.86	2.66		
0.80	0.06	1.84	0.09	2.88	2.78		
0.82	0.06	1.86	0.09	2.90	2.91		
0.84	0.06	1.88	0.09	2.92	3.03		
0.86	0.06	1.90	0.09	2.94	3.16		
0.88	0.06	1.92	0.09	2.96	3.29		
0.90	0.06	1.94	0.09	2.98	3.42		
0.92	0.06	1.96	0.09	3.00	3.56		
0.94	0.07	1.98	0.09	3.02	3.69		
0.96	0.07	2.00	0.10	3.04	3.83		
0.98	0.07	2.02	0.10	3.06	3.96		
1.00	0.07	2.04	0.10	3.08	4.10		
1.02	0.07	2.06	0.10	3.10	4.24		

**Stage-Area-Storage for Pond 1P: SC-310 Chambers**

Elevation (feet)	Storage (cubic-feet)	Elevation (feet)	Storage (cubic-feet)
0.00	0	2.60	3,542
0.05	111	2.65	3,542
0.10	222	2.70	3,542
0.15	332	2.75	3,542
0.20	441	2.80	3,542
0.25	549	2.85	3,542
0.30	656	2.90	3,542
0.35	762	2.95	3,542
0.40	867	3.00	3,542
0.45	971	3.05	3,542
0.50	1,073	3.10	3,542
0.55	1,174	3.15	3,542
0.60	1,274	3.20	3,542
0.65	1,372	3.25	3,542
0.70	1,468	3.30	3,542
0.75	1,562	3.35	3,542
0.80	1,654	3.40	3,542
0.85	1,744	3.45	3,542
0.90	1,832	3.50	3,542
0.95	1,916	3.55	3,542
1.00	1,998	3.60	3,542
1.05	2,075		
1.10	2,147		
1.15	2,215		
1.20	2,278		
1.25	2,339		
1.30	2,398		
1.35	2,454		
1.40	2,509		
1.45	2,565		
1.50	2,620		
1.55	2,676		
1.60	2,731		
1.65	2,787		
1.70	2,842		
1.75	2,898		
1.80	2,953		
1.85	3,009		
1.90	3,064		
1.95	3,120		
2.00	3,175		
2.05	3,231		
2.10	3,286		
2.15	3,342		
2.20	3,397		
2.25	3,453		
2.30	<b>3,508</b>		
2.35	<b>3,542</b>		
2.40	3,542		
2.45	3,542		
2.50	3,542		
2.55	3,542		

## APPENDIX A - RAINFALL INTENSITY - DURATION - RECURRENCE INTERVAL CURVES

---

### 1.0 Derivation of Curves

---

The Rainfall Intensity - Duration - Recurrence Interval (I-D-R) curves were computed in accordance with the method described in the 1973 NOAA Atlas 2 titled "Precipitation-Frequency Atlas of the Western United States, Volume X-Oregon." A regional rainfall analysis was made by comparing rainfall data for 136 cities and areas, and thirteen zones were established that have similar rainfall intensities. A set of I-D-R curves were calculated for each zone and the curves represent average values for that zone.

### 2.0 Use of Curves

---

The first step is to determine the zone in which the project is located. This can be accomplished by either using the enclosed map that shows the various zones or the alphabetical listing of cities and their corresponding zones. When the proper zone is located, the I-D-R curves for that zone will provide the needed rainfall intensities. The designer must use engineering judgement in selecting the proper zone if the proposed project lies within two zones or is on or near a dividing line. The zone with larger intensity should be used if no personal knowledge of the area is available, as this gives the most conservative design.


*Note: [Rainfall Zone Map](#) and [Rainfall Zone Map with Highway Milepoints](#) are in pdf formats.*

**TABLE 1: INDEX TO RAINFALL INTENSITY-DURATION-RECURRENCE INTERVAL CURVES**

City	Zone	City	Zone
-T-			
The Dalles	11	Yachats	2
Tidewater	4	Yamhill	8
Tillamook	2		
Tiller	6		
Toledo	2		
-U-			
Union	13		
Union Creek	3		
Umatilla	13		
-V-			
Vale	13		
Veneta	5		
Vernonia	8		
Vida	5		
-W-			
Wagontire	13		
Waldport	2		
Wallowa	10		
Willamina	8		
Wilsonville	7		
Woodburn	7		



# RAINFALL INTENSITY - DURATION - RECURRENCE INTERVAL CURVES



Project Name: 119 Pacific Highway  
 Project #: A21194.10

Design Frequency: 25yr

Designed By: JMS  
 Checked By: NWS

Date: 2/27/2023

Upstream Structure	downstream Structure	Area (A) sqft	Area (A) acres	Runoff Coeff. (c)	Equiv. Area (cA) acres	Total Drainage Area (cA) acres	Time of Concent. Or Flow Time (t) min	Total Time of Concent. (T) min	Average Rainfall Intensity (I) in/hr	Design Discharge (Q) cfs	IE (in) ft	IE (out) ft	Pipe Length (L) ft	Min. Invert Slope (s) %	Pipe Size (D) in	Capacity Flowing Full (Q) cfs	Velocity Flowing Full (V) fps	Flow Time (t) min
RD-01	A	684.5	0.016	0.90	0.014	0.014	5.0	5.0	2.45	0.035	187.10	186.84	54.00	0.5%	6	0.39	1.99	0.5
RD-02	A	684.5	0.016	0.90	0.014	0.014	5.0	5.0	2.45	0.035	187.10	186.84	3.00	8.7%	6	1.66	8.43	0.0
A	B		0.000	0.90	0.000	0.028	5.0	5.0	2.45	0.069	186.84	186.68	33.00	0.5%	6	0.39	1.99	0.3
RD-03	B	684.5	0.016	0.90	0.014	0.014	5.0	5.0	2.45	0.035	187.10	186.68	4.00	10.5%	6	1.82	9.28	0.0
B	CO-09		0.000	0.90	0.000	0.042	5.0	5.0	2.45	0.104	186.68	186.58	20.00	0.5%	6	0.40	2.02	0.2
RD-04	CO-09	684.5	0.016	0.90	0.014	0.014	5.0	5.0	2.45	0.035	187.10	186.58	3.00	17.3%	6	2.34	11.92	0.0
CO-09	C		0.000	0.90	0.000	0.057	5.0	5.0	2.45	0.139	186.58	186.39	37.00	0.5%	6	0.40	2.05	0.3
RD-05	C	684.5	0.016	0.90	0.014	0.014	5.0	5.0	2.45	0.035	187.10	186.39	3.00	23.7%	6	2.74	13.93	0.0
C	D		0.000	0.90	0.000	0.071	5.0	5.0	2.45	0.173	186.39	186.33	13.00	0.5%	6	0.38	1.95	0.1
RD-06	D	684.5	0.016	0.90	0.014	0.014	5.0	5.0	2.45	0.035	187.10	186.33	3.00	25.7%	6	2.85	14.51	0.0
D	CO-08		0.000	0.90	0.000	0.085	5.0	5.0	2.45	0.208	186.33	186.15	37.00	0.5%	6	0.39	2.00	0.3
RD-07	CO-08	684.5	0.016	0.90	0.014	0.014	5.0	5.0	2.45	0.035	187.10	186.15	3.00	31.7%	6	3.16	16.11	0.0
CO-08	E		0.000	0.90	0.000	0.099	5.0	5.0	2.45	0.243	186.15	186.03	25.00	0.5%	6	0.39	1.98	0.2
RD-08	E	684.5	0.016	0.90	0.014	0.014	5.0	5.0	2.45	0.035	187.10	186.03	4.00	26.7%	6	2.91	14.81	0.0
E	F		0.000	0.90	0.000	0.113	5.0	5.0	2.45	0.277	186.03	185.93	21.00	0.5%	6	0.39	1.98	0.2
RD-09	F	684.5	0.016	0.90	0.014	0.014	5.0	5.0	2.45	0.035	187.10	185.93	3.00	39.0%	6	3.51	17.88	0.0
F	CO-07		0.000	0.90	0.000	0.127	5.0	5.0	2.45	0.312	185.93	185.76	34.00	0.5%	6	0.40	2.02	0.3
RD-10	CO-07	684.5	0.016	0.90	0.014	0.014	5.0	5.0	2.45	0.035	187.10	185.76	3.00	44.7%	6	3.76	19.14	0.0
CO-07	G		0.000	0.90	0.000	0.141	5.0	5.0	2.45	0.346	185.76	185.60	34.00	0.5%	6	0.39	1.96	0.3
RD-11	G	684.5	0.016	0.90	0.014	0.014	5.0	5.0	2.45	0.035	187.10	185.60	3.00	50.0%	6	3.98	20.25	0.0
G	H		0.000	0.90	0.000	0.156	5.0	5.0	2.45	0.381	185.60	185.43	34.00	0.5%	6	0.40	2.02	0.3
RD-12	H	684.5	0.016	0.90	0.014	0.014	5.0	5.0	2.45	0.035	187.10	185.43	3.00	55.7%	6	4.19	21.36	0.0
H	I		0.000	0.90	0.000	0.170	5.0	5.0	2.45	0.416	185.43	185.20	47.00	0.5%	8	0.85	2.43	0.3
RD-16	J	684.5	0.016	0.90	0.014	0.170	5.0	5.0	2.45	0.416	187.10	186.63	25.00	1.9%	6	0.77	3.93	0.1

Project Name: 119 Pacific Highway  
 Project #: A21194.10

Design Frequency: 25yr

Designed By: JMS  
 Checked By: NWS

Date: 2/27/2023

Upstream Structure	downstream Structure	Area (A) sqft	Area (A) acres	Runoff Coeff. (c)	Equiv. Area (cA) acres	Total Drainage Area (cA) acres	Time of Concent. Or Flow Time (t) min	Total Time of Concent. (T) min	Average Rainfall Intensity (I) in/hr	Design Discharge (Q) cfs	IE (in) ft	IE (out) ft	Pipe Length (L) ft	Min. Invert Slope (s) %	Pipe Size (D) in	Capacity Flowing Full (Q) cfs	Velocity Flowing Full (V) fps	Flow Time (t) min
RD-15	J	684.5	0.016	0.90	0.014	0.184	5.0	5.0	2.45	0.450	187.10	186.63	3.00	15.7%	6	2.23	11.33	0.0
J	K		0.000	0.90	0.000	0.354	5.0	5.0	2.45	0.866	186.63	186.12	27.00	1.9%	8	1.66	4.77	0.1
RD-14	K	684.5	0.016	0.90	0.014	0.014	5.0	5.0	2.45	0.035	187.10	186.12	3.00	32.7%	6	3.21	16.37	0.0
K	L		0.000	0.90	0.000	0.368	5.0	5.0	2.45	0.901	186.12	185.31	43.00	1.9%	8	1.66	4.76	0.2
RD-13	L	684.5	0.016	0.90	0.014	0.552	5.0	5.0	2.45	1.351	187.10	185.31	3.00	59.7%	6	4.34	22.12	0.0
L	I		0.000	0.90	0.000	0.919	5.0	5.0	2.45	2.252	185.31	185.20	6.00	1.8%	10	2.97	5.45	0.0
I	M		0.000	0.90	0.000	1.089	5.0	5.0	2.45	2.668	185.20	184.81	80.00	0.5%	18	7.35	4.16	0.3
CB-02	M	1688	0.039	0.90	0.035	0.035	5.0	5.0	2.45	0.085	185.22	184.81	7.00	5.9%	6	1.36	6.93	0.0
M	N		0.000	0.90	0.000	1.124	5.0	5.0	2.45	2.753	184.81	184.71	6.00	1.7%	18	13.59	7.69	0.0
CB-01	N	5215	0.120	0.90	0.108	0.108	5.0	5.0	2.45	0.264	184.84	184.71	27.00	0.5%	6	0.39	1.99	0.2
N	O		0.000	0.90	0.000	1.232	5.0	5.0	2.45	3.017	184.71	184.49	44.00	0.5%	18	7.45	4.21	0.2
CB-07	P	2449	0.056	0.90	0.051	0.051	5.0	5.0	2.45	0.124	185.09	184.61	96.00	0.5%	6	0.40	2.02	0.8
CB-03	P	1577	0.036	0.90	0.033	0.033	5.0	5.0	2.45	0.080	184.80	184.61	21.00	0.9%	6	0.53	2.72	0.1
P	O		0.000	0.90	0.000	0.083	5.0	5.0	2.45	0.204	184.61	184.49	25.00	0.5%	6	0.39	1.98	0.2
O	X		0.000	0.90	0.000	1.315	5.0	5.0	2.45	3.221	184.49	184.46	6.00	0.5%	18	7.45	4.21	0.0
RD-17	Q	684.5	0.016	0.90	0.014	0.014	5.0	5.0	2.45	0.035	187.10	186.88	25.00	0.9%	6	0.53	2.69	0.2
RD-18	Q	684.5	0.016	0.90	0.014	0.014	5.0	5.0	2.45	0.035	187.10	186.88	3.00	7.3%	6	1.52	7.75	0.0
Q	R		0.000	0.90	0.000	0.028	5.0	5.0	2.45	0.069	186.88	186.63	27.00	0.9%	6	0.54	2.76	0.2
RD-19	R	684.5	0.016	0.90	0.014	0.014	5.0	5.0	2.45	0.035	187.10	186.63	3.00	15.7%	6	2.23	11.33	0.0
R	S		0.000	0.90	0.000	0.042	5.0	5.0	2.45	0.104	186.63	186.43	24.00	0.8%	6	0.51	2.61	0.2

Project Name: 119 Pacific Highway  
 Project #: A21194.10

Design Frequency: 25yr

Designed By: JMS  
 Checked By: NWS

Date: 2/27/2023

Upstream Structure	downstream Structure	Area (A) sqft	Area (A) acres	Runoff Coeff. (c)	Equiv. Area (cA) acres	Total Drainage Area (cA) acres	Time of Concent. Or Flow Time (t) min	Total Time of Concent. (T) min	Average Rainfall Intensity (I) in/hr	Design Discharge (Q) cfs	IE (in) ft	IE (out) ft	Pipe Length (L) ft	Min. Invert Slope (s) %	Pipe Size (D) in	Capacity Flowing Full (Q) cfs	Velocity Flowing Full (V) fps	Flow Time (t) min
RD-21	T	684.5	0.016	0.90	0.014	0.014	5.0	5.0	2.45	0.035	187.10	186.64	44.00	1.0%	6	0.57	2.93	0.3
RD-20	T	684.5	0.016	0.90	0.014	0.014	5.0	5.0	2.45	0.035	187.10	186.64	3.00	15.3%	6	2.20	11.21	0.0
T	S		0.000	0.90	0.000	0.028	5.0	5.0	2.45	0.069	186.64	186.43	20.00	1.0%	6	0.58	2.93	0.1
S	U		0.000	0.90	0.000	0.071	5.0	5.0	2.45	0.173	186.43	185.18	80.00	1.6%	6	0.70	3.58	0.4
CB-05	U	8226	0.189	0.90	0.170	0.170	5.0	5.0	2.45	0.416	185.28	185.18	21.00	0.5%	8	0.84	2.39	0.1
U	V		0.000	0.90	0.000	0.241	5.0	5.0	2.45	0.590	185.18	185.03	30.00	0.5%	8	0.86	2.45	0.2
CB-04	V	5978	0.137	0.90	0.124	0.124	5.0	5.0	2.45	0.303	185.06	185.03	5.00	0.6%	6	0.44	2.22	0.0
V	W		0.000	0.90	0.000	0.364	5.0	5.0	2.45	0.892	185.03	184.66	74.00	0.5%	10	1.55	2.85	0.4
CB-06	W	5978	0.137	0.90	0.124	0.124	5.0	5.0	2.45	0.303	184.69	184.66	6.00	0.5%	6	0.40	2.02	0.0
W	X		0.000	0.90	0.000	0.488	5.0	5.0	2.45	1.195	184.66	184.47	39.00	0.5%	10	1.53	2.81	0.2
X	MH-01		0.000	0.90	0.000	1.802	5.0	5.0	2.45	4.416	184.47	184.43	7.41	0.5%	18	7.74	4.38	0.0
MH-01	DET		0.000	0.90	0.000	1.802	5.0	5.0	2.45	4.416	184.43	184.40	5.50	0.5%	18	7.78	4.40	0.0
DET	FCMH-01		0.000	0.90	0.000	1.802	5.0	5.0	2.45	4.416	184.40	184.40	10.00	0.0%	18	1.05	0.60	0.3
FCMH-01	OUT		0.000	0.90	0.000	1.802	5.0	5.0	2.45	4.416	184.40	183.89	102.00	0.5%	18	7.45	4.21	0.4

# 119 N Pacific Hwy

## Appendix E

Operations and Maintenance

# Isolator<sup>®</sup> Row

## O&M Manual

---



# The Isolator<sup>®</sup> Row

## Introduction

An important component of any Stormwater Pollution Prevention Plan is inspection and maintenance. The StormTech Isolator Row is a technique to inexpensively enhance Total Suspended Solids (TSS) and Total Phosphorus (TP) removal with easy access for inspection and maintenance.

## The Isolator Row

The Isolator Row is a row of StormTech chambers, either SC-160, SC-310, SC-310-3, SC-740, DC-780, MC-3500 or MC-7200 models, that is surrounded with filter fabric and connected to a closely located manhole for easy access. The fabric-wrapped chambers provide for sediment settling and filtration as stormwater rises in the Isolator Row and passes through the filter fabric. The open bottom chambers and perforated sidewalls (SC-310, SC-310-3 and SC-740 models) allow stormwater to flow both vertically and horizontally out of the chambers. Sediments are captured in the Isolator Row protecting the adjacent stone and chambers storage areas from sediment accumulation.

ADS geotextile fabric is placed between the stone and the Isolator Row chambers. The woven geotextile provides a media for stormwater filtration, a durable surface for maintenance, prevents scour of the underlying stone and remains intact during high pressure jetting. A non-woven fabric is placed over the chambers to provide a filter media for flows passing through the chamber's sidewall. The non-woven fabric is not required over the SC-160, DC-780, MC-3500 or MC-7200 models as these chambers do not have perforated side walls.

The Isolator Row is designed to capture the "first flush" runoff and offers the versatility to be sized on a volume basis or a flow-rate basis. An upstream manhole provides access to the Isolator Row and includes a high/low concept such that stormwater flow rates or volumes that exceed the capacity of the Isolator Row bypass through a manifold to the other chambers. This is achieved with an elevated bypass manifold or a high-flow weir. This creates a differential between the Isolator Row of chambers and the manifold to the rest of the system, thus allowing for settlement time in the Isolator Row. After Stormwater flows through the Isolator Row and into the rest of the chamber system it is either exfiltrated into the soils below or passed at a controlled rate through an outlet manifold and outlet control structure.

The Isolator Row may be part of a treatment train system. The treatment train design and pretreatment device selection by the design engineer is often driven by regulatory requirements. Whether pretreatment is used or not, StormTech recommend using the Isolator Row to minimize maintenance requirements and maintenance costs.


**Note:** See the StormTech Design Manual for detailed information on designing inlets for a StormTech system, including the Isolator Row.



Looking down the Isolator Row from the manhole opening, woven geotextile fabric is shown between the chamber and stone base.



StormTech Isolator Row with Overflow Spillway (not to scale)



# Isolator Row Inspection/Maintenance

## Inspection

The frequency of inspection and maintenance varies by location. A routine inspection schedule needs to be established for each individual location based upon site specific variables. The type of land use (i.e. industrial, commercial, residential), anticipated pollutant load, percent imperviousness, climate, etc. all play a critical role in determining the **actual frequency of inspection and maintenance practices**.

At a minimum, StormTech recommends annual inspections. Initially, the Isolator Row should be inspected every 6 months for the first year of operation. For subsequent years, the inspection should be adjusted based upon previous observation of sediment deposition.

The Isolator Row incorporates a combination of standard manhole(s) and strategically located inspection ports (as needed). The inspection ports allow for easy access to the system from the surface, eliminating the need to perform a confined space entry for inspection purposes.



If upon visual inspection it is found that sediment has accumulated, a stadia rod should be inserted to determine the depth of sediment. When the average depth of sediment exceeds 3 inches throughout the length of the Isolator Row, clean-out should be performed.

## Maintenance

The Isolator Row was designed to reduce the cost of periodic maintenance. By "isolating" sediments to just one row, costs are dramatically reduced by eliminating the need to clean out each row of the entire storage bed. If inspection indicates the potential need for maintenance, access is provided


via a manhole(s) located on the end(s) of the row for cleanout. If entry into the manhole is required, please follow local and OSHA rules for a confined space entries.

Maintenance is accomplished with the JetVac process. The JetVac process utilizes a high pressure water nozzle to propel itself down the Isolator Row while scouring and suspending sediments. As the nozzle is retrieved, the captured pollutants are flushed back into the manhole for vacuuming. Most sewer and pipe maintenance companies have vacuum/JetVac combination vehicles. Selection of an appropriate JetVac nozzle will improve maintenance efficiency. Fixed nozzles designed for culverts or large diameter pipe cleaning are preferable. Rear facing jets with an effective spread of at least 45" are best. JetVac reels can vary in length. For ease of maintenance, ADS recommends Isolator Row lengths up to 200" (61 m). **The JetVac process shall only be performed on StormTech Isolator Rows that have AASHTO class 1 woven geotextile (as specified by StormTech) over their angular base stone.**



## StormTech Isolator Row (not to scale)

**Note:** Non-woven fabric is only required over the inlet pipe connection into the end cap for SC-160LP, DC-780, MC-3500 and MC-7200 chamber models and is not required over the entire Isolator Row.





# Isolator Row Step By Step Maintenance Procedures

## Step 1

Inspect Isolator Row for sediment.

- A) Inspection ports (if present)
  - i. Remove lid from floor box frame
  - ii. Remove cap from inspection riser
  - iii. Using a flashlight and stadia rod, measure depth of sediment and record results on maintenance log.
  - iv. If sediment is at or above 3 inch depth, proceed to Step 2. If not, proceed to Step 3.
- B) All Isolator Row
  - i. Remove cover from manhole at upstream end of Isolator Row
  - ii. Using a flashlight, inspect down Isolator Row through outlet pipe
    - 1. Mirrors on poles or cameras may be used to avoid a confined space entry
    - 2. Follow OSHA regulations for confined space entry if entering manhole
  - iii. If sediment is at or above the lower row of sidewall holes (approximately 3 inches), proceed to Step 2. If not, proceed to Step 3.

## Step 2

Clean out Isolator Row using the JetVac process.


- A) A fixed floor cleaning nozzle with rear facing nozzle spread of 45 inches or more is preferable
- B) Apply multiple passes of JetVac until backflush water is clean
- C) Vacuum manhole sump as required

## Step 3

Replace all caps, lids and covers, record observations and actions.

## Step 4

Inspect & clean catch basins and manholes upstream of the StormTech system.



## Sample Maintenance Log

Date	Stadia Rod Readings		Sedi-ment Depth (1)-(2)	Observations/Actions	Inspector
	Fixed point to chamber bottom (1)	Fixed point to top of sediment (2)			
3/15/11	6.3 ft	none		New installation. Fixed point is CI frame at grade	DJM
9/24/11		6.2	0.1 ft	Some grit felt	SM
6/20/13		5.8	0.5 ft	Mucky feel, debris visible in manhole and in Isolator Row, maintenance due	NV
7/7/13	6.3 ft		0	System jetted and vacuumed	DJM

adspipe.com

800-821-6710