

City of Woodburn Community Development Department 270 Montgomery Street Woodburn, OR 97071 Phone: 503-982-5246

Email: planning@ci.woodburn.or.us

OFFICE USE ONLY File Number(s):

GRAD 23-12

971-23-000091-PLNG

Visit the City of Woodburn <u>Planning webpage</u> for the most current forms and applications.

Uniform Application

Project				
Name:	Boones Crossing Ph	ase 6		
Address(es):				
Tax Lot #(s):	05 1W 18C 01405			
Applicant				
Name:	Eugene Labunsky		Title:	President
Phone:	503-509-5916		Firm:	West Coast Home Solutions, LLC
Mailing Address:	25030 SW Parkway	Ave, Suite 110, Wil	sonville	, OR 97070
Email:	eugenel.wchs@gma	il.com		
Applicant's Repres	entative/Project Mana	ger		
Name:	Alex Labunsky		Title:	Project Manager
Phone:	503-509-5916		Firm:	West Coast Home Solutions, LLC
Mailing Address:	25030 SW Parkway	Ave, Suite 110, Wil	sonville	, OR 97070
Email:	alexl.wchs@gmail.c	om		
Landowner				
Name:	Eugene Labunsky		Title:	President
Phone:	503-509-5916		Firm:	West Coast Home Solutions, LLC
Mailing Address:	25030 SW Parkway	Ave, Suite 110, Wil	sonville	, OR 97070
Email:	eugenel.wchs@gma	nil.com		
Architect				
Name:	Spencer Emerick		Title:	Project Manager
Phone:	503-480-8700		Firm:	CB Two Architects
Mailing Address:	500 Liberty St SE, U	nit 100, Salem, OR	97301	
Email:	spencer@CBTwoard	chitects.com		
Civil Engineer				
Name:	Greg Zartman		Title:	Vice President, Principle Engineer
Phone:	503-399-3828		Firm:	LEI Engineering and Surveying of Oregon
Mailing Address:	2564 19th St SE, Sa	lem, OR 97302		
Email:	greg@leiengineering	g.com		
Landscape Archite	ct			
Name:	Laura A. Antonson		Title:	
Phone:	503-784-6494		Firm:	Laurus Designs, LLC
Mailing Address:	1012 Pine St, Silve	rton, OR 97381		
Email:	laura@laurusdesig	ns.com		

Req	uested Review(s):	
	Annexation	☐ Phasing Plan
	Comprehensive Plan Map Change	☐ Property Line Adjustment / Consolidation of Lots
	Conditional Use Permit	☐ Planned Unit Development (PUD), Preliminary
	Design Review	□ PUD, Final
	□ Type I	☐ RCWOD Permit
	☐ Type II	☐ Significant Tree Removal Permit
	☐ Type III	☐ Street Adjustment (formally EXCP)
X	Grading Permit	□ Variance
	Partition or Subdivision, Preliminary	☐ Zoning Adjustment
	Other:	
	Partition or Subdivision, Final	□ Zoning Map Change
of the If ap or ot Agree othe Ito its	plying on behalf of a corporation, Manatherwise) to enter into this Agreement attended that has been duly authorized by all ar action on the part of Manager is necestindividual executing this Agreement for a terms.	ager certifies that Manager has full power and authority (corporate and to consummate the transactions contemplated by it. This necessary action on the part of Manager and no other corporate of essary to authorize the execution and delivery of this Agreement. Manager has full authority to do so and thereby to bind Manager pplicant must also obtain Landowner certification.
Lan	downer's Signature	Applicant's Signature
		I b
Prir	nt Name	Print Name
		Eugene Labunsky
Dat	e	Date
		7 17 23

 $\hfill \square$ Landowner certification attached in lieu of form signature.



August 22, 2022

Maxwell Hooley Alex Labunsky 650 SW 150th Ave Oregon City, Oregon 97045

Re: 1200-C National Pollutant Discharge Elimination System (NPDES) Registration

Permit/PLC No.: NGEN12C-ORR10H409 Project Location: Boones Ferry Rd., Woodburn

Marion County

Dear Maxwell Hooley:

The Oregon Department of Environmental Quality (DEQ) has reviewed your application and approved your registration for coverage under the NPDES Construction Stormwater Discharge Permit 1200-C (permit). As the registrant, you are legally responsible for compliance with all permit conditions. See this link https://www.oregon.gov/deq/wq/wqpermits/Pages/Stormwater-Construction.aspx for a copy of the permit, technical assistance, and all relevant permit forms.

Registrant Obligations

- Comply with all permit conditions. DEQ strongly recommends that you read the permit.
- Fully implement your Erosion and Sediment Control Plan (ESCP). You may need to modify site control measures as site conditions change.
- Ensure that all appropriate contractors hired by you to implement the permit on your behalf have a copy of the ESCP and the permit. Keep a list of all contractors working on your site along with their contact information.
- Notify DEQ of significant projects changes, including ESCP revisions, inspectors, or project ownership changes.
- Perform & document visual monitoring according to Schedule B of the permit by a certified erosion and sediment control person.
- Terminate coverage at the end of the project. You will be charged an annual registration fee until registration is terminated.

The permit does not authorize excavation or fill in state waterways, including wetlands, and does not replace the requirement for receiving authorization to do this type of work under Section 404 of the Clean Water Act. If the authorized activity involves earthmoving in a known or suspected wetland condition you must contact the Department of State Lands at 503-986-5200 if you are west of the Cascades, or 541-388-6112 if you are east of the Cascades, and request a wetland determination prior to earth moving.

The construction stormwater general permit, technical assistance manuals and other information is also available on DEQ Stormwater Program's website.

Sincerely,

DEQ Stormwater Permitting Program

EROSION CONTROL PLANS (CSMP)

THE PERMITTEE IS REQUIRED TO MEET ALL THE CONDITIONS OF THE 1200-C PERMIT. THIS ESCP AND GENERAL CONDITIONS HAVE BEEN DEVELOPED TO FACILITATE COMPLIANCE WITH THE 1200-C PERMIT REQUIREMENTS. IN CASES OF DISCREPANCIES OR OMISSIONS, THE 1200-C PERMIT REQUIREMENTS SUPERCEDE REQUIREMENTS OF THIS PLAN.

BMP MATRIX FOR CONSTRUCTION PHASES

REFER TO DEQ GUIDANCE MANUAL FOR A COMPREHENSIVE LIST OF AVAILABLE BMP'S.

		MASS	UTILITY	STREET	FINAL
	CLEARING	GRADING	INSTALLATION	CONSTRUCTION	STABILIZATION
EROSION PREVENTION		l l			
PRESERVE NATURAL VEGETATION					
GROUND COVER					
HYDRAULIC APPLICATIONS					
PLASTIC SHEETING					
MATTING					
DUST CONTROL	Х	х	Х	Х	Х
TEMPORARY/ PERMANENT SEEDING		х	Х	Х	Х
BUFFER ZONE					
OTHER:					
SEDIMENT CONTROL	<u>'</u>	'		I	
SEDIMENT FENCE (PERIMETER)	** X	х	Х	Х	Х
SEDIMENT FENCE (INTERIOR)					
STRAW WATTLES					
FILTER BERM					
INLET PROTECTION	** X	х	Х	Х	Х
DEWATERING					
SEDIMENT TRAP					
NATURAL BUFFER ENCROACHMENT					
OTHER:					
RUN OFF CONTROL	•				
CONSTRUCTION ENTRANCE	** X	х	Х	Х	Х
PIPE SLOPE DRAIN					
OUTLET PROTECTION					
SURFACE ROUGHENING					
CHECK DAMS					
OTHER:					
POLLUTION PREVENTION	•			1	
PROPER SIGNAGE	Х	x	Х	Х	Х
HAZ WASTE MGMT	Х	х	Х	Х	Х
SPILL KIT ON-SITE	Х	х	Х	Х	Х
CONCRETE WASHOUT AREA	Х	х	Х	Х	Х
OTHER:					

SIGNIFIES ADDITIONAL BMP'S REQUIRED FOR WORK WITHIN 50' OF WATER OF THE STATE. ** SIGNIFIES BMP THAT WILL BE INSTALLED PRIOR TO ANY GROUND DISTURBING ACTIVITY.

RATIONALE STATEMENT

A COMPREHENSIVE LIST OF AVAILABLE BEST MANAGEMENT PRACTICES (BMP) OPTIONS BASED ON DEQ'S GUIDANCE MANUAL HAS BEEN REVIEWED TO COMPLETE THIS EROSION AND SEDIMENT CONTROL PLAN. SOME OF THE ABOVE LISTED BMP's WERE NOT CHOSEN BECAUSE THEY WERE DETERMINED TO NOT EFFECTIVELY MANAGE EROSION PREVENTION AND SEDIMENT CONTROL FOR THIS PROJECT BASED ON SPECIFIC SITE CONDITIONS, INCLUDING SOIL CONDITIONS TOPOGRAPHIC CONSTRAINTS, ACCESSIBILITY TO THE SITE, AND OTHER RELATED CONDITIONS. AS THE PROJECT PROGRESSES AND THERE IS A NEED TO REVISE THE ESC PLAN, AN ACTION PLAN WILL BE SUBMITTED.

INITIA

PERMITTEE'S SITE INSPECTOR:

COMPANY/AGENCY: POINT ENVIRONMENTAL, MICHAEL ZENTHOEFER CPESC#7386

PHONE: <u>541 207 8441</u>

E-MAIL: MIKEZ@POINTENV.COM DESCRIPTION OF EXPERIENCE:

VICINITY MAP

🔾 Canvonville

SITE MAP

TILLAMOOK

NOT TO SCALE

NOT TO SCALE

CONDON HEPPNER **b** Ukiah

PRINEVILLE

⊘La Pine

Bonanza `

ardman Hermiston Athena Milton-Freewater

CANYON CITY

PENDLETON_82

N. Powder

⅓ Jordan Valley

ATTENTION EXCAVATORS:

OREGON LAW REQUIRES YOU TO FOLLOW RULES ADOPTED BY THE OREGON UTILITY NOTIFICATION CENTER. THOSE RULES ARE SET FORTH IN OAR 952-001-0010 THROUGH OAR 952-001-0090. YOU MAY OBTAIN COPIES OF THESE RULES FROM THE CENTER BY CALLING 503-232-1987. IF YOU HAVE ANY QUESTIONS ABOUT THE RULES, YOU MAY CONTACT THE CENTER. YOU MUST NOTIFY THE CENTER AT LEAST TWO BUSINESS DAYS, BEFORE COMMENCING AN EXCAVATION. CALL 503-246-6699.

* HOLD A PRE-CONSTRUCTION MEETING OF PROJECT CONSTRUCTION PERSONNEL THAT INCLUDES THE INSPECTOR TO DISCUSS EROSION AND SEDIMENT CONTROL MEASURES AND CONSTRUCTION LIMITS.

- * ALL INSPECTIONS MUST BE MADE IN ACCORDANCE WITH DEQ 1200-C PERMIT REQUIREMENTS.
- * INSPECTION LOGS MUST BE KEPT IN ACCORDANCE WITH DEQ'S 1200-C PERMIT REQUIREMENTS.
- RETAIN A COPY OF THE ESCP AND ALL REVISIONS ON SITE AND MAKE IT AVAILABLE ON REQUEST TO DEQ, AGENT, OR THE LOCAL MUNICIPALITY.

CONTRACTOR

DEVELOPER/COMPANY: WEST COAST HOME SOLUTIONS

CONTACT: ALEX LABUNSKY ADDRESS: 25030 SW PARK AVENUE WILSONVILLE. OR, 97361 503-619-9376

PLANNING / ENGINEERING / **SURVEYING FIRM**

CONTACT: LEI ENGINEERING AND SURVEYING OF OREGON LLC.

ADDRESS: 2564 19TH AVE SE SALEM, OR 97302 503-399-3828 866-232-6790

NARRATIVE DESCRIPTIONS

EXISTING SITE CONDITIONS

VACANT LOT/LAND IN THE CITY OF WOODBURN, MARION COUNTY OREGON

DEVELOPED CONDITIONS

MULTI-FAMILY: TOWN HOMES

- * CLEARING (AUGUST 2023)
- * MASS GRADING (AUGUST 2023/ SEPTEMBER 2023)
- * UTILITY INSTALLATION (OCTOBER 2023 / NOVEMBER 2023)
- * STREET CONSTRUCTION (NOVEMBER 2023)
- * VERTICAL CONSTRUCTION (NOVEMBER 2023 / JANUARY 2024)
- * FINAL STABILIZATION (JANUARY 2024)

TOTAL SITE AREA = 453,000 SF = 10.40 ACRES

TOTAL DISTURBED AREA = 453.000 SF = 10.40 ACRES

SITE SOIL CLASSIFICATION:

SANDY SILTS AND CLAYS (ML) ENCOUNTERED THROUGHOUT SITE

RECEIVING WATER BODIES:

NEAREST WATER BODY: N/A

PROJECT LOCATION:

BOONES FERRY RD, WOODBURN, MARION COUNTY, OREGON LATITUDE = 45.130027° N , LONGITUDE = 122.868052° W

PROPERTY DESCRIPTION:

TAX LOTS 01405 MARION COUNTY TAX MAP 051W18C. LOCATED IN SW 1/4 OF SECTION 18, TOWNSHIP 5 SOUTH, RANGE 1 WEST, AND SE 1/4 OF SECTION 13, TOWNSHIP 5 SOUTH, RANGE 2 WEST, WILLAMETTE MERIDIAN, MARION COUNTY, OREGON.

	1200C PERMIT SUB-SET
SHEET #	SHEET TITLE
01	1200C EROSION CONTROL COVER
02	1200C NOTES
03	1200C DEMO, CLEARING, GRADING, EXCAVATING, AND LAND DEVELOPMENT
04	1200C STREETS AND UTILITIES
05	1200C VERTICAL CONSTRUCTION
06	1200C FINAL LANDSCAPING AND SITE STABILIZATION
07	1200C DETAILS

SITE DESCRIPTION:

THE PROPOSED DEVELOPMENT SHALL CONSIST OF THE FOLLOWING CONSTRUCTION OF PAVED ROADS, PUBLIC AND PRIVATE CONSTRUCTION OF SIDEWALK, PUBLIC AND PRIVATE CONSTRUCTION OF TOWNHOUSES

NO STRUCTURES ARE BEING REMOVED/DEMOLISHED.

SECTION 1.4: ON-SITE STORMWATER DISCHARGE SHALL CONFORM TO ITEMS LISTED IN SECTION 1.4, AND ARE PERMITTED SO LONG AS THE TERMS AND CONDITIONS OF THE PERMIT ARE MET.

STORMWATER INFILTRATES ON-SITE AND NO RECEIVING BODY OF WATER IS NEARBY. STAGING OF MATERIAL SHALL OCCUR ON-SITE. APPROXIMATELY 9.70 ACRE SHALL BE DISTURBED AT ANY TIME. ON-SITE FILL SHALL CONSIST, PRIMARILY, OF CRUSHED AGGREGATE AND EXCAVATED ON-SITE SOIL. SEED USED FOR TEMPORARY OR PERMANENT SEEDING SHALL BE COMPOSED OF ONE OF THE FOLLOWING MIXTURES, UNLESS OTHERWISE AUTHORIZED:

A. VEGETATED CORRIDOR AREAS REQUIRE NATIVE SEED MIXES. SEE RESTORATION PLAN FOR APPROPRIATE SEED MIX.

B. DWARF GRASS MIX (MIN. 100 LB./AC.)

1. DWARF PERENNIAL RYEGRASS (80% BY WEIGHT)

2. CREEPING RED FESCUE (20% BY WEIGHT) C. STANDARD HEIGHT GRASS MIX (MIN. 100LB./AC.)

1. ANNUAL RYEGRASS (40% BY WEIGHT) 2. TURF-TYPE FESCUE (60% BY WEIGHT)

ON-SITE SOILS ARE DESCRIBED IN THE GEO-REPORT AS FOLLOWS: "AVAILABLE GEOLOGIC MAPPING OF THE SITE INDICATES THAT THE NEAR SURFACE SOILS CONSIST OF LACUSTRINE AND FLUVIAL (ALLUVIUM) SEDIMENTARY DEPOSITS (Qtg) OF PLEISTOCENE AGE. CHARACTERISTICS INCLUDE UNCONSOLIDATED TO SEMI—CONSOLIDATED LACUSTRINE CLAY, SILT, SAND AND GRAVEL; IN PLACES INCLUDES MUDFLOW AND RELATED DEPOSITS OF PIPER (1942), WILLAMETTE VALLEY SILT (WELLS AND PECK, 1961), ALLUVIAL SILT, SAND AND GRAVEL THAT F DEPOSITS OF WELLS AND OTHERS (1983). THESE UPPER (SURFICIAL) UNCONSOLIDATED TO SEMI-CONSOLIDATED ALLUVIAL SEDIMENTARY DEPOSITS ARE GENERALLY SEVERAL TENS OF FEET IN THICKNESS AND ARE UNDERLAIN AT

NO ENGINEERED SOIL USE IS PROPOSED ON-SITE AND IS NOT SUBJECT TO SECTION 6.6 MONITORING REQUIREMENTS NO ADDITIONAL DISCHARGES, OTHER THAN STORM WATER, ARE ANTICIPATED DURING SITE DEVELOPMENT, BUT MAY INCLUDE SOME. OR ALL OF THE AUTHORIZED NON-STORMWATER DISCHARGES LISTED IN SECTION 1.4

DEPTH BY SEMI-CONSOLIDATED TO WELL CONSOLIDATED CONGLOMERATE GRAVELS OF PLEISTOCENE AGE.

NATURE OF CONSTRUCTION ACTIVITY AND ESTIMATED TIME TABLE SECTION 4.4E: POTENTIAL ON-SITE POLLUTANT-GENERATING ACTIVITIES INCLUDE, BUT ARE NOT FOLLOWING: USE OF MECHANICAL EQUIPMENT WITH POTENTIAL RISK FUEL, OIL, AND SOLVENT POLLUTANTS CONTAMINATING THE LOCAL VICINITY OF THE MECHANICAL EQUIPMENT, CONCRETE TRUCK WASH, PAINT USE AND ASSOCIATED CLEANUP CHEMICALS AND ALL OTHER TRADES AND THEIR ASSOCIATED PRODUCTS AND CHEMICALS. AS

> BETWEEN THE DISTURBED PORTIONS OF THE SITE AND ANY WATERS OF THE STATE LOCATED WITHIN 50 FEET OF TH PROJECT SITE, PERMIT REGISTRANTS ARE NOT REQUIRED TO COMPLY WITH THE REQUIREMENTS IN SECTION 2.2.4 AND THIS APPENDIX."

> SEDIMENT FENCE SHALL ACT AS PERIMETER CONTROL, AND SHALL BE INSTALLED PURSUANT TO DETAILS PROVIDED WITHIN THIS PLAN SET. TRACK OUT CONTROL FOR THE SITE SHALL CONSIST OF A CONSTRUCTION ENTRANCE, AND SHALL BE INSTALLED PURSUANT TO DETAILS PROVIDED WITHIN THIS PLAN SET. STORM WATER INLET PROTECTION SHALL CONSIST OF BIOFILTER BAGS, AND SHALL BE INSTALLED PURSUANT TO DETAILS PROVIDED WITHIN THIS PLAN SET. CONCRETE WASHOUT AREA SHALL BE INSTALLED PURSUANT TO DETAILS PROVIDED WITHIN THIS PLAN SET. A FULL STORM WATER ANALYSIS HAS BEEN PREPARED, AND IS PART OF THE ENGINEERING DESIGN PACKAGE SUBMITTED TO CITY OF WOODBURN. A COPY OF THE ENGINEERING PLAN SET AND STORM WATER REPORT MAY BE PROVIDED UPON REQUEST TO THE CLIENT. THIS 1200C PLAN SET IS A SUB-SET OF THE SUBMITTED ENGINEERING PLANS.

> IN THE EVENT THAT CONTAMINATED SOILS ARE ENCOUNTERED ON-SITE, AN ENVIRONMENTAL MANAGEMENT PLAN SHALL BE PRODUCED BY OTHERS. SECTION 1.2.9 STATES, "IF THESE CONDITIONS ARE DISCOVERED AFTER REGISTERING FOR PERMIT COVERAGE, THE EMP MUST BE APPROVED BEFORE WORK AT THE SITE BEGINS. AN APPROVED EMP BECOMES A COMPONENT OF THE ESCP." NO ACTIVE TREATMENT SYSTEM IS PROPOSED AT THIS TIME. IF REQUIRED, SUCH SYSTEMS SHALL INSTALLED, OPERATED AND MAINTAINED BY OTHERS.

> SECTION 2.3.10: DISCHARGES OF TOXIC OR HAZARDOUS SUBSTANCES FROM A SPILL OR OTHER RELEASE ARE PROHIBITED, CONSISTENT WITH SECTION 1.5. WHERE A LEAK, SPILL, OR OTHER RELEASE CONTAINING A HAZARDOUS SUBSTANCE OR OIL OCCURS DURING A 24-HOUR PERIOD, THE REGISTRANT MUST NOTIFY THE OREGON EMERGENCY RESPONSE SYSTEM AT (800) 452-0311 AS SOON AS THE REGISTRANT HAS KNOWLEDGE OF THE RELEASE. CONTACT INFORMATION MUST BE IN LOCATIONS THAT ARE READILY ACCESSIBLE AND AVAILABLE TO ALL EMPLOYEES. THI CONTRACTOR SHALL PRODUCE PROVIDE A SET OF PROCEDURES FOR THE FOLLOWING, LISTED IN SECTION 4.4, BEFORE GRADING ACTIVITIES COMMENCE:

1.PROCEDURES FOR EXPEDITIOUSLY STOPPING, CONTAINING, AND CLEANING UP SPILLS, LEAKS, AND OTHER

2.THE ESCP MAY ALSO REFERENCE THE EXISTENCE OF OIL SPILL PREVENTION CONTROL AND COUNTERMEASURE (SPCC) PLANS DEVELOPED FOR THE CONSTRUCTION ACTIVITY (SEE SECTION 2.3.2.A), PROVIDED THAT THE REGISTRANT KEEP A COPY OF ON SITE OR ELECTRONICALLY AVAILABLE;

3. WASTE MANAGEMENT PROCEDURES (SEE SECTIONS 2.3.1 AND 2.3.4); AND 4.THE LOCATION OF FERTILIZERS APPLIED ON SITE (SEE SECTION 2.3.5).

TEMPORARY SLOPE STABILIZATION MEASURES SHALL INCLUDE: COVERING EXPOSED SOIL WITH PLASTIC SHEETING, STRAW MULCHING, WOOD CHIPS, OR OTHER APPROVED MEASURES. LONG TERM STABILIZATION MEASURES SHALL INCLUDE THE ESTABLISHMENT OF PERMANENT VEGETATIVE COVER VIA SEEDING WITH APPROVED MIX AND APPLICATION

VISUAL MONITORING MUST BE CONDUCTED BY A CERTIFIED EROSION AND SEDIMENT CONTROL OR STORM WATER QUALITY INSPECTOR. THE INSPECTOR MUST BE CERTIFIED IN ONE OF THE FOLLOWING SEDIMENT AND EROSION CONTROL PROGRAMS:

- 1. CERTIFIED PROFESSIONAL IN EROSION AND SEDIMENT CONTROL
- 2. CERTIFIED PROFESSIONAL IN STORM WATER QUALITY
- 3. CERTIFIED INSPECTOR OF SEDIMENT AND EROSION CONTROL 4. WASHINGTON STATE CERTIFIED EROSION AND SEDIMENT CONTROL LEAD
- 5. ROGUE VALLEY SEWER SERVICES EROSION AND SEDIMENT CONTROL CERTIFICATION

HOURS OF OPERATION FOR THE SITE ARE REFERENCED IN THE GENERAL NOTES OF THE CIVIL ENGINEERING PLAN SET, SHEET GN-1.

A LIST OF ALL CONTRACTORS PERFORMING WORK ON THE SITE SHALL BE FOUND IN THE ON-SITE EROSION CONTROL LOG BOOK MAINTAINED BY THE INSPECTOR.

S

Z Ш Ш (1)

1200C EROSION CONTROL COVER

NO SCALE *ER-1* 60-19

EROSION CONTROL NOTES

STANDARD EROSION AND SEDIMENT CONTROL PLAN DRAWING NOTES:

- 1. ONCE KNOWN, INCLUDE A LIST OF ALL CONTRACTORS THAT WILL ENGAGE IN CONSTRUCTION ACTIVITIES ON SITE, AND THE AREAS OF THE SITE WHERE THE CONTRACTOR(S) WILL ENGAGE IN CONSTRUCTION ACTIVITIES. REVISE THE LIST AS APPROPRIATE UNTIL PERMIT COVERAGE IS TERMINATED (SECTION 4.4.C.I). IN ADDITION, INCLUDE A LIST OF ALL PERSONNEL (BY NAME AND POSITION) THAT ARE RESPONSIBLE FOR THE DESIGN, INSTALLATION AND MAINTENANCE OF STORM WATER CONTROL MEASURES (E.G. ESCP DEVELOPER, BMP INSTALLER (SECTION 4.10). AS WELLAS THEIR INDIVIDUAL RESPONSIBILITIES. (SECTION 4.4.C.II)
- 2. VISUAL MONITORING INSPECTION REPORTS MUST BE MADE IN ACCORDANCE WITH DEQ 1200-C PERMIT REQUIREMENTS. (SECTION 6.5)
- 3. INSPECTION LOGS MUST BE KEPT IN ACCORDANCE WITH DEQ'S 1200-C PERMIT REQUIREMENTS. (SECTION 6.5.Q)
- 4. RETAIN A COPY OF THE ESCP AND ALL REVISIONS ON SITE AND MAKE IT AVAILABLE ON REQUEST TO DEQ, AGENT, OR THE LOCAL MUNICIPALITY. (SECTION 4.7)
- 5. THE PERMIT REGISTRANT MUST IMPLEMENT THE ESCP. FAILURE TO IMPLEMENT ANY OF THE CONTROL MEASURES OR PRACTICES DESCRIBED IN THE ESCP IS A VIOLATION OF THE PERMIT. (SECTIONS 4 AND 4.11)
- 6. THE ESCP MUST BE ACCURATE AND REFLECT SITE CONDITIONS. (SECTION 4.8)
- 7. SUBMISSION OF ALL ESCP REVISIONS IS NOT REQUIRED. SUBMITTAL OF THE ESCP REVISIONS IS ONLY UNDER SPECIFIC CONDITIONS. SUBMIT ALL NECESSARY REVISION TO DEQ OR AGENT WITHIN 10 DAYS. (SECTION 4.9)
- 8. SEQUENCE CLEARING AND GRADING TO THE MAXIMUM EXTENT PRACTICAL TO PREVENT EXPOSED INACTIVE AREAS FROM BECOMING A SOURCE OF EROSION. (SECTION 2.2.2)
- 9. CREATE SMOOTH SURFACES BETWEEN SOIL SURFACE AND EROSION AND SEDIMENT CONTROLS TO PREVENT STORM WATER FROM BYPASSING CONTROLS AND PONDING. (SECTION 2.2.3)
- 10. IDENTIFY, MARK, AND PROTECT (BY CONSTRUCTION FENCING OR OTHER MEANS) CRITICAL RIPARIAN AREAS AND VEGETATION INCLUDING IMPORTANT TREES AND ASSOCIATED ROOTING ZONES, AND VEGETATION AREAS TO BE PRESERVED. IDENTIFY VEGETATIVE BUFFER ZONES BETWEEN THE SITE AND SENSITIVE AREAS (E.G., WETLANDS), AND OTHER AREAS TO BE PRESERVED, ESPECIALLY IN PERIMETER AREAS. (SECTION 2.2.1)
- 11. PRESERVE EXISTING VEGETATION WHEN PRACTICAL AND RE-VEGETATE OPEN AREAS. RE-VEGETATE OPEN AREAS WHEN PRACTICABLE BEFORE AND AFTER GRADING OR CONSTRUCTION. IDENTIFY THE TYPE OF VEGETATIVE SEED MIX USED. (SECTION 2.2.5)
- 12. MAINTAIN AND DELINEATE ANY EXISTING NATURAL BUFFER WITHIN THE 50-FEET OF WATERS OF THE STATE. (SECTION 2.2.4)
- 13. INSTALL PERIMETER SEDIMENT CONTROL, INCLUDING STORM DRAIN INLET PROTECTION AS WELL AS ALL SEDIMENT BASINS, TRAPS, AND BARRIERS PRIOR TO LAND DISTURBANCE. (SECTIONS 2.1.3)
- 14. CONTROL BOTH PEAK FLOW RATES AND TOTAL STORM WATER VOLUME, TO MINIMIZE EROSION AT OUTLETS AND DOWNSTREAM CHANNELS AND STREAM BANKS. (SECTIONS 2.1.1. AND 2.2.16)
- 15. CONTROL SEDIMENT AS NEEDED ALONG THE SITE PERIMETER AND AT ALL OPERATIONAL INTERNAL STORM DRAIN INLETS AT ALL TIMES DURING CONSTRUCTION, BOTH INTERNALLY AND AT THE SITE BOUNDARY. (SECTIONS 2.2.6 AND 2.2.13)
- 16. ESTABLISH CONCRETE TRUCK AND OTHER CONCRETE EQUIPMENT WASHOUT AREAS BEFORE BEGINNING CONCRETE WORK. (SECTION2.2.14)
- 17. APPLY TEMPORARY AND/OR PERMANENT SOIL STABILIZATION MEASURES IMMEDIATELY ON ALL DISTURBED AREAS AS GRADING PROGRESSES. TEMPORARY OR PERMANENT STABILIZATION MEASURES ARE NOT REQUIRED FOR AREAS THAT ARE INTENDED TO BE LEFT UN-VEGETATED SUCH AS DIRT ACCESS ROADS OR UTILITY POLE PADS. (SECTIONS 2.2.20 AND 2.2.21)
- 18. ESTABLISH MATERIAL AND WASTE STORAGE AREAS, AND OTHER NON-STORM WATER CONTROLS. (SECTION 2.3.7)
- 19. KEEP WASTE CONTAINER LIDS CLOSED WHEN NOT IN USE AND CLOSE LIDS AT THE END OF THE BUSINESS DAY FOR THOSE CONTAINERS THAT ARE ACTIVELY USED THROUGHOUT THE DAY. FOR WASTE CONTAINERS THAT DO NOT HAVE LIDS, PROVIDE EITHER (1) COVER (E.G., TARP, PLASTIC SHEETING, TEMPORARY ROOF) TO PREVENT EXPOSURE OF WASTES TO PRECIPITATION, OR (2) A SIMILARLY EFFECTIVE MEANS DESIGNED TO PREVENT THE DISCHARGE OF POLLUTANTS (E.G., SECONDARY CONTAINMENT). (SECTION 2.3.7)
- 20. PREVENT TRACKING OF SEDIMENT ONTO PUBLIC OR PRIVATE ROADS USING BMPS SUCH AS: CONSTRUCTION ENTRANCE, GRAVELED (OR PAVED) EXITS AND PARKING AREAS, GRAVEL ALL UNPAVED ROADS LOCATED ONSITE, OR USE AN EXIT TIRE WASH. THESE BMPS MUST BE IN PLACE PRIOR TO LAND— DISTURBING ACTIVITIES. (SECTION 2.2.7)
- 21. WHEN TRUCKING SATURATED SOILS FROM THE SITE, EITHER USE WATER-TIGHT TRUCKS OR DRAIN LOADS ON SITE. (SECTION 2.2.7.F)
- 22. CONTROL PROHIBITED DISCHARGES FROM LEAVING THE CONSTRUCTION SITE, I.E., CONCRETE WASH-OUT, WASTEWATER FROM CLEAN OUT OF STUCCO, PAINT AND CURING COMPOUNDS. (SECTIONS 1.5 AND 2.3.9)
- 23. ENSURE THAT STEEP SLOPE AREAS WHERE CONSTRUCTION ACTIVITIES ARE NOT OCCURRING ARE NOT DISTURBED. (SECTION 2.2.10)
- 24. PREVENT SOIL COMPACTION IN AREAS WHERE POST-CONSTRUCTION INFILTRATION FACILITIES ARE TO BE INSTALLED. (SECTION 2.2.12)
- 25. USE BMPS TO PREVENT OR MINIMIZE STORM WATER EXPOSURE TO POLLUTANTS FROM SPILLS; VEHICLE AND EQUIPMENT FUELING, MAINTENANCE, AND STORAGE; OTHER CLEANING AND MAINTENANCE ACTIVITIES; AND WASTE HANDLING ACTIVITIES. THESE POLLUTANTS INCLUDE FUEL, HYDRAULIC FLUID, AND OTHER OILS FROM VEHICLES AND MACHINERY, AS WELL AS DEBRIS, FERTILIZER, PESTICIDES AND HERBICIDES, PAINTS, SOLVENTS, CURING COMPOUNDS AND ADHESIVES FROM CONSTRUCTION OPERATIONS. (SECTIONS 2.2.15 AND 2.3)
- 26. PROVIDE PLANS FOR SEDIMENTATION BASINS THAT HAVE BEEN DESIGNED PER SECTION 2.2.17 AND STAMPED BY AN OREGON PROFESSIONAL ENGINEER. (SEE SECTION 2.2.17.A)
- 27. IF ENGINEERED SOILS ARE USED ON SITE, A SEDIMENTATION BASIN/IMPOUNDMENT MUST BE INSTALLED. (SEE SECTIONS2.2.17 AND 2.2.18)
- 28. PROVIDE A DEWATERING PLAN FOR ACCUMULATED WATER FROM PRECIPITATION AND UNCONTAMINATED GROUNDWATER SEEPAGE DUE TO SHALLOW EXCAVATION ACTIVITIES. (SEE SECTION 2.4)
- 29. IMPLEMENT THE FOLLOWING BMPS WHEN APPLICABLE: WRITTEN SPILL PREVENTION AND RESPONSE PROCEDURES, EMPLOYEE TRAINING ON SPILL PREVENTION AND PROPER DISPOSAL PROCEDURES, SPILL KITS IN ALL VEHICLES, REGULAR MAINTENANCE SCHEDULE FOR VEHICLES AND MACHINERY, MATERIAL DELIVERY AND STORAGE CONTROLS, TRAINING AND SIGNAGE, AND COVERED STORAGE AREAS FOR WASTE AND SUPPLIES. (SECTION 2.3)
- 30. USE WATER, SOIL-BINDING AGENT OR OTHER DUST CONTROL TECHNIQUE AS NEEDED TO AVOID WIND-BLOWN SOIL. (SECTION 2.2.9)
- 31. THE APPLICATION RATE OF FERTILIZERS USED TO REESTABLISH VEGETATION MUST FOLLOW MANUFACTURER'S RECOMMENDATIONS TO MINIMIZE NUTRIENT RELEASES TO SURFACE WATERS. EXERCISE CAUTION WHEN USING TIME—RELEASE FERTILIZERS WITHIN ANY WATERWAY RIPARIAN ZONE. (SECTION 2.3.5)
- 32. IF AN ACTIVE TREATMENT SYSTEM (FOR EXAMPLE, ELECTRO-COAGULATION, FLOCCULATION, FILTRATION, ETC.) FOR SEDIMENT OR OTHER POLLUTANT REMOVAL IS EMPLOYED, SUBMIT AN OPERATION AND MAINTENANCE PLAN (INCLUDING SYSTEM SCHEMATIC, LOCATION OF SYSTEM, LOCATION OF INLET, LOCATION OF DISCHARGE, DISCHARGE DISPERSION DEVICE DESIGN, AND A SAMPLING PLAN AND FREQUENCY) BEFORE OPERATING THE TREATMENT SYSTEM. OPERATE AND MAINTAIN THE TREATMENT SYSTEM ACCORDING TO MANUFACTURER'S SPECIFICATIONS. (SECTION 1.2.9)
- 33. TEMPORARILY STABILIZE SOILS AT THE END OF THE SHIFT BEFORE HOLIDAYS AND WEEKENDS, IF NEEDED. THE REGISTRANT IS RESPONSIBLE FOR ENSURING THAT SOILS ARE STABLE DURING RAIN EVENTS AT ALL TIMES OF THE YEAR. (SECTION 2.2)
- 34. AS NEEDED BASED ON WEATHER CONDITIONS, AT THE END OF EACH WORKDAY SOIL STOCKPILES MUST BE STABILIZED OR COVERED, OR OTHER BMPS MUST BE IMPLEMENTED TO PREVENT DISCHARGES TO SURFACE WATERS OR CONVEYANCE SYSTEMS LEADING TO SURFACE WATERS. (SECTION 2.2.8)
- 35. SEDIMENT FENCE: REMOVE TRAPPED SEDIMENT BEFORE IT REACHES ONE THIRD OF THE ABOVE GROUND FENCE HEIGHT AND BEFORE FENCE REMOVAL. (SECTION 2.1.5.B)
- 36. OTHER SEDIMENT BARRIERS (SUCH AS BIOBAGS): REMOVE SEDIMENT BEFORE IT REACHES TWO INCHES DEPTH ABOVE GROUND HEIGHT AND BEFORE BMP REMOVAL. (SECTION 2.1.5.C)
- 37. CATCH BASINS: CLEAN BEFORE RETENTION CAPACITY HAS BEEN REDUCED BY FIFTY PERCENT. SEDIMENT BASINS AND SEDIMENT TRAPS: REMOVE TRAPPED SEDIMENTS BEFORE DESIGN CAPACITY HAS BEEN REDUCED BY FIFTY PERCENT AND AT COMPLETION OF PROJECT. (SECTION 2.1.5.D)
- 38. WITHIN 24 HOURS, SIGNIFICANT SEDIMENT THAT HAS LEFT THE CONSTRUCTION SITE, MUST BE REMEDIATED. INVESTIGATE THE CAUSE OF THE SEDIMENT RELEASE AND IMPLEMENT STEPS TO PREVENT A RECURRENCE OF THE DISCHARGE WITHIN THE SAME 24 HOURS.ANY IN-STREAM CLEAN-UP OF SEDIMENT SHALL BE PERFORMED ACCORDING TO THE OREGON DEPARTMENT OF STATE LANDS REQUIRED TIMEFRAME. (SECTION 2.2.19.A)
- 39. THE INTENTIONAL WASHING OF SEDIMENT INTO STORM SEWERS OR DRAINAGE WAYS MUST NOT OCCUR. VACUUMING OR DRY SWEEPING AND MATERIAL PICKUP MUST BE USED TO CLEANUP RELEASED SEDIMENTS. (SECTION 2.2.19)
- 40. DOCUMENT ANY PORTION(S) OF THE SITE WHERE LAND DISTURBING ACTIVITIES HAVE PERMANENTLY CEASED OR WILL BE TEMPORARILY INACTIVE FOR 14 OR MORE CALENDAR DAYS. (SECTION 6.5.F.)
- 41. PROVIDE TEMPORARY STABILIZATION FOR THAT PORTION OF THE SITE WHERE CONSTRUCTION ACTIVITIES CEASE FOR 14 DAYS OR MORE WITH A COVERING OF BLOWN STRAW AND A TACKIFIER, LOOSE STRAW, OR AN ADEQUATE COVERING OF COMPOST MULCH UNTIL WORK RESUMES ON THAT PORTION OF THE SITE. (SECTION 2.2.20)
- 42. DO NOT REMOVE TEMPORARY SEDIMENT CONTROL PRACTICES UNTIL PERMANENT VEGETATION OR OTHER COVER OF EXPOSED AREAS IS ESTABLISHED. ONCE CONSTRUCTION IS COMPLETE AND THE SITE IS STABILIZED, ALL

 TEMPORARY EROSION CONTROLS AND RETAINED SOILS
 MUST BE REMOVED AND DISPOSED OF PROPERLY, UNLESS NEEDED FOR LONG TERM USE FOLLOWING TERMINATION OF PERMIT COVERAGE. (SECTION 2.2.21)


CITY OF WOODBURN EROSION CONTROL NOTES:

CONTRACTOR SHALL COMPLY WITH SECTION 00280 OF THE 2015 OREGON STANDARD SPECIFICATIONS FOR CONSTRUCTION.


INSPECTION FREQUENCY:


	INSPECTION TIVEQUENCT.	
	SITE CONDITION	MINIMUM FREQUENCY
1.	ACTIVE PERIOD	ON INITIAL DATE THAT LAND DISTURBANCE ACTIVITIES COMMENCE.
		WITHIN 24 HOURS OF ANY STORM EVENT, INCLUDING RUNOFF FROM SNOW MELT, THAT RESULTS IN DISCHARGE FROM THE SITE.
		AT LEAST ONCE EVERY 14 DAYS, REGARDLESS OF WHETHER STORMWATER RUNOFF IS OCCURING.
2.	INACTIVE PERIODS GREATER THAN FOURTEEN (14) CONSECUTIVE CALENDER DAYS	THE INSPECTOR MAY REDUCE THE FREQUENCY OF INSPECTIONS IN ANY AREA OF THE SITE WHERE THE STABILIZATION STEPS IN SECTION 2.2.20 HAVE BEEN COMPLETED TO TWICE PER MONTH FOR THE FIRST MONTH, NO LESS THAN 14 CALENDAR DAYS APART, THEN ONCE PER MONTH.
3.	PERIODS DURING WHICH THE SITE IS INACCESSIBLE DUE TO INCLEMENT WEATHER	IF SAFE, ACCESSIBLE AND PRACTICAL, INSPECTIONS MUST OCCUR DAILY AT A RELEVANT DISCHARGE POINT OR DOWNSTREAM LOCATION OF THE RECEIVING WATERBODY.
4.	PERIODS DURING WHICH CONSTRUCTION ACTIVITIES ARE SUSPENDED AND RUNOFF IS UNLIKELY DUE TO FROZEN CONDITIONS.	VISUAL MONITORING INSPECTIONS MAY BE TEMPORARILY SUSPENDED. IMMEDIATELY RESUME MONITORING UPON THAWING, OR WHEN WEATHER CONDITIONS MAKE DISCHARGES LIKELY.
5.	PERIODS DURING WHICH CONSTRUCTION ACTIVITIES ARE CONDUCTED AND RUNOFF IS UNLIKELY DURING FROZEN CONDITIONS.	VISUAL MONITORING INSPECTIONS MAY BE REDUCED TO ONCE A MONTH. IMMEDIATELY RESUME MONITORING UPON THAWING, OR WHEN WEATHER CONDITIONS MAKE DISCHARGES LIKELY.

BOONES FERRY ROAD TYPICAL SECTION (NOT TO SCALE)



SOUTH ARTERIAL TYPICAL SECTION






1. ALL BASE ESC MEASURES (INLET PROTECTION, PERIMETER SEDIMENT CONTROL, GRAVEL CONSTRUCTION ENTRANCES, ETC.) MUST BE IN PLACE, FUNCTIONAL, AND APPROVED IN AN INITIAL INSPECTION, PRIOR TO COMMENCEMENT OF CONSTRUCTION ACTIVITIES.

2. SEDIMENT BARRIERS APPROVED FOR USE INCLUDE <u>SEDIMENT FENCE</u>, <u>BERMS</u> CONSTRUCTED OUT OF MULCH, CHIPPINGS, OR OTHER SUITABLE MATERIAL, STRAW WATTLES. OR OTHER APPROVED MATERIALS.


- 3. SENSITIVE RESOURCES INCLUDING, BUT NOT LIMITED TO, TREES, WETLANDS, AND RIPARIAN PROTECTION AREAS SHALL BE CLEARLY DELINEATED WITH ORANGE CONSTRUCTION FENCING OR CHAIN LINK FENCING IN A MANNER THAT IS CLEARLY VISIBLE TO ANYONE IN THE AREA. NO ACTIVITIES ARE PERMITTED TO OCCUR BEYOND THE CONSTRUCTION BARRIER.
- 4. CONSTRUCTION ENTRANCES SHALL BE INSTALLED AT THE BEGINNING OF CONSTRUCTION AND MAINTAINED FOR THE DURATION OF THE PROJECT. ADDITIONAL MEASURES INCLUDING, BUT NOT LIMITED TO, STREET SWEEPING, AND VACUUMING, MAY BE REQUIRED TO INSURE THAT ALL PAVED AREAS ARE KEPT CLEAN FOR THE DURATION OF THE PROJECT.
- 5. RUN-ON AND RUN-OFF CONTROLS SHALL BE IN PLACE AND FUNCTIONING PRIOR TO BEGINNING SUBSTANTIAL CONSTRUCTION ACTIVITIES. RUN-ON AND RUN-OFF CONTROL MEASURES INCLUDE: <u>SLOPE</u> <u>DRAINS</u> (<u>WITH</u> <u>OUTLET</u> PORTECTION), CHECK DAMS, SURFACE ROUGHENING, AND BEANK STABILIZATION.

GENERAL NOTES:

- EXISTING DRAINAGE PATTERNS ASSUME TO FLOW EAST CENTRALIZING IN ONE AREA, GENERALLY. THE SITE IS FLAT.
- 2. NO WETLAND DELINEATION HAS BEEN PERFORMED AT THIS TIME, AND NO WETLAND EVIDENCE IS PRESENT WITHIN THE DEVELOPMENT AREA.
- 3. AREA WITHIN DEVELOPMENT AREA: 453,000 SF = 10.40 ACRES
- 4. THE EXISTING LAND COVER IS PREDOMINANTLY GRASS, LIKELY UNATTENDED FOR SOME TIME AND OVERGROWN NATURALLY.
- 5. THE SURROUNDING PROPERTY IS AGRICULTURAL IN NATURE AND SINGLE FAMILY RESIDENTAIL.
- 6. A RAIN GAUGE SHALL BE INSTALLED ON A POST IN A LOCATION THAT SHALL NOT BE DISTURBED BY CONSTRUCTION ACTIVITIES, AND FREE FROM ANY AND ALL OVERHEAD OBSTRUCTION. LOCATION OF THE RAIN GAUGE IS SUBJECT TO THE DISCRETION OF THE CONTRACTOR. THE POST SHALL BE FLAGGED WITH HIGHLY VISIBLE FLAGGING.
- 7. NO ON-SITE WATER DISPOSAL SITE IS REQUIRED FOR THE SITE, AS DE-WATERING IS NOT ANTICIPATED. GEOLOGIST FIELD EXPLORATIONS EXPOSED NO GROUND WATER AT ANY OF THE DEPTHS EXCAVATED. SHOULD ON-SITE WATER DISPOSAL BE REQUIRED, A CONCRETE TRUCK WASH SHALL BE CONSTRUCTED AND USED, AND MARKED AS A WATER DISPOSAL AREA.



EXPIRES: 6-30-2024




ENGINEERING
& SURVEYING

OREGON

1200C DEMOLITION, CLEARING, GRADING, EXCAVATING, AND LAND DEVELOPMENT

ER-3 60-19



11. AN AREA SHALL BE PROVIDED FOR THE WASHING OUT OF CONCRETE TRUCKS IN A LOCATION THAT DOES NOT PROVIDE RUN-OFF THAT CAN ENTER THE STORM WATER SYSTEM. IF THE CONCRETE WASH-OUT AREA CAN NOT BE CONSTRUCTED GREATER THAN 50' FROM ANY DISCHARGE POINT, SECONDARY MEASURES SUCH AS BERMS OR TEMPORARY SETTLING PITS MAY BE REQUIRED. THE WASH-OUT SHALL BE LOCATED WITHIN SIX FEET OF TRUCK ACCESS AND BE CLEANED WHEN IT REACHES 50% OF THE CAPACITY.

12. SWEEPINGS FROM EXPOSED AGGREGATE CONCRETE SHALL NOT BE TRANSFERRED TO THE STORM WATER SYSTEM. SWEEPINGS SHALL BE PICKED UP AND DISPOSED IN THE TRASH.

13. AVOID PAVING IN WET WEATHER WHEN PAVING CHEMICALS CAN RUN-OFF INTO THE STORM WATER

14. USE BMPS SUCH AS CHECK-DAMS, BERMS, AND INLET PROTECTION TO PREVENT RUN-OFF FROM REACHING DISCHARGE POINTS.

15. COVER CATCH BASINS, MANHOLES, AND OTHER DISCHARGE POINTS WHEN APPLYING SEAL COAT, TACK COAT, ETC. TO PREVENT INTRODUCING THESE MATERIALS TO THE STORM WATER SYSTEM.

EROSION AND SEDIMENT CONTROL BMP IMPLEMENTATION:

I. ALL BASE ESC MEASURES (INLET PROTECTION, PERIMETER SEDIMENT CONTROL, GRAVEL CONSTRUCTION ENTRANCES, ETC.) MUST BE IN PLACE, FUNCTIONAL, AND APPROVED IN AN INITIAL INSPECTION, PRIOR TO COMMENCÉMENT OF CONSTRUCTION ACTIVITIES.

2. THE "STAGING, EQUIPMENT MAINTENANCE, FUELING, PORTA-POTTY, AND SOLID WASTE AREA 1" SHALL BE MOVED TO "STAGING, EQUIPMENT MAINTENANCE, FUELING, PORTA-POTTY, AND SOLID WASTE AREA 2" FOLLOWING EXCAVATION "CUT" ACTIVITIES.

3. ALL "SEDIMENT BARRIERS (TO BE INSTALLED AFTER GRADING)" SHALL BE INSTALLED IMMEDIATELY FOLLOWING ESTABLISHMENT OF FINISHED GRADE AS SHOWN ON THESE PLANS.

I. THE STORM WATER FACILITY SHALL BE CONSTRUCTED AND LANDSCAPED PRIOR TO THE STORM WATER SYSTEM FUNCTIONING AND SITE PAVING.

5. INLET PROTECTION SHALL BE IN-PLACE IMMEDIATELY FOLLOWING PAVING ACTIVITIES.

GRADING, STREET AND UTILITY EROSION AND SEDIMENT CONSTRUCTION NOTES:

1. SEED USED FOR TEMPORARY OR PERMANENT SEEDING SHALL BE COMPOSED OF ONE OF THE FOLLOWING MIXTURES, UNLESS OTHERWISE AUTHORIZED:

RESTORATION

A. VEGETATED CORRIDOR AREAS REQUIRE NATIVE SEED MIXES. SEE PLAN FOR APPROPRIATE SEED MIX.

B. DWARF GRASS MIX (MIN. 100 LB./AC.)

1. DWARF PERENNIAL RYEGRASS (80% BY WEIGHT)

2. CREEPING RED FESCUE (20% BY WEIGHT) C. STANDARD HEIGHT GRASS MIX (MIN. 100LB./AC.)

1. ANNUAL RYEGRASS (40% BY WEIGHT)

2. TURF-TYPE FESCUE (60% BY WEIGHT)

2. SLOPES TO RECEIVE TEMPORARY OR PERMANENT SEEDING SHALL HAVE THE SURFACE ROUGHENED BY MEANS OF TRACK-WALKING OR THE USE OF OTHER APPROVED IMPLEMENTS. SURFACE ROUGHENING IMPROVES SEED BEDDING AND REDUCES RUN-OFF VELOCITY.

3. LONG TERM SLOPE STABILIZATION MEASURES SHALL INCLUDE THE ESTABLISHMENT OF PERMANENT VEGETATIVE COVER VIA SEEDING WITH APPROVED MIX AND APPLICATION RATE.

4. TEMPORARY SLOPE STABILIZATION MEASURES SHALL INCLUDE: COVERING EXPOSED SOIL WITH PLASTIC SHEETING, STRAW MULCHING, WOOD CHIPS, OR OTHER APPROVED MEASURES.

5. STOCKPILED SOIL OR STRIPPINGS SHALL BE PLACED IN A STABLE LOCATION AND CONFIGURATION.

6. EXPOSED CUT OR FILL AREAS SHALL BE STABILIZED THROUGH THE USE OF TEMPORARY SEEDING AND MULCHING, EROSION CONTROL BLANKETS OR MATS, MID-SLOPE SEDIMENT FENCES OR WATTLES, OR OTHER APPROPRIATE MEASURES.


7. AREAS SUBJECT TO WIND EROSION SHALL USE APPROPRIATE DUST CONTROL MEASURES INCLUDING THE APPLICATION OF A FINE SPRAY OF WATER, PLASTIC SHEETING, STRAW MULCHING, OR OTHER APPROVED MEASURES.

8. CONSTRUCTION ENTRANCES SHALL BE INSTALLED AT THE BEGINNING OF CONSTRUCTION AND MAINTAINED FOR THE DURATION OF THE PROJECT. ADDITIONAL MEASURES INCLUDING, BUT NOT LIMITED TO, TIRE WASHES, STREET SWEEPING, AND VACUUMING MAY BE BE REQUIRED TO INSURE THAT ALL PAVED AREAS ARE KEPT CLEAN FOR THE DURATION OF THE PROJECT.

9. ACTIVE INLETS TO STORM WATER SYSTEMS SHALL BE PROTECTED THROUGH THE USE OF APPROVED INLET PROTECTION MEASURES. ALL INLET PROTECTION MEASURES ARE TO BE REGULARLY INSPECTED AND MAINTAINED AS NEEDED.

10. SATURATED MATERIALS THAT ARE HAULED OFF-SITE MUST BE TRANSPORTED IN WATER-TIGHT TRUCKS TO ELIMINATE SPILLAGE OF SEDIMENT AND SEDIMENT-LADEN WATER.


11. TOTAL SITE AREA DISTURBANCE CUT ≈ 22000 CYD AND FILL ≈ 24000 CYD.



RING Ш SURVE EGON ∞ ~

1200C STREET AND UTILITIES

60-19



11. AN AREA SHALL BE PROVIDED FOR THE WASHING OUT OF CONCRETE TRUCKS IN A LOCATION THAT DOES NOT PROVIDE RUN-OFF THAT CAN ENTER THE STORM WATER SYSTEM. IF THE CONCRETE WASH-OUT AREA CAN NOT BE CONSTRUCTED GREATER THAN 50' FROM ANY DISCHARGE POINT, SECONDARY MEASURES SUCH AS BERMS OR TEMPORARY SETTLING PITS MAY BE REQUIRED. THE WASH-OUT SHALL BE LOCATED WITHIN SIX FEET OF TRUCK ACCESS AND BE CLEANED WHEN IT REACHES 50% OF THE CAPACITY.

12. SWEEPINGS FROM EXPOSED AGGREGATE CONCRETE SHALL NOT BE TRANSFERRED TO THE STORM WATER SYSTEM. SWEEPINGS SHALL BE PICKED UP AND DISPOSED IN THE TRASH.

13. AVOID PAVING IN WET WEATHER WHEN PAVING CHEMICALS CAN RUN-OFF INTO THE STORM WATER

14. USE BMPS SUCH AS CHECK-DAMS, BERMS, AND INLET PROTECTION TO PREVENT RUN-OFF FROM REACHING DISCHARGE POINTS.

15. COVER CATCH BASINS, MANHOLES, AND OTHER DISCHARGE POINTS WHEN APPLYING SEAL COAT, TACK COAT, ETC. TO PREVENT INTRODUCING THESE MATERIALS TO THE STORM WATER SYSTEM.

EROSION AND SEDIMENT CONTROL BMP IMPLEMENTATION:

1. ALL BASE ESC MEASURES (INLET PROTECTION, PERIMETER SEDIMENT CONTROL, GRAVEL CONSTRUCTION ENTRANCES, ETC.) MUST BE IN PLACE, FUNCTIONAL, AND APPROVED IN AN INITIAL INSPECTION, PRIOR TO COMMENCÉMENT OF CONSTRUCTION ACTIVITIES.

2. THE "STAGING, EQUIPMENT MAINTENANCE, FUELING, PORTA-POTTY, AND SOLID WASTE AREA 1" SHALL BE MOVED TO "STAGING, EQUIPMENT MAINTENANCE, FUELING, PORTA-POTTY, AND SOLID WASTE AREA 2" FOLLOWING EXCAVATION "CUT" ACTIVITIES.

3. ALL "SEDIMENT BARRIERS (TO BE INSTALLED AFTER GRADING)" SHALL BE INSTALLED IMMEDIATELY FOLLOWING ESTABLISHMENT OF FINISHED GRADE AS SHOWN ON THESE PLANS.

4. THE STORM WATER FACILITY SHALL BE CONSTRUCTED AND LANDSCAPED PRIOR TO THE STORM WATER SYSTEM FUNCTIONING AND SITE PAVING.

5. INLET PROTECTION SHALL BE IN-PLACE IMMEDIATELY FOLLOWING PAVING ACTIVITIES.

GRADING, STREET AND UTILITY EROSION AND SEDIMENT CONSTRUCTION NOTES:

1. SEED USED FOR TEMPORARY OR PERMANENT SEEDING SHALL BE COMPOSED OF ONE OF THE FOLLOWING MIXTURES, UNLESS OTHERWISE AUTHORIZED:

A. VEGETATED CORRIDOR AREAS REQUIRE NATIVE SEED MIXES. SEE

PLAN FOR APPROPRIATE SEED MIX. B. DWARF GRASS MIX (MIN. 100 LB./AC.)

1. DWARF PERENNIAL RYEGRASS (80% BY WEIGHT)

2. CREEPING RED FESCUE (20% BY WEIGHT)

C. STANDARD HEIGHT GRASS MIX (MIN. 100LB./AC.) 1. ANNUAL RYEGRASS (40% BY WEIGHT)

2. TURF-TYPE FESCUE (60% BY WEIGHT)

2. SLOPES TO RECEIVE TEMPORARY OR PERMANENT SEEDING SHALL HAVE THE SURFACE ROUGHENED BY MEANS OF TRACK-WALKING OR THE USE OF OTHER APPROVED IMPLEMENTS. SURFACE ROUGHENING IMPROVES SEED BEDDING AND REDUCES RUN-OFF VELOCITY.

3. LONG TERM SLOPE STABILIZATION MEASURES SHALL INCLUDE THE ESTABLISHMENT OF PERMANENT VEGETATIVE COVER VIA SEEDING WITH APPROVED MIX AND APPLICATION RATE.

4. TEMPORARY SLOPE STABILIZATION MEASURES SHALL INCLUDE: COVERING EXPOSED SOIL WITH PLASTIC SHEETING, STRAW MULCHING, WOOD CHIPS, OR OTHER APPROVED MEASURES.

5. STOCKPILED SOIL OR STRIPPINGS SHALL BE PLACED IN A STABLE LOCATION AND CONFIGURATION.


6. EXPOSED CUT OR FILL AREAS SHALL BE STABILIZED THROUGH THE USE OF TEMPORARY SEEDING AND MULCHING, EROSION CONTROL BLANKETS OR MATS, MID-SLOPE SEDIMENT FENCES OR WATTLES, OR OTHER APPROPRIATE MEASURES.

7. AREAS SUBJECT TO WIND EROSION SHALL USE APPROPRIATE DUST CONTROL MEASURES INCLUDING THE APPLICATION OF A FINE SPRAY OF WATER, PLASTIC SHEETING, STRAW MULCHING, OR OTHER APPROVED MEASURES.

8. CONSTRUCTION ENTRANCES SHALL BE INSTALLED AT THE BEGINNING OF CONSTRUCTION AND MAINTAINED FOR THE DURATION OF THE PROJECT. ADDITIONAL MEASURES INCLUDING, BUT NOT LIMITED TO, TIRE WASHES, STREET SWEEPING, AND VACUUMING MAY BE BE REQUIRED TO INSURE THAT ALL PAVED AREAS ARE KEPT CLEAN FOR THE DURATION OF THE PROJECT.

9. ACTIVE INLETS TO STORM WATER SYSTEMS SHALL BE PROTECTED THROUGH THE USE OF APPROVED INLET PROTECTION MEASURES. ALL INLET PROTECTION MEASURES ARE TO BE REGULARLY INSPECTED AND MAINTAINED AS NEEDED.


10. SATURATED MATERIALS THAT ARE HAULED OFF-SITE MUST BE TRANSPORTED IN WATER-TIGHT TRUCKS TO ELIMINATE SPILLAGE OF SEDIMENT AND SEDIMENT-LADEN WATER.



RING Ш SURVE EGON

1200C: VERTICAL CONSTRUCTION

ER-5 60-19



THAT DOES NOT PROVIDE RUN-OFF THAT CAN ENTER THE STORM WATER SYSTEM. IF THE CONCRETE WASH-OUT AREA CAN NOT BE CONSTRUCTED GREATER THAN 50' FROM ANY DISCHARGE POINT, SECONDARY MEASURES SUCH AS BERMS OR TEMPORARY SETTLING PITS MAY BE REQUIRED. THE WASH-OUT SHALL BE LOCATED WITHIN SIX FEET OF TRUCK ACCESS AND BE CLEANED WHEN IT REACHES 50% OF THE CAPACITY.

12. SWEEPINGS FROM EXPOSED AGGREGATE CONCRETE SHALL NOT BE TRANSFERRED TO THE STORM WATER SYSTEM. SWEEPINGS SHALL BE PICKED UP AND DISPOSED IN THE TRASH.

13. AVOID PAVING IN WET WEATHER WHEN PAVING CHEMICALS CAN RUN-OFF INTO THE STORM WATER

14. USE BMPS SUCH AS CHECK-DAMS, BERMS, AND INLET PROTECTION TO PREVENT RUN-OFF FROM REACHING DISCHARGE POINTS.

15. COVER CATCH BASINS, MANHOLES, AND OTHER DISCHARGE POINTS WHEN APPLYING SEAL COAT, TACK COAT, ETC. TO PREVENT INTRODUCING THESE MATERIALS TO THE STORM WATER SYSTEM.

EROSION AND SEDIMENT CONTROL BMP IMPLEMENTATION:

1. ALL BASE ESC MEASURES (INLET PROTECTION, PERIMETER SEDIMENT CONTROL, GRAVEL CONSTRUCTION ENTRANCES, ETC.) MUST BE IN PLACE, FUNCTIONAL, AND APPROVED IN AN INITIAL INSPECTION, PRIOR TO COMMENCÉMENT OF CONSTRUCTION ACTIVITIES.

2. THE "STAGING, EQUIPMENT MAINTENANCE, FUELING, PORTA-POTTY, AND SOLID WASTE AREA 1" SHALL BE MOVED TO "STAGING, EQUIPMENT MAINTENANCE, FUELING, PORTA-POTTY, AND SOLID WASTE AREA 2" FOLLOWING EXCAVATION "CUT" ACTIVITIES.

3. ALL "SEDIMENT BARRIERS (TO BE INSTALLED AFTER GRADING)" SHALL BE INSTALLED IMMEDIATELY FOLLOWING ESTABLISHMENT OF FINISHED GRADE AS SHOWN ON THESE PLANS.

4. THE STORM WATER FACILITY SHALL BE CONSTRUCTED AND LANDSCAPED PRIOR TO THE STORM WATER SYSTEM FUNCTIONING AND SITE PAVING.

5. INLET PROTECTION SHALL BE IN-PLACE IMMEDIATELY FOLLOWING PAVING ACTIVITIES.

GRADING, STREET AND UTILITY EROSION AND SEDIMENT CONSTRUCTION NOTES:

1. SEED USED FOR TEMPORARY OR PERMANENT SEEDING SHALL BE COMPOSED OF ONE OF THE FOLLOWING MIXTURES, UNLESS OTHERWISE AUTHORIZED:

A. VEGETATED CORRIDOR AREAS REQUIRE NATIVE SEED MIXES. SEE

PLAN FOR APPROPRIATE SEED MIX. B. DWARF GRASS MIX (MIN. 100 LB./AC.)

1. DWARF PERENNIAL RYEGRASS (80% BY WEIGHT)

2. CREEPING RED FESCUE (20% BY WEIGHT)

C. STANDARD HEIGHT GRASS MIX (MIN. 100LB./AC.)

1. ANNUAL RYEGRASS (40% BY WEIGHT) 2. TURF-TYPE FESCUE (60% BY WEIGHT)

2. SLOPES TO RECEIVE TEMPORARY OR PERMANENT SEEDING SHALL HAVE THE SURFACE ROUGHENED BY MEANS OF TRACK-WALKING OR THE USE OF OTHER APPROVED IMPLEMENTS. SURFACE ROUGHENING IMPROVES SEED BEDDING AND REDUCES RUN-OFF VELOCITY.

3. LONG TERM SLOPE STABILIZATION MEASURES SHALL INCLUDE THE ESTABLISHMENT OF PERMANENT VEGETATIVE COVER VIA SEEDING WITH APPROVED MIX AND APPLICATION RATE.

4. TEMPORARY SLOPE STABILIZATION MEASURES SHALL INCLUDE: COVERING EXPOSED SOIL WITH PLASTIC SHEETING, STRAW MULCHING, WOOD CHIPS, OR OTHER APPROVED MEASURES.

5. STOCKPILED SOIL OR STRIPPINGS SHALL BE PLACED IN A STABLE LOCATION AND CONFIGURATION.


6. EXPOSED CUT OR FILL AREAS SHALL BE STABILIZED THROUGH THE USE OF TEMPORARY SEEDING AND MULCHING, EROSION CONTROL BLANKETS OR MATS, MID-SLOPE SEDIMENT FENCES OR WATTLES, OR OTHER APPROPRIATE MEASURES.

7. AREAS SUBJECT TO WIND EROSION SHALL USE APPROPRIATE DUST CONTROL MEASURES INCLUDING THE APPLICATION OF A FINE SPRAY OF WATER, PLASTIC SHEETING, STRAW MULCHING, OR OTHER APPROVED MEASURES.

8. CONSTRUCTION ENTRANCES SHALL BE INSTALLED AT THE BEGINNING OF CONSTRUCTION AND MAINTAINED FOR THE DURATION OF THE PROJECT. ADDITIONAL MEASURES INCLUDING, BUT NOT LIMITED TO, TIRE WASHES, STREET SWEEPING, AND VACUUMING MAY BE BE REQUIRED TO INSURE THAT ALL PAVED AREAS ARE KEPT CLEAN FOR THE DURATION OF THE PROJECT.

9. ACTIVE INLETS TO STORM WATER SYSTEMS SHALL BE PROTECTED THROUGH THE USE OF APPROVED INLET PROTECTION MEASURES. ALL INLET PROTECTION MEASURES ARE TO BE REGULARLY INSPECTED AND MAINTAINED AS NEEDED.


10. SATURATED MATERIALS THAT ARE HAULED OFF-SITE MUST BE TRANSPORTED IN WATER-TIGHT TRUCKS TO ELIMINATE SPILLAGE OF SEDIMENT AND SEDIMENT-LADEN WATER.




RING Ш SURVE EGON

1200C: FINAL LANDSCAPING AND SITE STABILIZATION

ER-6 60-19





4"-1" open-graded aggregate min 8" thick over subgrade geotextile —

Sandbags or straw bales

SECTION C-C

Area Of Exposed Soil (Acre)

0.25

0.25 < A < 1.0

A > 1.0

1. The Type 1 entrance is a simple entrance without a diversion

2. The wooden ramp may be used on either Type 1 or Type 2

entrances in situations where there is curb and the curb is not removed for the construction entrance.

CONSTRUCTION ENTRANCE TABLE

MINIMUM LENGTH

lined with plastic —

ridge or settling basin.

20

100

CONSTRUCTION ENTRANCE - TYPE 3 (TYPE 1 OR 2 WITH EXISTING CURB) NOT TO SCALE

25' min. radius commercial

15' min. radius residential -

Construction entrance

CALC. BOOK NO. _ _ <u>N/A</u> _

The selection and use of this

Standard Drawing, while de-

signed in accordance with

generally accepted engineer-

ing principles and practices,

is the sole responsibility of

the user and should not be

used without consulting a

Effective Date: June 1, 2021 - November 30, 2021

– Leave 3" gap for drainage

Wooden curb ramp

SDR DATE

WOODEN CURB RAMP SECTION D-D

NOT TO SCALE

-Wooden ramp (2x4, 2x8, 2x12)

___ January, 2021

NOTE: All material and workmanship shall be in accordance wit the current Oregon Standard Specifications

OREGON STANDARD DRAWINGS

CONSTRUCTION ENTRANCES

RD1040

– 25' min. radius commercial 15' min. radius residential

- 25' min. radius commercial

15' min. radius residential

Sandbags or straw

plastic (See RD1070) —

Diversion ridge required where

construction entrance grade exceeds 2%

Slope construction entrance to

drain to sediment settling basin

CONSTRUCTION ENTRANCE - TYPE 1

NOT TO SCALE

CONSTRUCTION ENTRANCE - TYPE 2


SECTION A-A

0 0 0 0 0 0 0 0

∕4"-1" open graded

aggregate min. 8" thick

If water is collected, provide a sediment



EXPIRES: 6-30-2024

EXPIRES: 6-30-2024

ON

EXPIRES: 6-30-2024

OONES CROSSING PHASE

SOLUTIONS,

COAST HOME

9

2564 191H STREET SE
Salem, Oregon 97302
(503) 399-3828
www.leiengineering.com


ENGINEERING
& SURVEYING
F OREGON

1200C DETAILS

SCALE
NO SCALE
PROJECT NO.
60-19
SHEET

RD1070

Effective Date: June 1, 2021 - November 30, 2021



RD1005

PHA CROSSING BOONES

WEST COAST HOME SOLUTIONS, LLC


& SURVEYING
OREGON

1200C DETAILS


NO SCALE
PROJECT NO.
60-19
SHEET


BOONES CROSSING - PHASE 6

ASSESSOR'S MAP 05 1W 18C TAX LOTS 1405 WOODBURN, MARION COUNTY, OREGON



LEGEND





PROJECT TEAM:

OWNER/APPLICANT:
WEST COAST HOME SOLUTIONS, LLC
25030 SW PARKWAY AVE., SUITE 110
WILSONVILLE, OREGON 97070

ENGINEER:
GREG J. ZARTMAN, PE
LEI ENGINEERING & SURVEYING
OF OREGON, LLC
2564 19TH ST. SE
SALEM, OREGON 97302

SURVEYOR:
LARRY M. ALLEN, PLS
LEI ENGINEERING & SURVEYING
OF OREGON, LLC
2564 19TH ST. SE
SALEM, OREGON 97302

GEOTECHNICAL ENGINEER:

DANIEL M. REDMOND, PE, GE

REDMOND GEOTECHNICAL SERVICES

PO BOX 20547

PORTLAND, OR 97294

ARCHITECT:
AARON TERPENING, AIA, LEED AP
CB TWO ARCHITECTS
500 LIBERTY ST. SE, UNIT 100
SALEM, OR 97301

PROPERTY DESCRIPTION:

TAX LOTS 01405 MARION COUNTY TAX MAP 05 1W 18C. LOCATED IN SE 1/4 OF SECTION 13, SW 1/4 OF SECTION 18, TOWNSHIP 5 SOUTH, RANGE 1 WEST, WILLAMETTE MERIDIAN, MARION COUNTY, OREGON.

BENCHMARK/BASIS OF BEARING: VERTICAL AND HORIZONTAL DATUM: LOCAL ASSUMED.

	Sheet List Table
neet Number	Sheet Title
01	COVER SHEET
02	GENERAL NOTES
03	EXISTING CONDITIONS
04	ROW & EASEMENT DEDICATIONS
05	COMPOSITE UTILITY LAYOUT
06	SANITARY SEWER SITE PLAN
07	SANITARY SEWER SITE PLAN
08	STORM SEWER SITE PLAN
09	STORM SEWER SITE PLAN
10	STORM WATER DETENTION SYSTEM
11	SITE GRADING
12	SITE GRADING
13	SITE GRADING
14	SITE GRADING
15	SITE GRADING
16	SITE GRADING
17	SITE GRADING
18	SITE GRADING
19	SITE GRAING
20	SITE GRADING
21	SITE GRADING DETAILS
22	SITE GRAING DETAILS
23	SITE GRADING DETAILS
24	STRIPING PLAN
25	FIRE ACCESS
26	DETAILS 1
27	DETAILS 2
28	DETAILS 3
29	DETAILS 4
30	DETAILS 5

STRED PROFESSION STREET STREET PROFESSION STREET ST

SING PHASE 6

WEST COAST HOME SOLUTIONS,

2564 19TH STREET SE Salem, Oregon 97302 (503) 399-3828 www.leiengineering.com

ENGINEERING

& SURVEYING


OF OREGON


COVER SHEET

SCALE
NO SCALE
PROJECT NO.
60-19
SHEET

CV-1

SITE MAP SCALE: 1" = 1000





PHA BOONE

ENGINEERING


& SURVEYING

OREGON

SEMICE, IS THE PROPERTY OF LEI ENGINEERING OF OREGON, LLC AND IS NOT TO

EXISTING CONDITIONS

60-19 | **EX-1**



SC CONTRACTOR SHALL SAW CUT PURSUANT TO CITY OF WOODBURN

(SD) CONTRACTOR SHALL INSTALL 3034 PVC SDR-35 PIPE, AS SHOWN, AND SHALL BACKFILL AND BED IN ACCORDANCE WITH CITY OF WOODBURN STANDARD DETAILS 3800-1 AND 3800-2 SHOWN ON SHEET DT-1. PIPE SIZES INDICATED HEREON.

ODOT STANDARD DETAIL RD364 SHOWN ON SHEET DT-2.

(MH) CONTRACTOR SHALL INSTALL STANDARD STORM SEWER MANHOLE, AS SHOWN, PURSUANT TO CITY OF WOODBURN STANDARD DRAWING 7500-1 SHOWN ON SHEET DT-3.

PURSUANT TO CITY OF WOODBURN STANDARD DETAIL 4150-8 ON SHEET DT-1, AND SHALL MATCH GRADES AT THE TIES TO EXISTING

GUTTER PURSUANT TO CITY OF WOODBURN STANDARD DETAIL NO

SHOWN, AND SHALL CONFORM TO STREET TYPICAL SECTION

(SR) CONTRACTOR SHALL CONSTRUCT SIDEWALK RAMPS, AS SHOWN, WITH TRUNCATED DOMES INSTALLED PURSUANT TO ODOT STANDARD DETAIL RD905. SIDEWALK RAMPS SHALL NOT EXCEED 8.33% LONGITUDINAL SLOPE AND 2.0% CROSS SLOPE.

COAST HOME SOLUTIONS,

& SURVEYING
OREGON

SOUTH ARTERIAL SD PP STA 14+50 - 19+20

1'' = 20'PROJECT NO. 60-19

