WOODBURN COMMUNITY CENTER WOODBURN, OREGON

GENERAL NOTES

- 1. SURVEY PROVIDED BY S&F LAND SERVICES, DATED 04/01/2020. ELEVATIONS ARE BASED ON MARION COUNTY VERTICAL DATUM ESTABLISHED PER BENCH MARK NO. T13, P10 RD 0246 LOCATED AT THE BENCHMARK AT THE INTERSECTION OF LINCOLN AND NORTH FIRST STREET WITH AN ELEVATION OF 187.52, NAVD 88. SURVEY HAS PROVIDED CONVERSTION FROM NAVD 88 TO NGVD 29 IS -3.37.
- 2. CONSTRUCTION LAYOUT (ALL ACTUAL LINES AND GRADES) SHALL BE STAKED BY A PROFESSIONAL SURVEYOR, REGISTERED IN THE STATE OF OREGON, BASED ON COORDINATES, DIMENSIONS, BEARINGS, AND ELEVATIONS, AS SHOWN, ON THE PLANS.
- 3. PROJECT CONTROL SHALL BE FIELD VERIFIED AND CHECKED FOR RELATIVE HORIZONTAL POSITION PRIOR TO BEGINNING CONSTRUCTION LAYOUT. [SEE SHEET C0.2A FOR PROJECT CONTROL INFORMATION.]
- 4. PROJECT CONTROL SHALL BE FIELD VERIFIED AND CHECKED FOR RELATIVE VERTICAL POSITION BASED ON THE BENCHMARK STATED HEREON, PRIOR TO BEGINNING CONSTRUCTION LAYOUT.
- 5. WHEN DIMENSIONS AND COORDINATE LOCATIONS ARE REPRESENTED DIMENSIONS SHALL HOLD OVER COORDINATE LOCATION. NOTIFY THE CIVIL ENGINEER OF RECORD IMMEDIATELY UPON DISCOVERY OF ANY DISCREPANCIES.
- 6. BUILDING SETBACK DIMENSIONS FROM PROPERTY LINES SHALL HOLD OVER ALL OTHER CALLOUTS. PROPERTY LINES AND ASSOCIATED BUILDING SETBACKS SHALL BE VERIFIED PRIOR TO CONSTRUCTION LAYOUT.
- 7. CONTRACTOR SHALL PRESERVE AND PROTECT FROM DAMAGE ALL EXISTING MONUMENTATION DURING CONSTRUCTION. THE CONTRACTOR IS RESPONSIBLE FOR COORDINATING AND PAYING FOR THE REPLACEMENT OF ANY MONUMENTS DAMAGED OR REMOVED DURING CONSTRUCTION. NEW MONUMENTS SHALL BE REESTABLISHED BY A LICENSED SURVEYOR.
- 8. SOME SITE DEMOLITION AND UTILITY RELOCATION HAS BEEN PERFORMED. SURVEY MAY NOT BE COMPLETE OR ACCURATE. CONTRACTOR TO VERIFY EXISTING SITE CONDITIONS PRIOR TO CONSTRUCTION. CONTRACTOR SHALL BRING ANY DISCREPANCIES TO THE ATTENTION OF THE ENGINEER PRIOR TO BEGINNING CONSTRUCTION.
- 9. CONTRACTOR TO REFERENCE SOILS REPORT FOR THE SITE SOILS CONDITIONS.
- 10. ALL CONSTRUCTION AND MATERIALS SHALL CONFORM TO THESE PLANS, THE PROJECT SPECIFICATIONS AND THE APPLICABLE REQUIREMENTS OF THE 2024 OREGON STANDARD SPECIFICATIONS FOR CONSTRUCTION AND REQUIREMENTS OF THE CITY OF WOODBURN.
- 11. THE COMPLETED INSTALLATION SHALL CONFORM TO ALL APPLICABLE FEDERAL, STATE, AND LOCAL CODES, ORDINANCES AND REGULATIONS. ALL PERMITS, LICENSES AND INSPECTIONS REQUIRED BY THE GOVERNING AUTHORITIES FOR THE EXECUTION AND COMPLETION OF WORK SHALL BE SECURED BY THE CONTRACTOR PRIOR TO COMMENCING CONSTRUCTION.
- 12. ATTENTION: OREGON LAW REQUIRES YOU TO FOLLOW RULES ADOPTED BY THE OREGON UTILITY NOTIFICATION CENTER. THOSE RULES ARE SET FORTH IN OAR 952-001-0010 THROUGH OAR 952-001-0090. YOU MAY OBTAIN COPIES OF THE RULES BY CALLING THE CENTER. (NOTE: THE TELEPHONE NUMBER FOR THE OREGON UTILITY NOTIFICATION CENTER IS (503) 232-1987). EXCAVATORS MUST NOTIFY ALL PERTINENT COMPANIES OR AGENCIES WITH UNDERGROUND UTILITIES IN THE PROJECT AREA AT LEAST 48 BUSINESS-DAY HOURS, BUT NOT MORE THAN 10 BUSINESS DAYS PRIOR TO COMMENCING AN EXCAVATION, SO UTILITIES MAY BE ACCURATELY
- 13. THE LOCATION OF EXISTING UNDERGROUND UTILITIES SHOWN ON THE PLANS ARE FOR INFORMATION ONLY AND ARE NOT GUARANTEED TO BE COMPLETE OR ACCURATE. CONTRACTOR SHALL VERIFY ELEVATIONS, PIPE SIZE, AND MATERIAL TYPES OF ALL UNDERGROUND UTILITIES PRIOR TO COMMENCING WITH CONSTRUCTION AND SHALL BRING ANY DISCREPANCIES TO THE ATTENTION OF KPFF CONSULTING ENGINEERS, 72 HOURS PRIOR TO START OF CONSTRUCTION TO PREVENT GRADE AND ALIGNMENT CONFLICTS.
- 14. THE ENGINEER OR OWNER IS NOT RESPONSIBLE FOR THE SAFETY OF THE CONTRACTOR OR HIS CREW. ALL O.S.H.A. REGULATIONS SHALL BE STRICTLY ADHERED TO IN THE PERFORMANCE OF THE
- 15. TEMPORARY AND PERMANENT EROSION CONTROL MEASURES SHALL BE IMPLEMENTED. THE CONTRACTOR SHALL ADHERE TO CITY OF WOODBURN DRAINAGE MANUAL AND DEQ MANUAL AND BEST MANAGEMENT PRACTICES FOR MINIMUM EROSION CONTROL MEASURES. THE ESC FACILITIES SHOWN IN THESE PLANS ARE THE MINIMUM REQUIREMENTS FOR ANTICIPATED SITE CONDITIONS. DURING THE CONSTRUCTION PERIOD, ESC FACILITIES SHALL BE UPGRADED AS NEEDED FOR UNEXPECTED STORM EVENTS AND TO ENSURE THAT SEDIMENT AND SEDIMENT LADEN WATER DO NOT LEAVE THE SITE.
- 16. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING ALL ROADWAYS, KEEPING THEM CLEAN AND FREE OF CONSTRUCTION MATERIALS AND DEBRIS, AND PROVIDING DUST CONTROL AS REQUIRED.
- 17. TRAFFIC CONTROL SHALL BE PROVIDED BY THE CONTRACTOR THROUGHOUT CONSTRUCTION. CONTRACTOR SHALL PROVIDE A TRAFFIC CONTROL PLAN TO THE CITY OF WOODBURN FOR REVIEW AND APPROVAL PRIOR TO COMMENCING CONSTRUCTION.
- 18. CONTRACTOR SHALL MAINTAIN ALL UTILITIES TO THE WOODBURN COMMUNITY CENTER DURING OPERATING HOURS. CHECK WITH THE CITY OF WOODBURN FOR MORE REQUIREMENTS.
- 19. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING AND SCHEDULING ALL WORK WITH THE OWNER.
- 20. NOTIFY CITY INSPECTOR 72 HOURS BEFORE STARTING WORK. A PRECONSTRUCTION MEETING WITH THE CITY'S REPRESENTATIVE, THE CITY'S ARCHITECT, THE CITY'S ENGINEER, AND THE CONTRACTOR SHALL BE REQUIRED.

CONSTRUCTION NOTES

<u>GENERAL</u>

- ACTUAL LINES AND GRADES SHALL BE STAKED BY A PROFESSIONAL SURVEYOR, REGISTERED IN THE STATE OF OREGON, BASED ON DIMENSIONS, ELEVATIONS AND BEARINGS AS SHOWN ON THE PLANS.
- 2. SUBGRADE AND TRENCH BACKFILL SHALL BE COMPACTED TO AT LEAST 95% OF THE MAXIMUM DRY DENSITY AS DETERMINED BY ASTM D-698. FLOODING OR JETTING THE BACKFILLED TRENCHES WITH WATER IS NOT PERMITTED.
- 3. SPECIAL INSPECTION REQUIRED FOR ALL COMPACTION TESTING.

DEMOLITION

- THE CONTRACTOR SHALL BE RESPONSIBLE FOR DEMOLITION AND DISPOSAL OF EXISTING AC, CURBS, SIDEWALKS AND OTHER SITE ELEMENTS WITHIN THE SITE AREA IDENTIFIED IN THE PLANS.
- 2. EXCEPT FOR MATERIALS INDICATED TO BE STOCKPILED OR TO REMAIN ON OWNER'S PROPERTY, CLEARED MATERIALS SHALL BECOME CONTRACTOR'S PROPERTY, REMOVED FROM THE SITE, AND
- 3. ITEMS INDICATED TO BE SALVAGED SHALL BE CAREFULLY REMOVED AND DELIVERED STORED AT THE PROJECT SITE AS DIRECTED BY THE OWNER.
- 4. ALL LANDSCAPING, PAVEMENT, CURBS AND SIDEWALKS, BEYOND THE IDENTIFIED SITE AREA, DAMAGED DURING THE CONSTRUCTION SHALL BE REPLACED TO THEIR ORIGINAL CONDITION OR
- 5. CONCRETE SIDEWALKS SHOWN FOR DEMOLITION SHALL BE REMOVED TO THE NEAREST EXISTING CONSTRUCTION JOINT.
- 6. SAWCUT STRAIGHT MATCHLINES TO CREATE A BUTT JOINT BETWEEN THE EXISTING AND NEW PAVEMENT.

UTILITIES

- 1. ADJUST ALL INCIDENTAL STRUCTURES, MANHOLES, VALVE BOXES, CATCH BASINS, FRAMES AND COVERS, ETC. TO FINISHED GRADE.
- 2. CONTRACTOR SHALL ADJUST ALL EXISTING AND/OR NEW FLEXIBLE UTILITIES (WATER, TV, TELEPHONE, ELEC., ETC.) TO CLEAR ANY EXISTING OR NEW GRAVITY DRAIN UTILITIES (STORM DRAIN, SANITARY SEWER, ETC.) IF CONFLICT OCCURS.
- 3. CONTRACTOR SHALL COORDINATE WITH PRIVATE UTILITY COMPANIES FOR THE INSTALLATION OF OR ADJUSTMENT TO GAS. ELECTRICAL. POWER AND TELEPHONE SERVICE.
- 4. BEFORE BACKFILLING ANY SUBGRADE UTILITY IMPROVEMENTS CONTRACTOR SHALL SURVEY AND RECORD MEASUREMENTS OF EXACT LOCATION AND DEPTH AND SUBMIT TO ENGINEER AND OWNER.
- 5. ALL WORK TO CONFORM TO THE 2023 OREGON PLUMBING SPECIALTY CODE

STORM AND SANITARY

- CONNECTIONS TO EXISTING STORM AND SANITARY SEWERS SHALL CONFORM TO THE 2018 OREGON STANDARD SPECIFICATIONS FOR CONSTRUCTION, SECTION 00490, "WORK ON EXISTING SEWERS AND STRUCTURES".
- 2. BEGIN LAYING STORM DRAIN AND SANITARY SEWER PIPE AT THE LOW POINT OF THE SYSTEM, TRUE TO GRADE AND ALIGNMENT INDICATED WITH UNBROKEN CONTINUITY OF INVERT. THE CONTRACTOR SHALL ESTABLISH LINE AND GRADE FOR THE STORM AND SANITARY SEWER PIPE USING A LASER.
- 3. ACTUAL LINES AND GRADES SHALL BE STAKED BY A QUALIFIED SURVEYOR, BASED ON COORDINATES, DIMENSIONS AND BEARINGS INDICATED ON THE PLANS. CONTRACTOR SHALL RETAIN A SURVEYOR LICENSED IN THE STATE OF OREGON.
- NOTED OTHERWISE IN THE PLANS.
- 5. ALL HORIZONTAL CONNECTIONS TO THE SANITARY OR STORM SEWERS SHALL BE OF THE 'WYE' BRANCH TYPE.

4. ALL ROOF DRAIN AND CATCH BASIN LEADERS SHALL HAVE A MINIMUM SLOPE OF 2 PERCENT UNLESS

WATER

- 1. ALL WATER AND FIRE PROTECTION PIPE SHALL HAVE A MINIMUM 36-INCH COVER TO THE FINISH
- 2. ALL WATER AND FIRE PRESSURE FITTINGS SHALL BE PROPERLY RESTRAINED WITH THRUST BLOCKS PER DETAIL.
- 3. ALL WATER MAIN / SANITARY SEWER CROSSINGS SHALL CONFORM TO THE OREGON STATE HEALTH DEPARTMENT REGULATIONS, CHAPTER 333.

EARTHWORKS

- 1. CONTRACTOR SHALL PREVENT SEDIMENTS AND SEDIMENT LADEN WATER FROM ENTERING THE STORM DRAINAGE SYSTEM.
- 2. TRENCH BEDDING AND BACKFILL SHALL BE AS SHOWN ON THE PIPE BEDDING AND BACKFILL DETAIL, THE PROJECT SPECIFICATIONS AND AS REQUIRED IN THE SOILS REPORT. FLOODING OR JETTING THE BACKFILLED TRENCHES WITH WATER WILL NOT BE PERMITTED.

<u>PAVING</u>

1. SEE LANDSCAPE PLANS FOR SIDEWALK FINISHING AND SCORING PATTERNS.

SEPARATION STATEMENT

ALL WATER MAIN CROSSINGS SHALL CONFORM TO THE OREGON STATE HEALTH DEPARTMENT, CHAPTER 333. WATER MAINS SHALL CROSS OVER SANITARY SEWERS WITH A 18" MINIMUM CLEARANCE BETWEEN OUTSIDE DIAMETERS OF PIPE WITH ALL PIPE JOINTS EQUIDISTANT FROM CROSSING. HORIZONTAL SEPARATION BETWEEN WATER MAINS AND SANITARY SEWERS IN PARALLEL INSTALLATIONS SHALL BE 10'. MAINTAIN 12" MINIMUM VERTICAL DISTANCE FOR ALL OTHER UTILITY CROSSINGS AND 12" HORIZONTAL PARALLEL DISTANCE. IN CASES WHERE IT IS NOT POSSIBLE TO MAINTAIN THE MINIMUM 10' HORIZONTAL SEPARATION, THE WATER MAIN SHALL BE LAID ON A SEPARATE SHELF IN THE TRENCH 18" INCHES ABOVE THE SEWER.

MATERIAL NOTES

- GENERAL: MATERIALS SHALL BE NEW. THE USE OF MANUFACTURER'S NAMES, MODELS, AND NUMBERS IS INTENDED TO ESTABLISH STYLE, QUALITY, APPEARANCE, AND USEFULNESS. PROPOSED SUBSTITUTIONS WILL REQUIRE WRITTEN APPROVAL FROM ARCHITECT AND OWNER PRIOR TO INSTALLATION.
- 2. STORM AND SANITARY SEWER PIPING SHALL BE PVC PIPE, DUCTILE IRON PIPE, REINFORCED CONCRETE PIPE (RCP), OR HIGH DENSITY POLYETHYLENE (HDPE) PIPE CONFORMING TO THE PROJECT SPECIFICATIONS; AS INDICATED IN THE PLANS.
- PRIVATE WATER MAINS 4-INCH DIAMETER AND LARGER SHALL BE DUCTILE IRON PIPE OR PVC PIPE CONFORMING TO THE PROJECT SPECIFICATIONS; AS INDICATED IN THE PLANS.
- 4. PRIVATE WATER LINES 3-INCH DIAMETER AND SMALLER SHALL BE TYPE K COPPER TUBING OR SCHEDULE 40 PVC CONFORMING TO THE PROJECT SPECIFICATIONS; AS INDICATED IN THE PLANS.
- 5. CONCRETE FOR CURBS, SIDEWALK AND DRIVEWAYS SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 3,500 PSI AT 28 DAYS.

ABBREVIATIONS

OVH/OH

OVERHEAD

AC	ASPHALT CONCRETE	P/L	PROPERTY LINE
AD	AREA DRAIN	PC	POINT OF CURVATURE
APPROX	APPROXIMATE	PCC	POINT OF COMPOUND CURVATURE
В	BOLLARD	PCR	POINT OF CURB RETURN
BLDG	BUILDING	PED	PEDESTRIAN
BOW	BACK OF WALK	PM	PARKING METER
BS	BOTTOM OF SWALE	POC	POINT ON CURVE
ВО	BOTTOM OF STAIR	PP	POWER POLE
BW	BOTTOM OF WALL	PRC	POINT OF REVERSE CURVATURE
CB	CATCH BASIN	PT	POINT OF TANGENT
CL	CENTERLINE	P.U.E	PUBLIC UTILITY EASEMENT
CO		P.U.E PVC	
CONC.	CLEANOUT	PVC PVMT	POLYVINYL CHLORIDE PAVEMENT
	CONCRETE		—
COTG	CLEANOUT TO GRADE	PVT	PRIVATE
CP	CONTROL POINT	R	RIM
Δ	DELTA	RD	ROOF DRAIN
D/W	DRIVEWAY	R.O.W	RIGHT-OF-WAY
DIA.,Ø	DIAMETER	S	SLOPE (FT/FT)
DIP	DUCTILE IRON PIPE	SD	STORM DRAIN
E	EASTING	SDMH	STORM DRAIN MANHOLE
EXIST./EX	EXISTING	SHT	SHEET
FDC	FIRE DEPARTMENT CONNECTION	SS	SANITARY SEWER
FF	FINISH FLOOR ELEVATION	SSMH	SANITARY SEWER MANHOLE
FG	FINISH GRADE	ST	STREET
FH	FIRE HYDRANT	STA	STATION
FL	FLOWLINE	STD	STANDARD
FND	FOUNDATION	S/W	SIDEWALK
G	GUTTER	TC	TOP OF CURB
GB	GRADE BREAK	TD	TRENCH DRAIN
GL	GAS LINE	TG	TOP OF GROUND
GV	GATE VALVE	TP	TOP OF PAVEMENT
Н	HEIGHT	TRANS.	TRANSFORMER
HCP	HANDICAP PARKING SPACE	TS	TOP OF STAIR
HP	HIGH POINT	TW	TOP OF WALL
IE	INVERT ELEVATION		TOP OF WALK
INV	INVERT	TYP	TYPICAL
IRR.	IRRIGATION	UG	UNDERGROUND
LP	LIGHT POLE	UGE	UNDERGROUND ELECTRIC
MH	MANHOLE	W	WATER
MIN	MINIMUM	W/	WITH
N	NORTHING	WCR	WHEEL CHAIR RAMP
OF			



WV

WATER VALVE



VICINITY MAP

SCALE: NTS

PROIECT CONTACTS

OWNER:
CITY OF WOODBURN
CITY OF WOODBURN 270 MONTGOMERY ST
WOODBURN, OREGON 97071
TEL: 503-XXX-XXXX
CONTACT: JESSE CUOMO

CIVIL ENGINEER/PROJECT MANAGER:
KPFF CONSULTING ENGINEERS
111 SW FIFTH AVENUE, SUITE 2600
PORTLAND, OREGON 97204
TEL: 503-542-3840
CONTACT: JOSH LIGHTHIPE

LANDSCAPE ARCHITECT:

LANGO HANSEN LANDSCAPE
ARCHITECTS

1100 NW GLISAN #3A,
PORTLAND, OREGON 97209
TEL: 971-380-3580
CONTACT: KYLE TRULEN

PORTLAND, OREGON 97214

CONTACT: JUSTINE BANDA

ARCHITECT:

975 SE MAIN ST.

TEL: 646-306-4120

OPSIS

SHEET INDEX

SHEET INDEX		
SHEET COUNT	SHEET NUMBER	SHEET TITLE
1	C0.1	COVER SHEET
2	C0.2A	EXISTING CONDITIONS
3	C0.2B	EXISTING CONDITIONS
4	C0.3	FEMA OVERLAY MAP
5	C0.4	FIRE ACCESS PLAN
6	C1.0	DEMOLITION PLAN
7	C2.0	SITE PLAN
8	C3.0	GRADING PLAN - OVERALL
9	C3.1	GRADING PLAN - AREA 1
10	C3.2	GRADING PLAN - AREA 2
11	C3.3	GRADING PLAN - AREA 3
12	C3.4	GRADING PLAN - AREA 4
13	C3.5	GRADING PLAN ENLARGEMENT & SECTIONS
14	C4.0	UTILITY PLAN
15	C4.1	UTILITY PLAN ENLARGEMENT 1
16	C4.2	UTILITY PLAN ENLARGEMENT 2
17	C5.0	CIVIL DETAILS
18	C5.1	CIVIL DETAILS
19	C5.2	CIVIL DETAILS
20	C6.0	EROSION AND SEDIMENT CONTROL PLAN
21	C7.0	EROSION AND SEDIMENT CONTROL DETAILS

opsis

111 SW Fifth Ave., Suite 2600
Portland, OR 97204
O: 503 542 3860

www.opsisarch.com

PRELIMITE OR TOP

Project Owner:
City Of Woodburn Oregoi

Project Name:
Woodburn Community
Center
Project Adress:
190 Oak Street

Woodburn, OR 97071

Key Plan

copyright 201

THESE DRAWINGS ARE THE PROPERTY OF OPSIS ARCHITECTURE LLP AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER, WITHOUT PRIOR WRITTEN PERMISSION.

Revisions to Sheet

Status: PLANNING COMMISSION


DESIGN REVIEW


Date: 10.28.2025

Sheet Title
COVER SHEET

ATTACHMENT 106A Community Center Plans

C0.1





FIRE APPARATUS ACCESS ROADS SHALL BE IN ACCORDANCE WITH THE 2022 OREGON FIRE CODE AND ALL OTHER APPLICABLE REQUIREMENTS OF THE INTERNATIONAL FIRE CODE.

1. FLOW TEST RESULTS

104 HYDRANT TESTED ON 5/08/2025

STATIC: 56 PSIG RESIDUAL: 47 PSIG

3. CURBS IN FIRE ACCESS ZONES SHALL BE PAINTED RED WITH WHITE "NO PARKING FIRE LANE" STENCIL AT A MINIMUM OF 20' ON CENTER. TEXT SHALL BE 1 INCH WIDE BY 6 INCHES HIGH PER OFC 503.3.

UTILITY LABEL LEGEND


STRUCTURE TYPE

DETAIL REF. FDC FIRE DEPARTMENT CONNECTION

FH FIRE HYDRANT (PRIVATE OR PUBLIC AS NOTED)

SHEET LEGEND

FIRE APPARATUS PATH OF TRAVEL AND MANEUVER NUMBER HOSE PULL, LENGTH AS NOTED.



4773-01

C_{0.4}

111 SW Fifth Ave., Suite 2600 Portland, OR 97204 O: 503.542.3860 F: 503.274.4681 <u>www.kpff.com</u>

www.opsisarch.com



Project Owner: City Of Woodburn Oregon

Project Name: Project Adress: 190 Oak Street Woodburn, OR 97071


Key Plan


THESE DRAWINGS ARE THE PROPERTY OF OPSIS ARCHITECTURE LLP AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER, WITHOUT PRIOR WRITTEN PERMISSION. Revisions to Sheet

Status: PLANNING COMMISSION DESIGN REVIEW

10.28.2025

FIRE ACCESS PLAN





opsis



F: 503.274.4681

www.kpff.com

www.opsisarch.com



Project Owner:

City Of Woodburn Oregon

Project Name:
Woodburn Community
Center
Project Adress:

Project Adress:
190 Oak Street
Woodburn, OR 97071
Key Plan

copyright 2018

THESE DRAWINGS ARE THE PROPERTY OF OPSIS ARCHITECTURE LLP AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER, WITHOUT PRIOR WRITTEN PERMISSION.

Revisions to Sheet

No. Revision Date

Sheet No.

4773-01


C1.0

Status: PLANNING COMMISSION DESIGN REVIEW

DEMOLITION PLAN

Sheet Title

10.28.2025



SHEET NOTES

- 1. ALL DIMENSIONS ARE TO FACE OF CURB OR FACE OF WALL. ALL SIDEWALK PAVEMENT JOINTS SHALL BE CONSTRUCTED PER DETAIL 15/C5.0.
- 3. PROPOSED FRONTAGE IMPROVEMENTS IN ROW SHALL BE CONSTRUCTED PER CITY OF WOODBURN AND/OR ODOT CONSTRUCTION STANDARDS AND DETAILS.
- 4. SLOPES PROVIDED ON SLOPE ARROW ARE FOR REFERENCE

111 SW Fifth Ave., Suite 2600 Portland, OR 97204 O: 503.542.3860 F: 503.274.4681 <u>www.kpff.com</u>

www.opsisarch.com

Project Owner:

City Of Woodburn Oregon

Woodburn Community

Woodburn, OR 97071

Project Adress: 190 Oak Street

Key Plan

- 5. LANDINGS ON ACCESSIBLE ROUTES SHALL NOT EXCEED 2% IN ANY DIRECTION.
- 6. ALL ACCESSIBLE ROUTES SHALL COMPLY WITH CURRENT ADA ACCESSIBILITY GUIDELINES FOR BUILDING AND FACILITIES (ADAAG).

× KEY NOTES

.#	DESCRIPTION	DETAIL <u>REF.</u>
1	SAWCUT	
2A	CONCRETE CURB	2A/C5.0
2B	CONCRETE CURB AND GUTTER	2B/C5.0
2C	THICKENED CURB AND GUTTER	2C/C5.0
2D	FLUSH CURB	2E/C5.0
3A	REMOVABLE BOLLARD	
3B	STANDARD BOLLARD	
4	WHEEL STOP	4/C5.0
5	SIDEWALK	1C/C5.0
6A	ADA PARKING STALLS AND STRIPING	2/C5.0
6B	'NO PARKING" ZONE STRIPING	3/C5.0
6C	4" WIDE WHITE STRIPE	
7	ADA PARKING SIGN	4/C5.0
8	DETECTABLE WARNING	8/C5.0
9	CURB RAMP	10/C5.0
10	'SIDEWALK CLOSED' SIGN	

× ARCHITECTURAL KEY NOTES

	(SHOWN FOR REFERENCE, SEE ARCHITECTURAL PLA	NS)
#	DESCRIPTION	DETAIL <u>REF.</u>
A1	TRASH ENCLOSURE	

	(SHOWN FOR REFERENCE, SEE	ELECTRICAL PLANS)
ш	DESCRIPTION	DETA
#	<u>DESCRIPTION</u>	RFF

- E1 ELECTRICAL CHARGER & YARD BOX
- E2 STREET LIGHT
- E3 ON-SITE LIGHTING

× LANDSCAPE (SHOWN FOR REFERENCE, SEE LANDSCAPE PLANS)

#	DESCRIPTION
L1	CONCRETE WALL
12	CONCRETE WAI KWAY/PLAZA

- L2 CONCRETE WALKWAY/PLAZA
- L3 SEAT WALL
- L4 STAIRS AND HANDRAIL L5 BIKE RACKS

× PUBLIC KEY NOTES (SEE SHEET NOTE 3)

#	DESCRIPTION	DETAIL REF. (ODOT OR COW
P1A	PERPENDICULAR CURB RAMP	RD910
P1B	PERPENDICULAR CURB RAMP THROUGH BUFFER STRIP RD912	
P1C	RAMP FOR WIDE SIDEWALKS OPTION "PR-2" RD910	
P2A	TYPE ' C' CURB	4100-2
P2B	FLUSH CURB	
P2C	TYPE 'A' CURB & GUTTER	4100-2
P2D	MOUNTABLE CURB	RD700
P2E	TYPE 'A' CURB AT DRIVEWAY	4100-4
P3A	REMOVABLE BOLLARD	RD130
P3B	STANDARD BOLLARD	RD130
P4	DRIVEWAY APPROACH	4150-1
P5	SURFACE FULL DEPTH REPAIR	4220-1
P6	SIDEWALKS	4150-8

SHEET LEGEND

	PROPERTY LINE
	CONCRETE PAVEMENT - DRIVE AISLES - PARKING STALLS
	ASPHALT PAVEMENT - DRIVE AISLES - PARKING STALLS TB C5.1
\(\psi\) \(\	STORMWATER 5 BASIN C5.

Status: PLANNING COMMISSION DESIGN REVIEW 10.28.2025

THESE DRAWINGS ARE THE PROPERTY OF OPSIS ARCHITECTURE LLP AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER, WITHOUT PRIOR WRITTEN PERMISSION.


Revisions to Sheet

Sheet Title
SITE PLAN





C2.0



SCALE: 1" = 10'

P1B

. P1A / ROW

SHEET NOTES

- 1. ALL DIMENSIONS ARE TO FACE OF CURB OR FACE OF WALL. 2. ALL SIDEWALK PAVEMENT JOINTS SHALL BE CONSTRUCTED PER DETAIL 15/C5.0.
- 3. PROPOSED FRONTAGE IMPROVEMENTS IN ROW SHALL BE CONSTRUCTED PER CITY OF WOODBURN AND/OR ODOT CONSTRUCTION STANDARDS AND DETAILS.
- 4. SLOPES PROVIDED ON SLOPE ARROW ARE FOR REFERENCE ONLY.

111 SW Fifth Ave., Suite 2600 Portland, OR 97204 O: 503.542.3860 F: 503.274.4681 <u>www.kpff.com</u>

www.opsisarch.com

Project Owner:

Project Name:

Project Adress: 190 Oak Street

Center

Key Plan

Woodburn Community

Woodburn, OR 97071

City Of Woodburn Oregon

- 5. LANDINGS ON ACCESSIBLE ROUTES SHALL NOT EXCEED 2% IN ANY DIRECTION.
- 6. ALL ACCESSIBLE ROUTES SHALL COMPLY WITH CURRENT ADA ACCESSIBILITY GUIDELINES FOR BUILDING AND FACILITIES (ADAAG).

× KEY NOTES

		NET 110 TES	
1.	#	DESCRIPTION	DETAIL <u>REF.</u>
	1	SAWCUT	
	2A	CONCRETE CURB	2A/C5.0
	2B	CONCRETE CURB AND GUTTER	2B/C5.0
	2C	THICKENED CURB AND GUTTER	2C/C5.0
	2D	FLUSH CURB	2E/C5.0
	3A	REMOVABLE BOLLARD	
	3B	STANDARD BOLLARD	
	4	WHEEL STOP	4/C5.0
	5	SIDEWALK	1C/C5.0
	6A	ADA PARKING STALLS AND STRIPING	2/C5.0
	6B	'NO PARKING" ZONE STRIPING	3/C5.0
	6C	4" WIDE WHITE STRIPE	
	7	ADA PARKING SIGN	4/C5.0
	8	DETECTABLE WARNING	8/C5.0
	9	CURB RAMP	10/C5.0
	10	'SIDEWALK CLOSED' SIGN	

ARCHITECTURAL KEY NOTES

	(SHOWN FOR REFERENCE, SEE ARCHITECTU	RAL PLANS)
#	DESCRIPTION	DETAI REF.
A1	TRASH ENCLOSURE	

•	(SHOWN FOR REFERENCE, SEE ELECTRICA	L PLANS)
#	DESCRIPTION	DETA REF

- E1 ELECTRICAL CHARGER E2 STREET LIGHT
- E3 ON-SITE LIGHTING

× LANDSCAPE

	(SHOWN FOR REFERENCE, SEE LANDSCAPE PLANS	3)
#	DESCRIPTION	DI <u>F</u>
L1	CONCRETE WALL	
L2	CONCRETE WALKWAY/PLAZA	

L3 SEAT WALL

L4 STAIRS AND HANDRAIL L5 BIKE RACKS

(x)	PUBLIC KEY NOTES	
•	(SEE SHEET NOTE 3)	
#	DESCRIPTION	DETAIL <u>REF.</u> (ODOT OR COV
P1A	PERPENDICULAR CURB RAMP	RD910
P1B	PERPENDICULAR CURB RAMP THROUGH BUFFER STRIP RD912	
P1C	RAMP FOR WIDE SIDEWALKS OPTION "PR-2" RD910	
P2A	TYPE ' C' CURB	4100-2
P2B	FLUSH CURB	
P2C	TYPE 'A' CURB & GUTTER	4100-2
P2D	MOUNTABLE CURB	RD700
P2E	TYPE 'A' CURB AT DRIVEWAY	4100-4
P3A	REMOVABLE BOLLARD	RD130
P3B	STANDARD BOLLARD	RD130
P4	DRIVEWAY APPROACH	4150-1
P5	SURFACE FULL DEPTH REPAIR	4220-1
P6	SIDEWALKS	4150-8

CHEET LECENID

SHEET LEGEND	
	PROPERTY LINE
	- DRIVE AISLES - PARKING STALLS
	- DRIVE AISLES - PARKING STALLS - PARKING STALLS
\(\psi\) \(\	STORMWATER 5 BASIN C5.1

Status: PLANNING COMMISSION DESIGN REVIEW 10.28.2025


THESE DRAWINGS ARE THE PROPERTY OF OPSIS ARCHITECTURE LLP AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER, WITHOUT PRIOR WRITTEN PERMISSION.

Revisions to Sheet

Sheet Title SITE PLAN -**ENLARGEMENTS**


Sheet No.





4773-01

C2.1



SHEET NOTES

- PRIOR TO CONSTRUCT FIELD VERIFY LOCATIONS, SIZE AND IE OF ALL EXISTING UTILITIES AT PROPOSED POINTS OF CONNECTION OR WHERE NOTED, NOTIFY ENGINEER
 - ON-SITE PIPE BEDDING AND BACKFILL FOR ALL UTILITIES SHALL BE DONE PER DETAIL 1/C5.1.
 - OFF-SITE (IN ROW) PIPE BEDDING AND TRENCH BACKFILL AND
 - STRUCTURES LOCATIONS ARE BASED ON CENTER OF
 - STRUCTURE.
 - STD DWG 5000-1, 5000-2, AND 5000-3

Portland, OR 97204 O: 503.542.3860 F: 503.274.4681

www.opsisarch.com

Project Owner:

City Of Woodburn Oregon

Woodburn Community

Woodburn, OR 97071

Project Adress:

Key Plan

190 Oak Street

- INSTALLATION OF SAMPLING TAP ASSEMBLY TO BE PER CITY
- STD DWG 5100-1.
- INSTALLATION OF SANITARY SEWER SERVICE PER CITY STD

× KEY NOTES

- 1 CONNECT TO EXISTING PIPE. SEE SHEET NOTE 1.
- 2 COORDINATE TEMPORARY SHUT DOWN WITH CITY PUBLIC

× UTILITY KEY NOTES

NOTE DESCRIPTION ADJ ADJUST RIM TO PROPOSED ELEVATION.

- WITH FRANCHISE COMPANY E CONNECT 1" CONDUIT, SEE AQUATIC PLANS ELECTRICAL VEHICLE CONDUIT AND VAULT, SEE
- STREET LIGHT CONDUIT, VERIFY ROUTING WITH
- CONNECT TO WASTE LINE. SEE PLUMBING PLANS FOR CONTINUATION. SIZE AS NOTED.
- CONNECT TO STORM DRAIN/ROOF DRAIN. SEE
- CONNECT TO COLD WATER SYSTEM. SEE W PLUMBING PLANS FOR CONTINUATION. SIZE AS
- UTILITY CROSSING. PROVIDE 12" MIN. CLEARANCE, U.N.O.
- MAINTENANCE EXISTING UTILITY PIPE AND CONFIRM FUNCTIONAL.

UTILITY LABEL LEGEND

STRUCTURE LABEL —— UTILITY TYPE (SD=STORM DRAINAGE, SS=SANITARY

SEWER, W=WATER, FP=FIRE PROTECTION) ——— STRUCTURE TYPE CALLOUT ID NUMBER (WHERE APPLICABLE)

IE IN = XX.X

STRUCTURE INFO (WHERE APPLICABLE)

PIPE LABEL

----- UTILITY LENGTH UTILITY SIZE

S=X.XX% SLOPE (WHERE APPLICABLE)

STRUCTURE TYPE

CALLOUT	DESCRIPTION	DETAIL REF.
BWV	BACKWATER VALVE	
СВ	CATCH BASIN	4/C5.1
CO	CLEANOUT TO GRADE	6200-1
CG-2	CONCRETE INLET	RD366
DCBA	DOUBLE CHECK BACKFLOW ASSEMBLY	1/C5.2
DCVA	DOUBLE CHECK VALVE ASSEMBLY	5070-2
FC	FLOW-CONTROL VAULT	1/C5.1
FDC	FIRE DEPARTMENT CONNECTION	(SEE OTHERS)
FH	FIRE HYDRANT	5070-1
G-2	CONCRETE INLET	RD364
GV	GATE VALVE	5050-2
HB	HORIZONTAL BEND	
MH	MANHOLE	6510-3
OV	OVERFLOW INLET	3/C5.1
SCB	SANITARY CATCH BASIN	9/C5.1
STUB	STUB	
TD	TRENCH DRAIN	2/C5.1
TEE	TEE CONNECTION	
W	WATERLINE	
WM	WATER METER	6/C5.2

SHEET LEGEND

STORMWATER PLANTER/BASIN

— — — — — — PERIMETER FOUNDATION DRAIN

MANHOLE

OVERFLOW INLET BACKWATER VALVE

CATCH BASIN

OUTFALL PIPE REMOVAL Status: PLANNING COMMISSION **DESIGN REVIEW** 10.28.2025

THESE DRAWINGS ARE THE PROPERTY OF OPSIS ARCHITECTURE LLP AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER,


Revisions to Sheet


UTILITY PLAN

Sheet Title

Sheet No.

C4.0





SCALE: 1" = 5'

SHEET NOTES

- PRIOR TO CONSTRUCT FIELD VERIFY LOCATIONS, SIZE AND IE OF ALL EXISTING UTILITIES AT PROPOSED POINTS OF CONNECTION OR WHERE NOTED, NOTIFY ENGINEER DISCREPANCIES.
 - 2. ON-SITE PIPE BEDDING AND BACKFILL FOR ALL UTILITIES SHALL BE DONE PER DETAIL 1/C5.1.
 - 3. OFF-SITE (IN ROW) PIPE BEDDING AND TRENCH BACKFILL AND

111 SW Fifth Ave., Suite 2600 Portland, OR 97204 O: 503.542.3860 F: 503.274.4681 <u>www.kpff.com</u>

www.opsisarch.com

Project Owner:

Project Name:

Project Adress:

Key Plan

190 Oak Street

Woodburn Community

Woodburn, OR 97071

City Of Woodburn Oregon

- SURFACING PER CITY STD DWG P-100 AND P-101. STRUCTURES LOCATIONS ARE BASED ON CENTER OF
- INSTALL TRUST BLOCK ON FIRE AND WATER LINES PER CITY
- INSTALLATION OF WATER MAIN AIR RELEASE VALVES TO BE DONE PER CITY STD DWG 5050-3.
- INSTALLATION OF SAMPLING TAP ASSEMBLY TO BE PER CITY
- INSTALLATION OF SANITARY SEWER SERVICE PER CITY STD DWG 6200-3.

× KEY NOTES

- 1 CONNECT TO EXISTING PIPE. SEE SHEET NOTE 1.
- CUT-IN-TEE CONNECTION TO EX PUBLIC WATER LINE. COORDINATE TEMPORARY SHUT DOWN WITH CITY PUBLIC

⟨×⟩ UTILITY KEY NOTES

NOTE DESCRIPTION ADJ ADJUST RIM TO PROPOSED ELEVATION. PROPOSED TELECOM / DATA, VERIFY ROUTING WITH FRANCHISE COMPANY

- ELECTRICAL VEHICLE CONDUIT AND VAULT, SEE ELECTRICAL PLANS. FD FOUNDATION DRAIN
- CONNECT TO WASTE LINE. SEE PLUMBING PLANS FOR CONTINUATION. SIZE AS NOTED.
- CONNECT TO STORM DRAIN/ROOF DRAIN. SEE SD PLUMBING PLANS FOR CONTINUATION. SIZE AND IE
- AS NOTED CONNECT TO COLD WATER SYSTEM. SEE
- W PLUMBING PLANS FOR CONTINUATION. SIZE AS
- MAINTENANCE EXISTING UTILITY PIPE AND CONFIRM FUNCTIONAL.

UTILITY LABEL LEGEND

STRUCTURE LABEL —— UTILITY TYPE (SD=STORM DRAINAGE, SS=SANITARY SEWER, W=WATER, FP=FIRE PROTECTION) STRUCTURE TYPE CALLOUT

ID NUMBER (WHERE APPLICABLE) IE IN = XX.X STRUCTURE INFO (WHERE APPLICABLE)

PIPE LABEL

CALLOUT	DESCRIPTION	DETAIL REF
BWV	BACKWATER VALVE	
СВ	CATCH BASIN	4/C5.1
CO	CLEANOUT TO GRADE	6200-1
CG-2	CONCRETE INLET	RD366
DCBA	DOUBLE CHECK BACKFLOW ASSEMBLY	1/C5.2
DCVA	DOUBLE CHECK VALVE ASSEMBLY	5070-2
FC	FLOW-CONTROL VAULT	1/C5.1
FDC	FIRE DEPARTMENT CONNECTION	(SEE OTHER
FH	FIRE HYDRANT	5070-1
G-2	CONCRETE INLET	RD364
GV	GATE VALVE	5050-2
HB	HORIZONTAL BEND	
MH	MANHOLE	6510-3
OV	OVERFLOW INLET	3/C5.1
SCB	SANITARY CATCH BASIN	9/C5.1
STUB	STUB	
TD	TRENCH DRAIN	2/C5.1
TEE	TEE CONNECTION	
W	WATERLINE	
WM	WATER METER	6/C5.2

STORMWATER PLANTER/BASIN

— — — — — — PERIMETER FOUNDATION DRAIN

MANHOLE OVERFLOW INLET BACKWATER VALVE CATCH BASIN

OUTFALL

Sheet Title **UTILITY PLAN ENLARGEMENT 1**



C4.1

Sheet No.

4773-01

Status: PLANNING COMMISSION DESIGN REVIEW

10.28.2025

THESE DRAWINGS ARE THE PROPERTY OF OPSIS ARCHITECTURE LLP AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER,

WITHOUT PRIOR WRITTEN PERMISSION.

Revisions to Sheet


S=X.XX% SLOPE (WHERE APPLICABLE) STRUCTURE TYPE

UTILITY SIZE

SHEET LEGEND

STORM PIPE

PIPE REMOVAL · // // // // //





- PRIOR TO CONSTRUCT FIELD VERIFY LOCATIONS, SIZE AND IE OF ALL EXISTING UTILITIES AT PROPOSED POINTS OF CONNECTION OR WHERE NOTED, NOTIFY ENGINEER DISCREPANCIES.
- 2. ON-SITE PIPE BEDDING AND BACKFILL FOR ALL UTILITIES SHALL BE DONE PER DETAIL 1/C5.1.
- 3. OFF-SITE (IN ROW) PIPE BEDDING AND TRENCH BACKFILL AND
- 4. STRUCTURES LOCATIONS ARE BASED ON CENTER OF
- 5. INSTALL TRUST BLOCK ON FIRE AND WATER LINES PER CITY
- 6. INSTALL UTILITIES PER CITY STD DWG 5000-6 AND 6200-4.
- 7. INSTALLATION OF WATER MAIN AIR RELEASE VALVES TO BE DONE PER CITY STD DWG 5050-3.
- 8. INSTALLATION OF SAMPLING TAP ASSEMBLY TO BE PER CITY STD DWG 5100-1.
- 9. INSTALLATION OF SANITARY SEWER SERVICE PER CITY STD DWG 6200-3.

× KEY NOTES

- 1 CONNECT TO EXISTING PIPE. SEE SHEET NOTE 1.
- CUT-IN-TEE CONNECTION TO EX PUBLIC WATER LINE. 2 COORDINATE TEMPORARY SHUT DOWN WITH CITY PUBLIC WORKS.

NOTE DESCRIPTION ADJ ADJUST RIM TO PROPOSED ELEVATION. PROPOSED TELECOM / DATA, VERIFY ROUTING WITH FRANCHISE COMPANY E CONNECT 1" CONDUIT, SEE AQUATIC PLANS

- FD FOUNDATION DRAIN PGE STREET LIGHT CONDUIT, VERIFY ROUTING WITH PGE
- CONNECT TO WASTE LINE. SEE PLUMBING PLANS FOR CONTINUATION. SIZE AS NOTED.
- CONNECT TO STORM DRAIN/ROOF DRAIN. SEE SD PLUMBING PLANS FOR CONTINUATION. SIZE AND IE
- AS NOTED CONNECT TO COLD WATER SYSTEM. SEE
- W PLUMBING PLANS FOR CONTINUATION. SIZE AS
- UTILITY CROSSING. PROVIDE 12" MIN. CLEARANCE,
- MAINTENANCE EXISTING UTILITY PIPE AND CONFIRM FUNCTIONAL.

UTILITY LABEL LEGEND

STRUCTURE LABEL —— UTILITY TYPE (SD=STORM DRAINAGE, SS=SANITARY SEWER, W=WATER, FP=FIRE PROTECTION) STRUCTURE TYPE CALLOUT

ID NUMBER (WHERE APPLICABLE) IE IN = XX.XSTRUCTURE INFO (WHERE APPLICABLE)

PIPE LABEL — UTILITY LENGTH

UTILITY SIZE XXLF - XX" XX → UTILITY TYPE

S=X.XX% SLOPE (WHERE APPLICABLE)

STRUCTURE TYPE

CALLOUT	DESCRIPTION	DETAIL REF.
BWV	BACKWATER VALVE	
СВ	CATCH BASIN	4/C5.1
CO	CLEANOUT TO GRADE	6200-1
CG-2	CONCRETE INLET	RD366
DCBA	DOUBLE CHECK BACKFLOW ASSEMBLY	1/C5.2
DCVA	DOUBLE CHECK VALVE ASSEMBLY	5070-2
FC	FLOW-CONTROL VAULT	1/C5.1
FDC	FIRE DEPARTMENT CONNECTION	(SEE OTHERS)
FH	FIRE HYDRANT	5070-1
G-2	CONCRETE INLET	RD364
GV	GATE VALVE	5050-2
HB	HORIZONTAL BEND	
MH	MANHOLE	6510-3
OV	OVERFLOW INLET	3/C5.1
SCB	SANITARY CATCH BASIN	9/C5.1
STUB	STUB	
TD	TRENCH DRAIN	2/C5.1
TEE	TEE CONNECTION	
W	WATERLINE	
WM	WATER METER	6/C5.2

SHEET LEGEND

STORMWATER PLANTER/BASIN

MANHOLE **OVERFLOW INLET** BACKWATER VALVE CATCH BASIN

OUTFALL PIPE REMOVAL Status: PLANNING COMMISSION **DESIGN REVIEW** 10.28.2025

THESE DRAWINGS ARE THE PROPERTY OF OPSIS ARCHITECTURE LLP AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER,

Revisions to Sheet

Portland, OR 97204 O: 503.542.3860 F: 503.274.4681

www.kpff.com

www.opsisarch.com

Project Owner:

Project Name:

Project Adress: 190 Oak Street


Key Plan

Woodburn Community


Woodburn, OR 97071

City Of Woodburn Oregon

Sheet Title **UTILITY PLAN ENLARGEMENT 2**



C4.2



LANDSCAPE LIMIT OF WORK

TREE PROTECTION FENCE ******************* TEMPORARY ORANGE PLASITC TREE

PROTECTION FENCE

EXISTING TREE TO REMAIN



EXISTING TREE TO BE REMOVED

ABBREVIATIONS

ARCHITECTURAL CALIPER DIAMETER AT BREAST HEIGHT **EXISTING** FINISH SURFACE SQUARE FEET

TREE PROTECTION NOTES

- THIS PLAN IS BASED ON A SURVEY BY S&F LAND SERVICES, DATED 04/01/2020. NOTIFY OWNER'S REPRESENTATIVE OF ANY DISCREPANCIES IDENTIFIED ON SITE RELATED TO SURVEY INFORMATION PRIOR TO INSTALLATION.
- PRECONSTRUCTION CONFERENCE: THE PROJECT ARBORIST SHALL BE ON SITE TO VERIFY THE INSTALLATION OF TREE PROTECTION MEASURES AND DISCUSS METHODS OF TREE REMOVAL AND TREE PROTECTION PRIOR TO ANY CONSTRUCTION.
- TREE ROOT PROTECTION ZONE. THE ROOT PROTECTION ZONE (RPZ) IS DEFINED AS THE DRIPLINE OF PROTECTED TREES REGARDLESS OF THE LOCATION OF THE TREE PROTECTION FENCING
- 4-FOOT-TALL WELDED WIRE FENCING ON METAL STAKES. THE PROTECTION FENCING SHALL BE INSTALLED AS DEPICTED ON THE TREE PROTECTION PLAN AND SHALL NOT BE MOVED, REMOVED OR ENTERED BY EQUIPMENT WITHOUT PRIOR COORDINATION WITH THE PROJECT ARBORIST PROTECTION FENCING IS NOT NECESSARY WHERE TREES ARE LOCATED AT LEAST 30-FEET FROM ANY PROPOSED CONSTRUCTION ACTIVITY, INCLUDING BUT NOT LIMITED TO EQUIPMENT ACCESS, STAGING, STOCKPILING, GRADING, AND BUILDING.
- 5. EROSION CONTROL: SILT FENCING REQUIRED TO BE INSTALLED WITHIN THE RPZ SHALL NOT BE TRENCHED IN PER MANUFACTURER SPECIFICATIONS TO AVOID ROOT DAMAGE. INSTEAD, ROLL THE BASE OF THE SILT FENCE AROUND A STRAW WATTLE AND STAKE THE WATTLE SECURELY INTO THE GROUND OR USE OTHER METHODS THAT DO NOT REQUIRE TRENCHING.
- 6. TREE AND STUMP REMOVAL: TREES TO BE REMOVED SHALL BE CLEARLY IDENTIFIED WITH TREE-MARKING PAINT OR OTHER METHODS. TREE PROTECTION FENCING AT TREE #17 MAY BE TEMPORARILY OPENED FOR TREE #15 TO BE DIRECTIONALLY FELLED WITH A CHAINSAW AND HAULED OUTSIDE OF THE TREE PROTECTION ZONE. THE STUMP OF TREE #15 SHALL REMAIN IN THE GROUND; A STUMP GRINDER MAY BE USED TO GRIND THE STUMP FACE UP TO 6-INCHES BELOW GRADE. CLOSE THE PROTECTION FENCING ONCE REMOVAL OF TREE #15 IS COMPLETED.
- 7. PRUNING: PRUNING MAY BE NEEDED TO PROVIDE FOR OVERHEAD CLEARANCE AND TO REMOVE DEAD AND DEFECTIVE BRANCHES FOR SAFETY. THE PROJECT ARBORIST CAN HELP IDENTIFY WHERE PRUNING IS NECESSARY ONCE TREES RECOMMENDED FOR REMOVAL HAVE BEEN REMOVED AND THE SITE IS STAKED AND PREPARED FOR CONSTRUCTION. PRUNING SHALL BE PERFORMED BY AN EXPERIENCED, LICENSED, BONDED AND INSURED TREE SERVICE PROVIDER USING ISA BEST MANAGEMENT PRACTICES FOR PRUNING AND ANSI A300 PRUNING STANDARDS.
- 8. DEMOLITION AND ADDITIONAL PROTECTION FENCING: REMOVAL OF THE EXISTING ASPHALT PARKING LOT ADJACENT TO TREES #17 AND #18 SHALL PROCEED WITH CAUTION TO MINIMIZE DAMAGE TO EXPANSIVE SURFACE ROOTS BENEATH THE ASPHALT. AS INDICATED ON SITE PLAN DRAWINGS, 4-FOOT-HIGH ORANGE PLASTIC FENCING ON METAL STAKES SHALL BE TEMPORARILY INSTALLED WITHIN THE LARGER AREA OF METAL TREE PROTECTION FENCING DURING REMOVAL OF THE EXISTING CONCRETE SIDEWALK AND STAIRS BETWEEN TREES #17 AND #18 IN ORDER TO PROVIDE A PHYSICAL BARRIER WHERE WORK WILL OCCUR IN CLOSE PROXIMITY TO TREES WITHIN THE RPZ SPOILS SHALL BE HAULED OUTSIDE OF THE RPZ IMMEDIATELY (NO TEMPORARY STOCKPILES). IF TREE ROOTS ARE REVEALED DURING THIS WORK, CONTACT THE PROJECT ARBORIST FOR ADDITIONAL RECOMMENDATIONS. TREE PROTECTION FENCING MAY BE TEMPORARILY OPENED IN THE NORTHWEST QUADRANT AT TREE #19 TO REMOVE THE EXISTING GUY WIRE; CLOSE THE PROTECTION FENCING ONCE THIS WORK IS COMPLETED.
- 9. DEVELOPMENT LIMITATIONS: THE FOLLOWING IS NOT ALLOWED WITHIN THE RPZ UNLESS OTHERWISE DEPICTED ON THE TREE PROTECTION PLAN AND IN COORDINATION WITH THE PROJECT ARBORIST IN ADVANCE OF WORK ADJACENT TO TREES #17 AND #18:

•GROUND DISTURBANCE OR CONSTRUCTION ACTIVITY INCLUDING VEHICLE AND EQUIPMENT ACCESS OR MANEUVERING;

•STAGING OR STORAGE OF MATERIALS AND EQUIPMENT, INCLUDING SOIL AND TEMPORARY OR PERMANENT STOCKPILING; NEW BUILDINGS;

•GRADE CHANGE OF CUT AND FILL DURING OR AFTER CONSTRUCTION; •NEW IMPERVIOUS SURFACES;

•UTILITY OR DRAINAGE FIELD PLACEMENT; OR • TRENCHING.

- 9. EXCAVATION AND ROOT PRUNING: EXCAVATION SHALL BE AVOIDED WITHIN THE RPZ IF ALTERNATIVES ARE AVAILABLE. THE PROJECT ARBORIST SHALL PROVIDE ON-SITE CONSULTATION DURING EXCAVATION ACTIVITIES WITHIN THE RPZ OF PROTECTED TREES. WHERE NEEDED, ROOTS SMALLER THAN 2-INCHES IN DIAMETER SHOULD BE PRUNED CLEAN TO SOUND WOOD (NO JAGGED EDGES) USING A SHARP SAW AS DIGGING PROGRESSES TO AVOID PULLING AND TEARING ROOTS. PRUNE ROOTS PERPENDICULAR TO THE NATURAL GROWTH DIRECTION WITH BARK FIRMLY ATTACHED AROUND THE ENTIRE ROOT CIRCUMFERENCE. EXCAVATION IMMEDIATELY ADJACENT TO ROOTS 2-INCHES IN DIAMETER AND LARGER WITHIN THE RPZ SHALL BE BY HAND OR OTHER NON-INVASIVE TECHNIQUES TO ENSURE THAT ROOTS ARE NOT DAMAGED; AIR-SPADING OR HYDRO-VACUUM EXCAVATION MAY BE NEEDED. THE PROJECT ARBORIST SHOULD ASSESS AND DOCUMENT ROOTS 2-INCHES AND LARGER IN DIAMETER PRIOR TO IMPACTS. WHERE FEASIBLE, THESE ROOTS SHALL BE PROTECTED BY TUNNELING OR OTHER MEANS TO AVOID DESTRUCTION OR UNACCEPTABLE DAMAGE WILL NOT OCCUR TO THE TREE. IF UNACCEPTABLE DAMAGE IS UNAVOIDABLE, WORK SHALL NOT PROCEED ADJACENT TO THE TREE UNTIL THE CITY AUTHORIZES TREE REMOVAL.
- 10. LANDSCAPING: FOLLOWING CONSTRUCTION AND WHERE LANDSCAPING IS DESIRED, APPLY APPROXIMATELY 3-INCHES OF BARK MULCH OR ARBORIST CHIP MULCH BENEATH THE DRIPLINE OF PROTECTED TREES BUT NOT DIRECTLY AGAINST TREE TRUNKS. SHRUBS AND GROUND COVERS MAY BE PLANTED BY HAND WITHIN RPZS, BUT PLANTS SHALL BE ADJUSTED TO AVOID TREE ROOT IMPACTS. HAND-WATER OR USE DRIP IRRIGATION INSTALLED ABOVE GROUND LEVEL ONLY BENEATH THE DRIPLINES OF PROTECTED TREES AND MONITOR IRRIGATION REGULARLY TO AVOID SATURATION WITHIN THE RPZ.

lango.hansen

LANDSCAPE ARCHITECTS

Opsis Architecture LLP 975 SE Main St, Portland, OR 97214

503.525.9511 | info@opsisarch.com

1100 nw glisan #3k portland or 9720

NOT FOR CONSTRUCTION

Project Owner: City Of Woodburn Oregon

Woodburn Community

Center

Project

Adress: 190 Oak Street Woodburn, OR 97071


THESE DRAWINGS ARE THE PROPERTY OF OPSIS ARCHITECTURE LLP AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER, WITHOUT PRIOR WRITTEN PERMISSION. Revisions to Sheet

Status: Planning Commission

Design Review 10.28.2025

Sheet Title TREE PROTECTION **PLAN**

Sheet No. L001



PARKING NOTES

- BICYCLE PARKING: 18 TOTAL SHORT—TERM STALLS PROVIDED, 8 STALLS WITHIN 50' OF MAIN ENTRANCE
- 2. CARPOOL/VANPOOL PARKING: 0 C/V STALLS PROVIDED
- 3. ELECTRIC VEHICLE PARKING: 4 TOTAL EV STALLS PROVIDED INCLUDING 1 EV STALL FOR ADA PARKING STALL
- 4. OFF-STREET VEHICLE PARKING: 97 TOTAL STALLS, 12 ADA STALLS

LEGEND

LANDSCAPE LIMIT OF WORK

---- PROPERTY LINE/RIGHT-OF-WAY

VEHICULAR CONCRETE PAVING, TYPE 1

VEHICULAR CONCRETE PAVING, TYPE 2

VEHICULAR ASPHALT PAVING

PEDESTRIAN CONCRETE PAVEMENT,
TYPE 1

PEDESTRIAN CONCRETE PAVEMENT,
TYPE 2

UNIT PAVERS SAND SET

ONIT PAVENS SAND SET

MEXICAN BEACH PEBBLES

BENCH
CONCRETE CURB

BIKE RACK
CITY STREET LIGHT POLE

→ PARKING LOT LIGHT POLE⊕ BOLLARD LIGHT

■ ELECTRIC VEHICLE CHARGER

• REMOVABLE BOLLARD

EXISTING TREE TO REMAIN

NOT FOR CONSTRUCTION

OPSIS

lango.hansen

LANDSCAPE ARCHITECTS

1100 nw glisan #3b portland or 97209

Opsis Architecture LLP 975 SE Main St, Portland, OR 97214

503.525.9511 | info@opsisarch.com

opsisarch.com

Project Owner:
City Of Woodburn Oregon

Project Name:
Woodburn Community

Center
Project
Adress:

190 Oak Street
Woodburn, OR 97071

Key Plan

ABBREVIATIONS

ARCHITECTURAL CONCRETE CONC DWG **DRAWINGS** ELECTRICAL ELEC MECHANICAL MECH NOT IN CONTRACT PLANTING AREA SEEDED LAWN SIM SIMILAR SPECS SPECIFICATIONS STORMWATER PLANTING AREA STRUC STRUCTURAL TYP TYPICAL

MATERIALS NOTES

WITH

- 1. THIS PLAN IS BASED ON A SURVEY BY S&F LAND SERVICES DATED 09/24/2020. NOTIFY OWNER'S REPRESENTATIVE OF ANY DISCREPANCIES IDENTIFIED ON SITE RELATED TO SURVEY INFORMATION PRIOR TO INSTALLATION.
- PROTECT EXISTING VEGETATION TO REMAIN. SEE SPECIFICATION SECTION 015639 FOR FENCING AND OTHER REQUIREMENTS.
- 3. SEE CIVIL DRAWINGS FOR LOCATION OF UTILITIES.

PAVEMENT IN THE RIGHT-OF-WAY.

- 4. SEE CIVIL DRAWINGS FOR EARTHWORK CALCULATIONS.
- 5. VEHICULAR PAVEMENT AND PAVEMENT IN THE RIGHT-OF-WAY SHOWN FOR REFERENCE ONLY. SEE CIVIL DRAWINGS FOR ALL VEHICULAR PAVEMENT, VEHICULAR CURBS, GUTTERS, AND

copyright 2018

No. Revision

THESE DRAWINGS ARE THE PROPERTY OF OPSIS ARCHITECTURE LLP AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER, WITHOUT PRIOR WRITTEN PERMISSION.

Revisions to Sheet

Status: Planning Commission
Design Review


10.28.2025

Sheet Title

MATERIALS PLAN

OVERALL

Sheet No.



LANDSCAPE LIMIT OF WORK --- PROPERTY LINE/RIGHT-OF-WAY VEHICULAR CONCRETE PAVING, TYPE 1 VEHICULAR CONCRETE PAVING, TYPE 2 VEHICULAR ASPHALT PAVING PEDESTRIAN CONCRETE PAVEMENT,

UNIT PAVERS SAND SET

PEDESTRIAN CONCRETE PAVEMENT, TYPE 2

MEXICAN BEACH PEBBLES

—— CONCRETE CURB

BIKE RACK

CITY STREET LIGHT POLE PARKING LOT LIGHT POLE BOLLARD LIGHT

TYPE 1

ELECTRIC VEHICLE CHARGER REMOVABLE BOLLARD



EXISTING TREE TO REMAIN

OPSIS

lango.hansen

LANDSCAPE ARCHITECTS 1100 nw glisan #3b portland or 97209

Opsis Architecture LLP 975 SE Main St, Portland, OR 97214 503.525.9511 | info@opsisarch.com opsisarch.com

NOT FOR CONSTRUCTION

Project Owner: City Of Woodburn Oregon

Woodburn Community

Adress: 190 Oak Street Woodburn, OR 97071 Key Plan

NOTES

1. SEE L101 FOR GENERAL NOTES AND ABBREVIATIONS.


THESE DRAWINGS ARE THE PROPERTY OF OPSIS ARCHITECTURE LLP AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER, WITHOUT PRIOR WRITTEN PERMISSION. Revisions to Sheet No. Revision

Status: Planning Commission
Design Review

10.28.2025

Sheet Title **MATERIALS PLAN ENLARGEMENT**

L102



LANDSCAPE LIMIT OF WORK --- PROPERTY LINE/RIGHT-OF-WAY

CENTERLINE

PEDESTRIAN CONCRETE PAVEMENT EXPANSION JOINT TOOLED CONTROL JOINT

———— CONCRETE CURB BIKE RACK

CITY STREET LIGHT POLE

PARKING LOT LIGHT POLE

BOLLARD LIGHT ELECTRIC VEHICLE CHARGER

REMOVABLE BOLLARD EXISTING TREE TO REMAIN

ABBREVIATIONS

BACK OF CURB CONTROL JOINT

DIAMETER EXPANSION JOINT

EQUAL EACH WAY FACE OF CURB

NUMBER ON CENTER

POINT OF TANGENCY RADIUS

SPACES TYP TYPICAL

EASTING NORTHING

LAYOUT NOTES

- 1. THIS PLAN IS BASED ON A SURVEY BY S&F LAND SERVICES DATED 09/24/2020. NOTIFY OWNER'S REPRESENTATIVE OF ANY DISCREPANCIES IDENTIFIED ON SITE RELATED TO SURVEY INFORMATION PRIOR TO INSTALLATION.
- 2. PROTECT EXISTING VEGETATION TO REMAIN; SEE SPECIFICATION SECTION 015639 FOR FENCING AND OTHER REQUIREMENTS.
- 3. SEE CIVIL DRAWING FOR LOCATION OF UTILITIES. 4. FOR DIMENSIONS WHERE INCHES ARE NOT GIVEN,
- ASSUME 0 INCHES, SUCH THAT 2' EQUALS 2'-0" 5. PAVING DIMENSIONS ARE TO FACE BUILDING, FACE
- OF CURB, OR FACE OF WALL, UNLESS OTHERWISE 6. IF THERE IS A CONFLICT WITH LAYOUT IN THE FIELD,
- NOTIFY THE OWNER'S REPRESENTATIVE PRIOR TO INSTALLATION. 7. INSTALL EXPANSION JOINTS AND SEALANT WHERE
- CONCRETE PAVING ABUTS STRUCTURES SUCH AS SITE WALLS, BUILDING EDGES, CONCRETE HEADERS, COLUMNS, FENCING STRUCTURES, AND FREE STANDING STRUCTURES, TYP. 8. SEE CIVIL DRAWINGS FOR ALL VEHICULAR AREA
- IMPROVEMENTS, INCLUDING PAVING, CURBS, DRIVEWAY APRONS, STRIPING AND SIGNAGE, AS WELL AS ANY VEHICULAR AND PEDESTRIAN PAVING IMPROVEMENTS WITHIN THE RIGHT-OF-WAY.
- 9. ALL SITEWALL DIMENSIONS ARE TO BUILDING GRIDLINES, UNLESS OTHERWISE NOTED. VERIFY THAT ALL BUILDING GRIDLINE DIMENSIONS ARE STAKED ACCURATELY IN THE FIELD PRIOR TO INSTALLATION OF SITEWALLS. REFER TO STRUCTURAL DRAWINGS FOR DIMENSIONS BETWEEN ARCHITECTURAL GRIDLINES. SITEWALLS INCLUDE CAST-IN-PLACE RETAINING WALLS AND CHEEKWALLS.
- 10. DIMENSIONS TO JOINT LINES ARE TO CENTERLINES
- 11. DIMENSIONS TO AREA DRAINS ARE TO CENTER POINTS, TYP.
- 12. DIMENSIONS TO HANDRAILS ARE TO CENTERLINES,
- 13. DIMENSIONS TO LIGHTPOSTS ARE TO CENTERLINES,
- 14. SEE CIVIL DRAWINGS FOR LOCATIONS OF MANHOLES. 15. SEE ELECTRICAL DRAWINGS FOR ADDITIONAL INFORMATION RELATING TO LIGHTING, TRANSFORMER,
- 16. NORTHING/EASTING POINTS FOR LIGHTS ARE TO CENTER OF POLE.

AND PEDESTALS.

- 17. COORDINATES ARE GIVEN AT ____ INTERVALS ALONG PATH. INSTALL PATH SO THAT EDGE CONDITION CURVES ARE SMOOTH WITH NO KINKS.
- 18. NORTHEASTING COORDINATES ARE BASED ON BENCHMARK INFORMATION AS GIVEN ON SURVEY. (OR THE INTERSECTION OF 2 BUILDING GRIDLINES, ESTABLISHED AS 0,0)

OPSIS

lango.hansen

LANDSCAPE ARCHITECTS 1100 nw glisan #3b portland or 97209

Opsis Architecture LLP 975 SE Main St, Portland, OR 97214 503.525.9511 | info@opsisarch.com opsisarch.com

NOT FOR CONSTRUCTION

Project Owner: City Of Woodburn Oregon

Project Name: **Woodburn Community**

Project Adress:

190 Oak Street Woodburn, OR 97071

Key Plan

No. Revision


THESE DRAWINGS ARE THE PROPERTY OF OPSIS ARCHITECTURE LLP AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER, WITHOUT PRIOR WRITTEN PERMISSION. Revisions to Sheet

Design Review 10.28.2025

Sheet Title LAYOUT PLAN **OVERALL**

Status: Planning Commission

Sheet No. L201



LANDSCAPE LIMIT OF WORK --- PROPERTY LINE/RIGHT-OF-WAY CENTERLINE

PEDESTRIAN CONCRETE PAVEMENT EXPANSION JOINT TOOLED CONTROL JOINT ----- CONCRETE CURB

BIKE RACK

CITY STREET LIGHT POLE PARKING LOT LIGHT POLE BOLLARD LIGHT

ELECTRIC VEHICLE CHARGER REMOVABLE BOLLARD

EXISTING TREE TO REMAIN

opsis

lango.hansen LANDSCAPE ARCHITECTS

1100 nw glisan #3b portland or 97209

Opsis Architecture LLP 975 SE Main St, Portland, OR 97214 503.525.9511 | info@opsisarch.com opsisarch.com

NOT FOR CONSTRUCTION

Project Owner: City Of Woodburn Oregon

Woodburn Community

Project Adress: 190 Oak Street Woodburn, OR 97071 Key Plan

NOTES

SEE L201 FOR GENERAL NOTES AND ABBREVIATIONS.

THESE DRAWINGS ARE THE PROPERTY OF OPSIS ARCHITECTURE LLP AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER, WITHOUT PRIOR WRITTEN PERMISSION. Revisions to Sheet


Status: Planning Commission
Design Review

10.28.2025

Sheet Title

LAYOUT PLAN **ENLARGEMENT**

L202



LANDSCAPE LIMIT OF WORK


LAWN

CONCRETE CURB

BIKE RACK CITY STREET LIGHT POLE

PARKING LOT LIGHT POLE

BOLLARD LIGHT ELECTRIC VEHICLE CHARGER



EXISTING TREE TO REMAIN

REMOVABLE BOLLARD

ABBREVIATIONS

BALLED & BURLAPPED

CALIPER CONTAINER

DIAMETER DIAMETER AT BREAST HEIGHT

NUMBER ON CENTER

SEEDED LAWN SPECS SPECIFICATIONS

TYP TYPICAL CONTAINER SIZE

PLANTING NOTES

1. THIS PLAN IS BASED ON A SURVEY BY S&F LAND SERVICES DATED 09/24/2020. NOTIFY OWNER'S TO INSTALLATION.

PROTECT EXISTING VEGETATION TO REMAIN; SEE SPECIFICATION SECTION 015639 FOR FENCING AND

3. ALL PLANT MATERIAL SHALL BE NURSERY GROWN, WELL ROOTED, AND WELL BRANCHED. ALL TREES MUST BE FREE OF INSECTS, DISEASES, MECHANICAL INJURY, AND OTHER OBJECTIONABLE FEATURES WHEN PLANTED. ALL PLANT MATERIAL SHALL CONFORM TO

VALVE BOX LOCATIONS. INSTALLED VALVE BOXES THAT CONFLICT WITH ACCEPTED PLANT LAYOUT

WATERED AS NECESSARY TO MINIMIZE STRESS TO THE TREE, PROMOTE ROOT GROWTH, AND ENSURE SURVIVAL, THROUGHOUT THE CONSTRUCTION PERIOD AND THE FIRST THREE GROWING SEASONS AFTER PLANTING. TREES SHALL BE MULCHED WITH COMPOST MULCH, SEE SPECIFICATIONS. PROTECTIVE BARRIERS SHALL STAY IN PLACE UNTIL PLANNING OFFICIAL AUTHORIZES THEIR REMOVAL OR A FINAL CERTIFICATE OF OCCUPANCY IS ISSUED, WHICHEVER OCCURS FIRST. STAKING & FERTILIZING SHALL BE REQUIRED WHERE DEEMED NECESSARY BY PLANNING

REPAIR AND RESEED ALL LAWN AREAS DISTURBED BY CONSTRUCTION ACTIVITY, INCLUDING SOIL PREPARATION. SEE 329100 AND 329300.

10. ALL LANDSCAPE AREAS THAT HAVE A SLOPE GREATER THAN 1 VERTICAL FOOT IN 3 HORIZONTAL FEET SHALL RECEIVE JUTE MATTING, SEE SPECIFICATIONS.

11. ALL PLANTING AREAS ARE TO BE IRRIGATED WITH A PERMANENT AUTOMATIC IRRIGATION SYSTEM.

13. MULCH RINGS TO BE INSTALLED AT ALL EXISTING TREES. TWO (2) INCHES OF MULCH TO BE INSTALLED. SÈE PLAN FOR DIAMETER OF MULCH

1100 nw glisan #3k portland or 9720

lango.hansen

LANDSCAPE ARCHITECTS

OPSIS

Opsis Architecture LLP 975 SE Main St, Portland, OR 97214 503.525.9511 | info@opsisarch.com

NOT FOR CONSTRUCTION

Project Owner: City Of Woodburn Oregon

Woodburn Community

Project Adress:

190 Oak Street Woodburn, OR 97071 Key Plan

REPRESENTATIVE OF ANY DISCREPANCIES IDENTIFIED ON SITE RELATED TO SURVEY INFORMATION PRIOR

OTHER REQUIREMENTS.

"AMERICAN STOCK STANDARDS" LATEST EDITION.

4. ALL PLANT MATERIAL TO BE APPROVED BY LANDSCAPE ARCHITECT PRIOR TO INSTALLATION. SEE SPECIFICATIONS.

PLANT SPACING SHALL TAKE PRECEDENCE OVER SHALL BE MOVED TO POSITION BETWEEN PLANTS.

PLANT COUNTS FOR TREES AND SHRUBS ARE SUPPLIED FOR THE CONTRACTOR'S CONVENIENCE CONTRACTOR RESPONSIBLE FOR INSTALLING ALL PLANTS IN LOCATIONS AND QUANTITIES SHOWN. FOR GROUNDCOVER PLANTING, SEE DETAIL 01/L503.

CLEAR PLANT BEDS OF ALL GRAVEL AND DEBRIS PRIOR TO SOIL PREPARATION AND PLANTING, FOR APPROVAL BY LANDSCAPE ARCHITECT.

TREES TO BE RETAINED AND/OR PLANTED SHALL BE OFFICIAL.

12. ALL PARKING LOT AND STREET TREES MUST HAVE 6' CLEAR HEIGHT TO LOWEST BRANCHES.

RINGS.

Status: Planning Commission **Design Review** 10.28.2025

THESE DRAWINGS ARE THE PROPERTY OF OPSIS ARCHITECTURE LLP AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER

Revisions to Sheet

Sheet Title **PLANTING PLAN**

Sheet No.

4773-06

L301

(5)			
CLEVELAND STRE	ET	SPRAY HEADS — MP ROTATOR NOZZLES	SPRAY HEADS — HUNTER PRO ADJUSTABLE
		Sym Spray Head Nozzle Arc GPM Rad ⊕ ⊕ ⊗ HUNTER PRO-SPRAY PRS40 MP800sr 90-210 210°-270° .1623 8'-	
		⊕ HUNTER PRO-SPRAY PRS40 MP800sr 360 360° .5678 8'- ⊕ HUNTER PRO-SPRAY PRS40 MP CORNER 45°-105° .1945 11'-	10'
		⊕ ⊕	-14'
			-14' HUNTER PROSPRAY PRS30 PRO-ADJUST 10A
		➡ ➡ HUNTER PRO-SPRAY PRS40 MP2000 90-210 90°-210° .4386 15'- ➡ ➡ HUNTER PRO-SPRAY PRS40 MP2000 210-270 210°-270° .86-1.10 15'-	-20' HUNTER PROSPRAY PRS30 PRO-ADJUST 12A
WORK ORK		O HUNTER PRO−SPRAY PRS40 MP2000 360 360° 1.48 15'− O O HUNTER PRO−SPRAY PRS40 MP3000 90−210 90°−210° .86−2.12 23'−	-30' HUNTER PROSPRAY PRS30 PRO-ADJUST 15A
MIT OF		→ HUNTER PRO−SPRAY PRS40 MP3000 210−270 210°−270° 2.12−2.73 23′− → HUNTER PRO−SPRAY PRS40 MP3000 360 360° 3.64 23′−	-30'
A PE		→ ← HUNTER PRO-SPRAY PRS40 MP3500 90-210 210° 2.12 31'- ■ HUNTER PRO-SPRAY PRS40 MPSS530 .44 5'x;	30'
L'ANDSC		■ HUNTER PR0-SPRAY PRS40 MPLCS515 .22 5'x' ■ HUNTER PR0-SPRAY PRS40 MPRCS515 .22 5'x'	15'
			<u>/A</u>
WEET.			
	J. J		
	RST &		
DRIP IRRIGATION, TYP			
SPRAYHEAD—IRRIGATION, TYP			
SEC			
		<u></u>	
OAK STREET			
OAR SIREE!		SEE NOTE 16	ROOT WATERING SYSTEM, 2 PER TREE, TYP
			7
SPRAYHEAD IRRIGATION, TYP			
IRRIGATION, TYP			
ROOT WATERING SYSTEM, 2 PER TREE, TYP			
		SEE NOTE 16	
		SEE HOTE TO	
		SPRAYHEAD IRRIGATION, TYP	
RELOCATE EXISTING	LANDSCAPE LIMIT OF WORK		
RELOCATE EXISTING IRRIGATION VALVES		DRIP IRRIGATION, TYP	
		ROOT WATERING— SYSTEM, 2 PER TREE, TYP	
1 IRRIGATION PLAN	\times \downarrow	TREE, TYP Plan	
		SCALE: 1"=20' 0 10 20 40	

PRO ADJUSTABLE NOZZLES

45°-360° | .58-4.60 | 17'

Sym	Spray Head	Nozzle	Arc	GPM	Radius
\$ \$	HUNTER PROSPRAY PRS30	PRO-ADJUST 4A	45°-360°	.1380	4'
	HUNTER PROSPRAY PRS30	PRO-ADJUST 6A	45°-360°	.18-1.26	6'
₽₽₽	HUNTER PROSPRAY PRS30	PRO-ADJUST 8A	45°-360°	.22-1.76	8'
	HUNTER PROSPRAY PRS30	PRO-ADJUST 10A	45°-360°	.25-2.00	10'
	HUNTER PROSPRAY PRS30	PRO-ADJUST 12A	45°-360°	.32-2.52	12'
*	HUNTER PROSPRAY PRS30	PRO-ADJUST 15A	45°-360°	.47-3.72	15'

LEGEND

LANDSCAPE LIMIT OF WORK DRIP IRRIGATION

SPRAYHEAD IRRIGATION TEMPORARY IRRIGATION

———— CONCRETE CURB BIKE RACK

CITY STREET LIGHT POLE PARKING LOT LIGHT POLE

BOLLARD LIGHT ELECTRIC VEHICLE CHARGER REMOVABLE BOLLARD

PROPOSED TREE, 3" CALIPER

EXISTING TREE TO REMAIN

ABBREVIATIONS

BALLED & BURLAPPED CALIPER

B&B CAL CONT CONTAINER

DIAMETER DIAMETER AT BREAST HEIGHT

EQUAL

HEIGHT MINIMUM MIN

MAXIMUM NUMBER ON CENTER

SIMILAR SEEDED LAWN SPECS SPECIFICATIONS

TYPICAL

TYP CONTAINER SIZE

IRRIGATION NOTES

- 1. THIS PLAN IS BASED ON A SURVEY S&F LAND SERVICES DATED 09/24/2020. NOTIFY ARCHITECT OF ANY DISCREPANCIES IDENTIFIED ON SITE RELATED TO SURVEY INFORMATION PRIOR TO INSTALLATION.
- 2. INSTALL IRRIGATION SYSTEM IN ACCORDANCE WITH ALL LOCAL CODES AND ORDINANCES.
- 3. PRIOR TO COMMENCEMENT OF ANY IRRIGATION WORK, VERIFY MINIMUM FLOW RATE OF __GPM AND MINIMUM DYNAMIC (WORKING) PRESSURE OF __PSI WHEN FLOWING AT `__(MIN FLOW RATE)__ AT THE POINT OF CONNECTION.
- 4. ALL TRENCHING WITHIN ROOT PROTECTION ZONES SHALL COMPLY WITH THE REQUIREMENTS SPECIFIED IN THE TREE PROTECTION PLANS AND SECTION 015639.
- 5. COORDINATE ALL IRRIGATION WORK WITH OTHER TRADES AS REQUIRED, INCLUDING POINT(S)-OF-CONNECTION AND CONTROLLER INSTALLATION.
- 6. IRRIGATION PLANS ARE DIAGRAMMATIC. ALL VALVES AND IRRIGATION HEADS SHALL BE LOCATED IN PLANTED AREAS. FIELD ADJUST LINES TO AVOID CONFLICTS WITH STRUCTURES AND UTILITIES.
- 7. ALL PIPES AND EQUIPMENT SHOWN IN PAVED AREAS IS FOR GRAPHIC CLARITY ONLY. ALL PIPES AND EQUIPMENT SHALL BE IN PLANTING AREAS UNLESS OTHERWISE NOTED.
- 8. PROVIDE SLEEVES UNDER ALL PAVED AREAS FOR IRRIGATION MAINLINE AND LATERALS.
- 9. ALL VALVES (EXCEPT FOR MANUAL DRAIN VALVES ON DRIP ZONES) AND THE MAINLINE MUST BE LOCATED WITHIN PROPERTY LINE.
- 10. COORDINATE IRRIGATION POINTS OF CONNECTION AND LOCATION OF REMOTE CONTROL VALVE ASSEMBLIES AND SLEEVES. COORDINATE ALL WORK WITH OTHER TRADES INVOLVED.
- 11. PLACE ALL VALVES IN VALVE BOXES AND IN A MANNER THAT FACILITATES ACCESS FOR MAINTENANCE. SIZE BOXES TO ACCOMMODATE COMPLETE VALVE ASSEMBLY. MAINTAIN MIN. 12" BETWEEN VALVE BOXES AND PAVEMENT.
- 12. IRRIGATION LATERALS ARE SIZED STARTING AT VALVE AND CONTINUING IN DIRECTION OF FLOW. REDUCTIONS IN PIPE SIZE ARE LABELED BEGINNING DOWNSTREAM OF NEAREST FITTING. ALL LATERALS NOT SIZED ARE MINIMUM 3/4" OR SAME SIZE AS NEAREST ADJACENT PIPE.
- 13. CONTRACTOR TO MARK LAYOUT OF TRENCHES AND VALVE LOCATIONS FOR PREVIEW BY OWNER IN FIELD PRIOR TO CONSTRUCTION.
- 14. INSTALL AND ADJUST ALL COMPONENTS OF IRRIGATION SYSTEM TO PROVIDE 100% COVERAGE OF ALL PLANTING AREAS AND MINIMIZE OVERSPRAY ONTO BUILDINGS AND PAVING AREAS. CONTRACTOR IS RESPONSIBLE FOR PROVIDING A COMPLETE WORKING SYSTEM.
- 15. PROVIDE 12" POP-UP SPRINKLER BODIES FOR ALL SHRUB AND GROUNDCOVER BEDS, AND 6" SPRINKLER BODIES FOR LAWN AREAS AND SHRUB BEDS IMMEDIATELY ADJACENT TO PARKING AREAS.
- 16. TEMPORARY IRRIGATION HEADS TO BE ADJUSTED SUCH THAT SPRAY DOES NOT CONTACT THE TRUNKS OF EXISTING TREES.

lango.hansen LANDSCAPE ARCHITECTS

1100 nw glisan #3b portland or 97209

Opsis Architecture LLP 975 SE Main St, Portland, OR 97214 503.525.9511 | info@opsisarch.com opsisarch.com

NOT FOR CONSTRUCTION

Project Owner: City Of Woodburn Oregon

Project Name:

Woodburn Community Center

Project Adress: 190 Oak Street Woodburn, OR 97071

Key Plan

copyright 2018

No. Revision


THESE DRAWINGS ARE THE PROPERTY OF OPSIS ARCHITECTURE LLP AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER, WITHOUT PRIOR WRITTEN PERMISSION. Revisions to Sheet

Status: Planning Commission

Design Review 10.28.2025

Sheet Title **IRRIGATION PLAN**

Sheet No. L401



SITE PLAN SHEET NOTES

1. NEW WOODBURN COMMUNITY CENTER LEVEL 01

2. CIVIL AND LANDSCAPE ARE SHOWN FOR REFERENCE ONLY. SEE CIVIL AND LANDSCAPE DRAWINGS FOR ADDITIONAL INFORMATION.

3. REFERENCE ELECTRICAL FOR SITE LIGHTING AND

Opsis Architecture LLP 975 SE Main St, Portland, OR 97214 503.525.9511 | info@opsisarch.com opsisarch.com

Project Owner: City Of Woodburn Oregon

Project Name: **Woodburn Community** Center

Project Adress: 190 Oak Street Woodburn, OR 97071


Key Plan

THESE DRAWINGS ARE THE PROPERTY OF OPSIS ARCHITECTURE LLP AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER, WITHOUT PRIOR WRITTEN PERMISSION. Revisions to Sheet No. Revision

Status: PLANNING COMMISSION DESIGN REVIEW


10.28.2025

Sheet Title ARCHITECTURAL SITE PLAN



opsis


THESE DRAWINGS ARE THE PROPERTY OF OPSIS ARCHITECTURE LLP AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER, WITHOUT PRIOR WRITTEN PERMISSION.



EXTERIOR ELEVATIONS SHEET NOTES

- REFERENCE LEGEND FOR EXTERIOR MATERIALS
 REFERENCE A4.00 FOR EXTERIOR FRAME TYPES
 REFERENCE LANDSCAPE FOR GRADING.
 ALL REVEAL JOINTS DIMENSIONED TO CENTERLINE OF
- **REVEAL UON** 5. REFERENCE A0.40 FOR EXTERIOR WALL ASSEMBLIES.
- REFERENCE A0.60 FOR ROOF ASSEMBLIES. 6. ALL EXPOSED EXTERIOR SEALANT AT CMU TO BE
- SANDED AND SET AT SIMILAR DEPTH TO MORTAR. 7. ALL CMU TO RECEIVE GRAFITTI RESISTANT SEALER.

Opsis Architecture LLP 975 SE Main St, Portland, OR 97214 503.525.9511 | info@opsisarch.com opsisarch.com



1 NORTH ELEVATION
1/8" = 1'-0"

2 | WEST ELEVATION | 1/8" = 1'-0"

EE.1 PREP AND PAINT EXISTING METAL ROOF ASSEMBLY, TYP. REPAIR WHERE REQUIRED PREP AND PAINT EXISTING METAL PANEL FASCIA, TYP. REPAIR WHERE REQUIRED PREP AND PAINT EXISTING CMU TYP-REPAIR WHERE REQUIRED — ROOFTOP AC UNIT, SEE MECH FOR SCREENING, TYP NEW PAD MOUNTED TRANSFORMER EXISTING HVAC UNIT -TO REMAIN NEW GENERATOR

Status: PLANNING COMMISSION DESIGN REVIEW

THESE DRAWINGS ARE THE PROPERTY OF OPSIS ARCHITECTURE LLP AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER, WITHOUT PRIOR WRITTEN PERMISSION.

Revisions to Sheet

No. Revision

10.28.2025

Sheet Title

EXTERIOR


ELEVATIONS

A2.10


EXTERIOR ELEVATIONS SHEET NOTES

- REFERENCE LEGEND FOR EXTERIOR MATERIALS REFERENCE A4.00 FOR EXTERIOR FRAME TYPES
- REFERENCE LANDSCAPE FOR GRADING. 4. ALL REVEAL JOINTS DIMENSIONED TO CENTERLINE OF
- **REVEAL UON**
- REFERENCE A0.40 FOR EXTERIOR WALL ASSEMBLIES. REFERENCE A0.60 FOR ROOF ASSEMBLIES. 6. ALL EXPOSED EXTERIOR SEALANT AT CMU TO BE
- SANDED AND SET AT SIMILAR DEPTH TO MORTAR. 7. ALL CMU TO RECEIVE GRAFITTI RESISTANT SEALER.

Opsis Architecture LLP 975 SE Main St, Portland, OR 97214 503.525.9511 | info@opsisarch.com opsisarch.com



1 | SOUTH ELEVATION | 1/8" = 1'-0"



2 | EAST ELEVATION | 1/8" = 1'-0"

4773-06

A2.11

10.28.2025

Opsis Architecture LLP 975 SE Main St, Portland, OR 97214 503.525.9511 | info@opsisarch.com opsisarch.com

NOT FOR CONSTRUCTION

Project Owner: City Of Woodburn Oregon

Project Name: **Woodburn Community** Center


Project Adress: 190 Oak Street Woodburn, OR 97071


Key Plan

CMU-X —


1 WEST - TRASH ENCLOSURE
1/4" = 1'-0"

2 NORTH - TRASH ENCLOSURE









5 | FLOOR PLAN - TRASH ENCLOSURE | 1/4" = 1'-0"

THESE DRAWINGS ARE THE PROPERTY OF OPSIS ARCHITECTURE LLP AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER, WITHOUT PRIOR WRITTEN PERMISSION. Revisions to Sheet

Status: PLANNING COMMISSION DESIGN REVIEW

10.28.2025

Date: 10.2

Sheet Title

ENLARGED

PLAN AND

ELEVATIONS
TRASH

ENCLOSURE

Sheet No. A4.40

Job No. 4773-06

						LUM	INAIRE S	CHED	ULF						
									INITIAL						
						UL/IP	DRIVER/POWER	DIMMING	DELIVERED		RATED	l II	IPUT		
ГҮРЕ	DESCRIPTION	HOUSING	OPTICS	MOUNTING	FINISH	RATING	SUPPLY	CONTROL		CCT CRI	LIFE			VOLTAGE	MFG/CATALOG # NOTES
'B' R	JSPENDED LED LINEAR; 3.1"H x 2.6"W x 48.3"L NOMINAL DIMENSIONS ECESSED LED TROFFER LUMINAIRE; 23.6875W x 23.6875L x 4.6875H NOMINAL	STEEL DIE FORMED	CURVED ACRYLIC MESOOPTICS	SUSPENDED RECESSED	WHITE	DAMP DAMP	INTEGRAL INTEGRAL	DALI-2; 1% DALI-2; 1%	3400 5000	3500K 90 2700K- 90	100,000 (L70) 102,000 (L70)		31.0 44.0	277 277	CREE/LS SERIES; LS-4-40L-935-4-UL-AWNS W/ AC-144-Q14B-LP LEDALITE/ARCFORM DUO; AF-22-D1-ST-L-9T2-50-Q-1-D-S-N
'C5' R	MENSIONS ECESSED LINEAR LED LUMINAIRE; 4'-11.8125"L x 2.375"W x 3.5625"H NOMINAL MENSIONS	STEEL EXTRUDED ALUMINUM	ACRYLIC	RECESSED	WHITE	DAMP	INTEGRAL	DALI-2; 1%	2660	6500K 2700K- 90+ 6500K	60,000 (L70)	66	40.5	277	SELUX/M60; L60-1A32-TW-LW-SG-TB-05-WH-UNV-DMW-EC
C6' R	ECESSED LINEAR LED LUMINAIRE; 5'-11.875"L x 2.375"W x 3.5625"H NOMINAL MENSIONS	EXTRUDED ALUMINUM	ACRYLIC	RECESSED	WHITE	DAMP	INTEGRAL	DALI-2; 1%	3192	2700K- 90+ 6500K	60,000 (L70)	66	48.6	277	SELUX/M60; L60-1A32-TW-LW-SG-TB-06-WH-UNV-DMW-EC
	ECESSED LINEAR LED LUMINAIRE; 6'-11.875"L x 2.375"W x 3.5625"H NOMINAL MENSIONS	EXTRUDED ALUMINUM	ACRYLIC	RECESSED	WHITE	DAMP	INTEGRAL	DALI-2; 1%	3724	2700K- 6500K	60,000 (L70)	66	56.7	277	SELUX/M60; L60-1A32-TW-LW-SG-TB-07-WH-UNV-DMW-EC
	ECESSED LINEAR LED LUMINAIRE; 7'-11.8125"L x 2.375"W x 3.5625"H NOMINAL MENSIONS	EXTRUDED ALUMINUM	ACRYLIC	RECESSED	WHITE	DAMP	INTEGRAL	DALI-2; 1%	4256	2700K- 6500K	60,000 (L70)	66	64.8	277	SELUX/M60; L60-1A32-TW-LW-SG-TB-08-WH-UNV-DMW-EC
	ECESSED LINEAR LED LUMINAIRE; 11'-11.875"L x 2.375"W x 3.5625"H NOMINAL MENSIONS	EXTRUDED ALUMINUM	ACRYLIC	RECESSED	WHITE	DAMP	INTEGRAL	DALI-2; 1%	6384	2700K- 6500K	60,000 (L70)	66	97.2	277	SELUX/M60; L60-1A32-TW-LW-SG-TB-12-WH-UNV-DMW-EC
D	ECESSED LINEAR LED LUMINAIRE; 23'-11.875"L x 2.375"W x 3.5625"H NOMINAL MENSIONS	EXTRUDED ALUMINUM	ACRYLIC	RECESSED	WHITE	DAMP	INTEGRAL	DALI-2; 1%	12768	2700K- 90+ 6500K	60,000 (L70)	66	94.4	277	SELUX/M60; L60-1A32-TW-LW-SG-TB-24-WH-UNV-DMW-EC
N	JSPENDED DIRECT LED LINEAR LUMINAIRE; 27'-11.4375"L x 2.375"W x 3.5625"H DMINAL DIMENSIONS	EXTRUDED ALUMINUM	ACRYLIC	SUSPENDED	WHITE	DAMP	INTEGRAL	DALI-2; 1%	14896	2700K- 90+ 6500K	60,000 (L70)		226.8		SELUX/M60; L60-1A32-TW-LW-C-28-WH-UNV-DMW-EC
	ECESSED LED DOWNLIGHT; 5.28" DIAMETER x 1.575H NOMINAL DIMENSIONS	DIE CAST ALUMINUM	FIXED THERMOPLASTIC	RECESSED		IP20	INTEGRAL	DALI-2	<varies></varies>	<varies <varies<="" td=""><td></td><td></td><td>26.8</td><td></td><td>IGUZZINI/BLADE R; QW49-01</td></varies>			26.8		IGUZZINI/BLADE R; QW49-01
SI	JSPENDED LED GLOBE; 11.875"DIAMETER NOMINAL DIMENSION itable for both commercial and residential applications.	MACHINED ALUMINUM	FROSTED ACRYLIC	SUSPENDED	WHITE	DAMP	INTEGRAL	0-10V	978	3500K 80	50,000 (L80)		12.4		SISTEMALUX/BOLLA; 1933-835-UNV-01-D10
	ECESSED LED DOWNLIGHT; 3.75" DIAMETER x 4.125H NOMINAL DIMENSIONS	DIE CAST ALUMINUM	60 DEGREE REFLECTOR	RECESSED	WHITE	IP54	INTEGRAL	DALI; 1%	1000	3500K 90+	225,000 (L70)		12.0	277	LUMENCORE/NANO; LCRN-EZ-A-FD-277-R-L10-35K-90-W-SDALI1-SB-MWH-RD-MWH-NC-1-WET-NA
	ALL MOUNTED LED LUMINAIRE; 11.875"L x 2.5"W x 4.375H	DIE CAST ALUMINUM	CRYSTAL GLASS	SURFACE WALL MOUNTED	WHITE	DAMP	INTEGRAL	0-10V	893	3500K 90			15.7		BEGA; 12 278.1-K35
D	ECESSED LINEAR LED LUMINAIRE; 17'-11.875"L x 2.375"W x 3.5625"H NOMINAL MENSIONS	EXTRUDED ALUMINUM	ACRYLIC	RECESSED		DAMP	INTEGRAL	DALI-2; 1%		2700K- 90+ 6500K	60,000 (L70)		45.8		SELUX/M60; L60-1A32-TW-LW-SF2-18-WH-UNV-DMW-EC
D	ECESSED LINEAR LED LUMINAIRE; 23'-11.875"L x 2.375"W x 3.5625"H NOMINAL MENSIONS	EXTRUDED ALUMINUM	ACRYLIC	RECESSED		DAMP	INTEGRAL	DALI-2; 1%	12768	2700K- 90+ 6500K	60,000 (L70)		94.4		SELUX/M60; L60-1A32-TW-LW-SF2-24-WH-UNV-DMW-EC
D	ECESSED LINEAR LED LUMINAIRE; 31'-11.875"L x 2.375"W x 3.5625"H NOMINAL MENSIONS	EXTRUDED ALUMINUM	ACRYLIC	RECESSED		DAMP	INTEGRAL	DALI-2; 1%		2700K- 90+ 6500K	60,000 (L70)		259.2		SELUX/M60; L60-1A32-TW-LW-SF2-32-WH-UNV-DMW-EC
	AIL MOUNT INDIRECT LED LUMINAIRE; 18"W x 24"L x 4"H NOMINAL DIMENSIONS	ALUMINUM	ACRYLIC	SUSPENDED ALUMINUM RAILS			INTEGRAL	0-10V	51061	3500K 80	72,000 (L90)		133.0		SPI LIGHTING/LIGHTRUSS LED GEN 2; LRU12239-L433W-120-277V-3500K-DF_80-DIM10-DF_DA-NAT-PT51 PROVIDE WITH 18" RAIL SYSTEM
	JRFACE LINEAR LED LUMINAIRE; 0.26"H x 0.66"W x 13'L NOMINAL DIMENSIONS	EXTRUDED ALUMINUM	FROSTED HARD RESIN	SURFACE	ALUMINUM			NONE	7267	3000K 90	50,000		57.2		LUMINII SENSO/KATANA IP; 455-815-FH-175-30-B36-13'-902-096-STD-277 W/ 555-815-20
	JRFACE LINEAR LED LUMINAIRE; 0.26"H x 0.66"W x 31'L NOMINAL DIMENSIONS	EXTRUDED ALUMINUM	FROSTED HARD RESIN	SURFACE	ALUMINUM		REMOTE	NONE	17329	3000K 90	50,000		36.4	277	LUMINII SENSO/KATANA IP; 455-815-FH-175-30-B36-31'-902-096-STD-277 W/ 555-815-20
	JRFACE LINEAR LED LUMINAIRE; 0.26"H x 0.66"W x 75'L NOMINAL DIMENSIONS	EXTRUDED ALUMINUM	FROSTED HARD RESIN	SURFACE	ALUMINUM		REMOTE	NONE	41925	3000K 90	50,000		330.0	277	LUMINII SENSO/KATANA IP; 455-815-FH-175-30-B36-75'-902-096-STD-277 W/ 555-815-20
	JRFACE LINEAR LED LUMINAIRE; 0.26"H x 0.66"W x 82'L NOMINAL DIMENSIONS	EXTRUDED ALUMINUM	FROSTED HARD RESIN	SURFACE WALL MOUNTED	ANTHRACIT		REMOTE REMOTE	NONE	45838	3000K 90	50,000		13.5		LUMINII SENSO/KATANA IP; 455-815-FH-175-30-B36-82'-902-096-STD-277 W/ 555-815-20 SISTEMALLIX/I OOK WALL: \$7301 W DE LINV 24 D10 4448 0024 150 LINV D10
D	TE/AREA WALL MOUNTED LED LUMINAIRE; 8.625"L x 3.125"W x 1.25"H NOMINAL MENSIONS TE/BECESSED LED DOWNLIGHT: 10.125" DIAMETER x 8.5"H NOMINAL	DIE CAST ALUMINUM DIE CAST	TOUGHENED GLASS TEMPERED GLASS	SURFACE WALL MOUNTED RECESSED	ANTHRACIT E GRAY STAINLESS		INTEGRAL	0-10V 0-10V	<varies></varies>	<pre><varies <varies=""></varies></pre>	<pre><varies> 50,000</varies></pre>		13.5		SISTEMALUX/LOOK WALL; S7201-W-DF-UNV-24-D10-4448-0024-150-UNV-D10 SISTEMALUX/ZIP COMFORT; MEGAZIP
D	TE/RECESSED LED DOWNLIGHT; 10.125" DIAMETER x 8.5"H NOMINAL MENSIONS TE/ABEA DOUBLE HEADED BOLE MOUNTED LED LUMINABE: 18.5"W x 24.2"L x	ALUMINUM	COMFORT OPTICS	POLE MOUNTED TO 14'-6" TALL ROUND	STEEL						,		33.5		COMFORT: MEGAZIP COMFORT-ROUND-930-FLOOD-UNV-19-D10 GARDCO/PUREFORM:
	TE/AREA DOUBLE HEADED POLE MOUNTED LED LUMINAIRE; 18.5"W x 24.2"L x 2"H NOMINAL DIMENSIONS	DIE CAST ALUMINUM	COMPORT OPTICS	STEEL POLE; POLE TO WITHSTAND 100 MPH WINDS WITH GUST FACTOR OF 1.3		IP66	INTEGRAL	30% MEDIAN	22002	3000K 80	100,000 (L70)	163	82.0		P20-C-A06-830-T4-NONE-AR1-UNV-DALI-CM30-NONE-MG, POLE SRA-CA-4-125-14'-6"-D1-DT5-MG
	TE/AREA SINGLE HEADED POLE MOUNTED LED LUMINAIRE; 18.5"W x 24.2"L x 2"H NOMINAL DIMENSIONS	DIE CAST ALUMINUM	COMFORT OPTICS	POLE MOUNTED TO 14'-6" TALL ROUND STEEL POLE; POLE TO WITHSTAND 100 MPH WINDS WITH GUST FACTOR OF 1.3		IP66	INTEGRAL	30% MEDIAN	11291	3000K 80	100,000 (L70)	163	82.0		GARDCO/PUREFORM; P20-C-A06-830-T4-NONE-AR1-UNV-DALI-CM30-NONE-MG, POLE SRA-CA-4-125-14'-6"-D1-DT5-MG
F' S	TE/BOLLARD LED; 9.4" DIAMETER x 36"H NOMINAL DIMENSIONS	DIE CAST ALUMINUM		36" SURFACE MOUNTED BOLLARD	MEDIUM GRAY	IP65	INTEGRAL	30% MEDIAN	2268	3000K 80	100,000 (L70)	103	22.0		GARDCO/PUREFORM; PBL-36-14L-450-WW-G2-3-UNV-CM30-IMRI-PCB-MDY
	TE/AREA WALL MOUNTED LED LUMINAIRE; 18"L x 8"W x 9"H NOMINAL MENSIONS	DIE CAST ALUMINUM	ACRYLIC	SURFACE WALL MOUNTED	BLACK	IP66	INTEGRAL	0-10V	9250	3000K 80	100,000 (L92)	130	71.0	277	LITHONIA WDGE3; WDGE3-P3-30K-80CRI-MVOLT-SRM-DBLXD
	TE/AREA POLE MOUNTED LUMINAIRE; SINGLE HEAD; P30 LED; TYPE 3 STRIBUTION; 1'-5.25"W x 3'-4.375" NOMINAL DIMENSIONS	ACRYLIC/CAST ALUMINUM	ACRYLIC	POLE MOUNTED TO 14' FLUTED DECORATIVE POLE	BLACK	IP55	INTEGRAL	N/A	8852	3000K 70	100,000 (L83)	145	61.0	277	HOLOPHANE; AWDE3-P30-30K-MVOLT-SPL-AL3-BK-ST-TBK
' E	KIT SIGN	ALUMINUM ALLOY	RED LENS	REFER TO ARCHITECTURAL DRAWINGS FOR MOUNTING CONDITIONS	WHITE	UL DAMP	INTEGRAL	N/A					3.0	277	ISOLITE; LPDC-AC-R-1-WH-WH-MTEB
W' E	KIT SIGN WET LOCATION	POLYCARBONATE	RED LENS	REFER TO ARCHITECTURAL DRAWINGS FOR MOUNTING CONDITIONS	WHITE	WET	INTEGRAL	N/A					3.0	277	ISOLITE; RWL-EM-R-1-WH-MTEB-SD

NOTES

- THIS LUMINAIRE SCHEDULE IS NOT COMPLETE WITHOUT A COPY OF THE PROJECT MANUAL CONTAINING THE ELECTRICAL SPECIFICATIONS.
- 2 DIMMING CONTROL PROTOCOL (0-10VDC, LINE VOLTAGE, DALI, ETC.) COMPATIBLE WITH LIGHTING CONTROL SYSTEM AS SPECIFIED AND SHOWN ON DRAWINGS.
- PROVIDE +/- 12 INCH ADJUSTABILITY IN AIRCRAFT CABLE LENGTH WHERE USED.
- 4 COORDINATE ALL CEILING TYPES WITH LUMINAIRE LOCATIONS PRIOR TO ORDERING LUMINAIRES. COORDINATE INSTALLATION WITH REFLECTED CEILING PLAN.
- SPECIFIED MANUFACTURERS ARE BASIS OF DESIGN. SUBMIT ALTERNATES FOR APPROVAL PRIOR TO BID CLOSE.
- PROVIDE SUBMITTALS THAT INCLUDE THE LUMINAIRE, LAMP AND DRIVER INFORMATION OF EACH LUMINAIRE, WITH APPLICABLE OPTIONS CLEARLY CHECKED OR HIGHLIGHTED. SUBMITTALS NOT INCLUDING THIS INFORMATION WILL BE RETURNED AS REJECTED BY THE ENGINEER OF RECORD.
- 7 REMOTE BALLASTS/DRIVERS: UL LISTED FOR THEIR APPLICATION. BALLASTS/DRIVERS MARKED AS UL RECOGNIZED COMPONENT BUT NOT UL LISTED ARE SUBJECT TO REMOVAL AND REPLACEMENT AT NO COST TO OWNER.
- 8 LABEL ALL REMOTE DRIVERS TO SHOW LUMINAIRE TYPE IDENTIFICATION AND SOURCE CIRCUIT. PROVIDE WIRING BETWEEN REMOTE DRIVER AND LUMINAIRE AS RECOMMENDED BY MANUFACTURER. DO NOT EXCEED MAXIMUM DISTANCE RECOMMENDED BY MANUFACTURER BETWEEN DRIVER AND FURTHEST LUMINAIRE.



Opsis Architecture LLP 975 SE Main St, Portland, OR 97214 503.525.9511 | info@opsisarch.com opsisarch.com



Project Owner:

City Of Woodburn Oregon

Project Name:
Woodburn Community
Center

Project Adress:
190 Oak Street
Woodburn, OR 97071

INTERFACE ENGINEERING

PROJECT 2019-0359 CONTACT Cody Bargholz 100 SW Main Street, Suite 1600 Portland, OR 97204 TEL 503.382.2266 www.interfaceengineering.com

RAWINGS ARE THE PROPERTY OF OPS

THESE DRAWINGS ARE THE PROPERTY OF OPSIS ARCHITECTURE LLP AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER, WITHOUT PRIOR WRITTEN PERMISSION.

Revisions to Sheet

No. Revision Date

Status: PLANNING COMMISSION DESIGN REVIEW

10.28.2025

Date:

Sheet Title

LUMINAIRE

SCHEDULE
ELECTRICAL

E0.02

Job No.

GENERAL SHEET NOTES

- A. COORDINATE INSTALLATION OF ALL UNDERGROUND FEEDERS TO MAINTAIN MINIMUM CLEARANCES OF 6' FROM GAS LINES THAT RUN BESIDE FEEDERS AND 1' FROM GAS LINES THAT CROSS UNDERGROUND FEEDERS. ALSO MAINTAIN 10' FROM SAINTARY, STORM AND WATER LINES THAT RUN PARALLEL TO UNDERGROUND
- B. NO WIRE SMALLER THAN NO. 10 AWG SHALL BE USED AS BRANCH CIRCUIT WIRING OF EXTERIOR LIGHTING. USE NO. 10 AWG FOR RUNS UP TO 300'. USE NO. 8 AWG FOR RUNS UP TO 450'. USE NO. 6 AWG FOR RUNS UP TO 750'. USE NO. 4 AWG FOR RUNS UP TO 1200'. SIZE CONDUIT AS PER NEC STANDARDS.
- C. CONDUIT RUNS ARE SHOWN FOR DIAGRAMMATIC PURPOSES ONLY. CONFIRM AND COORDINATE FINAL LOCATIONS ON-SITE PRIOR TO ROUGH-IN. UNLESS OTHERWISE NOTED CONDUIT MUST BE RIGID PVC.
- D. THE INSTALLATION OF POLE BASES MUST BE COORDINATED ON SITE WITH ARCHITECTURAL AND CIVIL TRADES.
- E. ALL STREET LIGHTING TO COMPLY TO PGE STANDARDS AND SPECIFICATIONS; ADDITIONALLY ILLUMINATION TO COMPLY TO ENGINEERING SOCIETY (IES) OF NORTH AMERICA RECOMMENDED PRACTICE 8, ROADWAY LIGHTING (RP-8) AND INSTALL LIGHTING TO MEET STANDARD OF 3.02.03A.

○ SHEET KEYNOTES

EXISTING STREET LIGHT TO REMAIN

OAK STREET

- TENNIS COURTS LIGHTING · IS EXISTING TO REMAIN

(X) POWER POLE

EXISTING STREET

OVERHEAD LINES TO_

- EV CHARGER

1 1 1

OVERHEAD LINES TO BE DEMOLISHED

1. FOR LUMINAIRE TYPE SS PROVIDE PGE APPROVED LUMINAIRE HOLOPHANE AWDE3, SEE LUMINAIRE SCHEDULE FOR EXACT SPECIFICATION. CONTRACTOR TO PROVIDE CONDUIT ROUGH-IN. POLE BASE, POLE INSTALLATION ONLY, POLE MOUNTED LUMINAIRE AND BRANCH CIRCUIT WIRING ARE SUPPLIED AND INSTALLED BY PGE. PRE-CAST POLE BASES ARE SUPPLIED BY PGE AND INSTALLED BY THE CONTRACTOR. COORDINATE REQUIREMENTS WITH PGE. PGE WORK ORDER NUMBER IS M5896508.


Opsis Architecture LLP 975 SE Main St, Portland, OR 97214 503.525.9511 | info@opsisarch.com opsisarch.com



Project Owner: City Of Woodburn Oregon

Woodburn Community Center

Project Adress: 190 Oak Street Woodburn, OR 97071



INTERFACE ENGINEERING

PROJECT 2019-0359 CONTACT Cody Bargholz 100 SW Main Street, Suite 1600 Portland, OR 97204 TEL 503.382.2266 www.interfaceengineering.com

THESE DRAWINGS ARE THE PROPERTY OF OPSIS ARCHITECTURE LLP AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER, WITHOUT PRIOR WRITTEN PERMISSION. Revisions to Sheet

Status: PLANNING COMMISSION DESIGN REVIEW

10.28.2025

Sheet Title SITE PLAN -**ELECTRICAL**

2 LUMINAIRE TYPE SS POLE BASE DETAIL

GROUND ROD WITH #6 SOLID CU WIRE MUST BE INSTALLED

AT LEAST 2" BELOW FINAL GRADE IN UNDISTURBED SOIL.

PER NESC 21 5C

NO SCALE

E1.00

4773-01

SITE PLAN - ELECTRICAL

____GENERATOR —

OAK STREET

(E) POWER POLE -

MAIN DISTRIBUTION — SWITCHBOARD 'MDS'

(N) UTILITY VAULT —

(N) UTILITY TRANSFORMER

1" = 20'-0"



Opsis Architecture LLP 975 SE Main St, Portland, OR 97214 503.525.9511 | info@opsisarch.com



City Of Woodburn Oregor

Woodburn Community

INTERFACE ENGINEERING

CONTACT Cody Bargholz 100 SW Main Street, Suite 1600 Portland, OR 97204 TEL 503.382.2266 www.interfaceengineering.com

THESE DRAWINGS ARE THE PROPERTY OF OPSIS ARCHITECTURE LLP AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER, Revisions to Sheet

Status: PLANNING COMMISSION **DESIGN REVIEW**

10.28.2025

SITE PLAN -**PHOTOMETRICS**

EG1.00