PUBLIC WORKS DEPARTMENT

Engineering Division -CITY OF WOODBURN 190 Garfield Street Woodburn, OR 97071 FAX: 503.982.5242

ADDENDUM

Addendum No.:3Project Name:New Production Well for Parr Road Treatment PlantProject No.2018-011-28Date:June 3, 2022To:All Bidders

<u>NOTE:</u> This Addendum forms part of the Contract Documents and modifies the specifications and drawings under Bid No. 2022-09, as noted below. Bidders submitting an offer must sign this form, acknowledging receipt of addendum, and supply it with their proposal. Failure to do so will subject the Bidder to disqualification.

CLARIFICATIONS:

- Non-US manufactured valves, pipe, fittings, etc. are approved for this project.
- The landscape plant establishment/maintenance period shall be one-year.
- The fiber optic conduit (N1) terminates at Well 12, resulting in a trench length of 1550 LF.
- Ductile iron pipe and fittings shall be asphaltic exterior coated.

REVISIONS TO FRONT END SPECIFICATIONS:

- Remove the words "zinc-coated" from Item No. 11 of the Bid Form included in Section 05 – Form of Proposal.

REVISIONS TO TECHNICAL SPECIFICATIONS:

- Remove the words "zinc coated", from Section 01 22 20, Part 1.12
- Replace Section 43 21 52 Part 1.2 G, except for the number, with the following:
 - G. Unit Responsibility for the supply and installation of equipment specified in this section shall be assigned to the pump supplier. Certificate of Unit Responsibility shall be provided.
- Add the following to Section 43 21 52 Part 1.2:
 - H. Well casing and discharge head installation work will be by a licensed water well constructor per ORS 537.747
- Add the following to Section 33 11 10, Part 2.1.B.6.d.4:
 - b) "Fast Grip", American Cast Iron Company.

c) "Field-Lok", United States Pipe and Foundry Company.

REVISIONS TO DRAWINGS:

- Remove and replace Note no. 2, on sheet L-2, under "Plant Maintenance Notes", with the following:
 - 2. CONTRACTOR SHALL PROVIDE **1** YEAR PLANT ESTABLISHMENT PERIOD TO MAINTAIN PLANTS IN A VIGOROUS GROWING CONDITION THROUGH PERIODIC INSPECTIONS. DURING PLANT ESTABLISHMENT PERIOD, THE CONTRACTOR SHALL ENSURE PLANTING AREAS ARE FREE OF INVASIVE WEEDS AND PLANTS SHALL BE FREE OF INSECTS AND DISEASES WHILE SHOWING SIGNS OF CONTINUING HEALTH. THE CONTRACTOR SHALL REPLACE ALL PLANTS THAT SHOW UNHEALTHY SIGNS OR ARE DEAD.
- Remove and replace Note no. 4, on sheet L-2, under "Plant Maintenance Notes", with the following:
 - 4. OTHER MAINTENANCE OPERATIONS DURING THE **ONE**-YEAR GUARANTEE PERIOD:
 - RESET PLANTS TO FINISH GRADE AND RESTORATION OF PLANT SAUCERS, AS NECESSARY
 - · REPAIR DAMAGED OR WASHED OUT EROSION CONTROL SEEDING.
 - · PRUNING, INCLUDING REMOVAL OF DEAD OR BROKEN BRANCHES.
 - · DISEASE CONTROL.
 - · MAINTAINING WRAPPING, GUYS, [TURNBUCKLES,] AND STAKES. [ADJUST TURNBUCKLES TO KEEP GUY WIRES TIGHT.] REPAIR OR REPLACE ACCESSORIES WHEN REQUIRED.
 - · REPORT ANY PROBLEMS THAT MAY BE A HINDRANCE TO COMPLETING AND FULFILLING THE CONDITIONS
- Add the attached "Soakage Trench" detail to sheet C-16

ATTACHMENTS:

- Soakage Trench Detail

I have received, read and incorporated changes, per this addendum, in my proposed bid:	
Signature	Date



